



AUGUST 1914

AMERICAN CARPENTER AND BUILDER



THE WORLD'S GREATEST BUILDING PAPER



BUILDER TYPES

Picturing certain important groups of "Our Readers"

③ THE JOURNEYMAN CARPENTER

NINE times out of ten he is the builder with a future before him. He is the timber from which Contractors, Builders and Architects are made. A skillful, studious man—observing, responsible, ambitious. In building circles he is recognized as the "brains of the job"; and his all around training best fits him for advancement in the building world. We are proud of our Carpenter readers. We recommend them to all business men. Gain their loyalty at the beginning of their building career and they will stay with you always.

Price 20 Cents

4,000
Blows per
Minute

Do Your Drilling, Chipping, Caulking, or Surfacing with an ELECTRIC HAMMER

or the Manually Operated

Drilhammer

If you have a lot of work to do, the solution of the problem for you is our **Electric Hammer**. If you have but a small amount of work to do at any one time, the **Drilhammer** is the thing to use. In either case you can do the work **ten times as fast**.

Our Drilhammer

does the work in one minute that takes ten times as long by cruder methods. Strikes 1,000 powerful hammer blows per minute. Operator simply turns the crank.

Centrifugal force does the work. Hardened tool steel hammer elements revolving at high speed strike the blows.

Exceedingly simple in construction. Has no springs to weaken or wear out. Makes an immense saving in the cost of drilling concrete, brick, stone, tile, conduit, walls, floors, ceilings, etc.

Made in two sizes and accommodates drills from $\frac{1}{4}$ in. to $1\frac{1}{4}$ in. Can be carried in regular tool kit. Sold at a price that will enable every mechanic to have one. Write for circular 132 and prices.

This ELECTRIC HAMMER

is practically automatic;—i.e. the same pressure that holds the tool against the work closes the switch in the handle and starts operation. Delivers four thousand blows a minute. Built for various voltages. Requires only one or two amperes on 110-volt circuit. Circular A-13 describes it.

For use on direct current, or can be used on alternating current by using a motor generator set.

Send for the Circulars illustrating and describing these hammers. The price at which they are sold make it desirable that you should own one immediately.

ORR & LOCKETT

Established 1872 **HARDWARE CO.**


Main Office, 14-16 W. Randolph St., Chicago

Branch Offices { 401 Broome St., New York
Room 608-79 Milk St., Boston


Ceiling
Work
Made
Easy

No
Exertion

WHEN WRITING ADVERTISERS PLEASE MENTION THE AMERICAN CARPENTER AND BUILDER



Complete Set of
Attachments
FREE



An Eveready Saw Rig Saves the Wages of Six Men

NEW LIST OF AGENCIES

CHICAGO, ILL.—Oshkosh Mfg. Company, 1440 Monadnock Bldg.
ATLANTA, GA.—Oshkosh Mfg. Company, Southern Sales Office, 604 Walton Bldg.
CINCINNATI, O.—K. & H. Contractors' Mach'y & Supply Co., 1128 Gilbert Ave.
DENVER, COLO.—Geo. W. Summers & Company, 355 Railway Exchange.
EVANSVILLE, IND.—Indiana Builders' Supply Co., Furniture Exchange Bldg.
MILWAUKEE, WIS.—Badger-Packard Mach'y Co., 74 West Water St.
NEW ORLEANS, LA.—Henry J. Maloches, 802 Perrin Bldg.
OMAHA, NEBR.—Sunderland Mach'y. & Supply Company.
PORTLAND, ORE.—G. A. Saunders Supply Co., Bldgs. Exchange, 2nd and Alder Sts.
RICHMOND, VA.—I. Bluford & Company, 1338 East Cary St.
SALT LAKE CITY, UTAH—F. C. Richmond Mach'y Co., 117 West Second South St.
SAN FRANCISCO, CAL.—J. E. Dwan & Co., 445 Turk St.
LOS ANGELES, CAL.—J. E. Dwan & Co., 1835 South Main St.
SAN DIEGO, CAL.—J. E. Dwan & Co., 250 Fifth St.
PHOENIX, ARIZ.—J. E. Dwan & Co., Creighton Bldg.
SEATTLE, WASH.—Harold G. Stern & Company, 524 First Ave. South.
ST. LOUIS, MO.—C. O. Fischer & Company, 712 International Life Bldg.
KANSAS CITY, MO.—King Supply & Equipment Co., 1201 Scarrist Bldg.
PITTSBURGH, PA.—Patterson Bros., 421 Wood St.
BIRMINGHAM, ALA.—Chadwick & Company, 510 Empire Bldg.
ST. PAUL, MINN.—Daily-Fraser Hdwe. Company, 417 Cedar St.
CHARLESTON, ON—KANAWHA, WEST VA.—O. A. & H. G. Thayer Company.
MONTREAL, QUE.—The Canada Mach'y Agency, 298 St. James St.
WINNIPEG, MAN.—John H. Alexander, 604 Builders' Exchange Bldg.
VANCOUVER, B. C.—Dominion Dock & Supply Co., 304 Northwest Trust Bldg.

MIXERS AND PUMPS EXCLUSIVELY.
NEW YORK, N. Y.—John J. Duggan, Room 1652, 50 Church St.

Oshkosh Mixer

It will pay any contractor to get acquainted with the OSHKOSH MIXER. Request brings full information. Write us today for prices and Special Offer. The Mixer with the Effective 4-Way Mix. Also built for steam or electric power.



Ask for the Bore and Stroke of the Engine

Whether a Portable Saw Rig will *pay* you or not, depends largely on the *Engine*. It requires *power* for a machine to turn out the work of from 4 to 6 men and soon return its *full cost*. Some makers of Saw Rigs *claim* all kind of power for their machines. We state the facts—bore, 4¾ inches—stroke, 6 inches. More than that, we guarantee our Engines will develop over 4 actual brake horse power. Now for some tangible

Proof of What the Eveready Portable Saw Rig Has Done

Note we did not say *will do*. One contractor who formerly bought factory-made window frames, now makes all his own frames with our machine, at 30% less cost and secures even better frames. Another, a building contracting concern, used our machine in building a church and it saved them enough the first season on that *one* contract alone to almost pay for the Saw Rig.

Our Eveready Saw Rig is not a frail, weak machine like some are, but built heavy and strong enough for any service. It is also constructed so that it is easy to *move* from one job to another. Also, so *simple*—anyone can operate it. Besides doing cross-cutting and rip-sawing, it joints, sands, jig saws, grooves, bores, miters, and grinds tools. All attachments complete come with it—*no extras* to buy. Send for our Catalog, which gives complete details and contains a long list of letters from well known users.

Live Agents Wanted in Open Territory

OSHKOSH MFG. COMPANY

316 South Main Street

Oshkosh, Wisconsin

FOR SURFACING AND POLISHING HARDWOOD FLOORS

The American Floor Surfacing Machine

IS NO EXPERIMENT. Its work since 1903 has established a standard for finely surfaced and polished floors. It is the only machine whose work is specified by leading architects and used in the best government buildings and will surface and polish any kind of a floor from common pine to finest parquet.

IT IS THE ORIGINAL and only two-roll, self-propelled, dust-collecting machine, that surfaces close to the wall and can be used in small rooms. Anyone can operate it.

ITS WORK IS RAPID, regular, smooth and even, because the power that drives the rolls also propels the machine at the same ratio of speed. It has surfaced and polished millions of square feet of the best floors in America and Europe.

GET A MACHINE that does first-class work and in paying quantities, that is fully guaranteed and sold on its merits. Don't be fooled with an imitation.


We sell direct to the users. Write for our free book "Surfacing Floors as a Business."

Use Our Champion Double Disc Machine for Cement, Terrazzo and Marble Floors.

Manufactured by **The American Floor Surfacing Machine Co., Toledo, O.**

**THE AUTOMATIC BALL BEARING ELECTRIC FLOOR SURFACING MACHINE**

Contractors and builders find, dresses in paying quantities, quarter-sawn oak, etc., the way they want it or rapidly refinishes old floors. Having ballbearings, roller and dust-suction fans spin true and easy: yielding arms give flexible or rigid roller as needed: self-propelling with automatic control (as shown) gauges roller cut for even work and brakes forward pull for large capacity—you simply guide. Surfaces to base baseboard with Edge Roller. No hand scraping



Patented Oct. 15, 1912.
Machines sold outright for use anywhere.

Booklet tells all about it and our **FREE TRIAL OFFER.**

Made in several sizes for small rooms or large areas.

WAYVELL CHAPPELL & CO.
Dept. D, 4847 E. Ravenswood Ave.
CHICAGO, ILL.

You May Pay
a higher Price
but you can't
get a better Floor
Scraper than the
Fox. *It's a dandy.*
Fox Supply Co.

Dept. A
Brooklyn, Wis.



Complete
Scraping
Outfit
Only
\$25

**ROOF FRAMING
MADE EASY**

By the use of
our little book

It's Free

Send today for one of these
and learn how to get the
lengths and cuts of all rafters
for seventeen different
pitches of roof. We stamp

this rule on our squares, making it handy and convenient.




We Manufacture the Only Practical Take-Down Square

NICHOLLS MFG. CO.

OTTUMWA, IOWA

The Quick Clamp
is a new

**HARGRAVE
CLAMP**



Like all **HARGRAVE** tools, it will save you money.

Have you our catalog?

THE CINCINNATI TOOL CO.

Dept. H, Norwood, Cincinnati, Ohio



IMPERVITE is Guaranteed to Waterproof Walls: Cellars & Pits.

A facing of IMPERVITE MORTAR on the inside will resist water on the outside.

ASK FOR BOOK No. 62 **The Standard Paint Co.** NEW YORK BOSTON CHICAGO

Houses, Flats and Apartments

Buy a Plan Book of Flat Buildings and plan an income in

your old age. Our book gives you ideas from two-family flats to twelve families, and our prices are reasonable.

First edition (right off the press) 50c
Also a book for residences 25c
Both 65c

H. O. Cook & Company

722 Ashton Building

Grand Rapids, Mich.

WOOD



Made in three sizes:
8 x 18, 8 x 15 and 8 x 12 in. Flexible Roller.
Edge Roller easily adjusted to either side.

FREE TRIAL
5,000 in use


RAPID, FLEXIBLE, SELF-PROPELLING WHEN RAISING HANDLE

Send for our new list and free trial proposition.

M. L. Schlueter

107 N. Canal St.
Chicago, Ill.

MONITOR SASH LOCKS



(PATENTED)

NEVER BREAK

BECAUSE THEY ARE MADE OF VERY HEAVY GAUGE METAL AND PERFECTLY CONSTRUCTED.

If the upper plate drops, the Monitor "Never Break" Sash Lock will pick it up from a lower point than any other, adjust the sashes perfectly, prevent all vibration and lock securely, so it cannot be opened from the outside.

MADE IN TWO SIZES AND ALL FURNISHED BY

The Champion Safety Lock Co.
Geneva, Ohio

There are more Adjustable Floor Finishers

being sold today than all others combined

There's a reason

Ask me why

H. P. DIDRIKSEN

Anderson, Indiana




H. P. Didriksen
Anderson Ind.

Without obligating me in any way, you may send your printed matter, provided you accept this coupon as a partial payment, if I decide to buy for cash.

Name.....

Town..... State.....

THIS COUPON IS WORTH \$2.50



Makes Floor Scraping an Easy Job

The automatic action of the Acme Floor Scraper allows the operator to stand in an easy, upright position while working. No back-breaking positions to get into, and no lifting. Simplest and most effective floor-scraping machine on the market.

Let me prove this by having me send the complete

ACME FLOOR-SCRAPING OUTFIT

to you on a week's free trial basis at my expense.

Catalog and complete detailed information of my Free Trial Offer are yours for the asking.

JOSEPH MIOTKE, 247 Lake St., MILWAUKEE, WIS.

Carpenters and Builders Attention

You owe it to yourself, as well as to the property owner for whom you are working, to see that his buildings are adequately equipped with proper protection from loss by lightning.

His confidence in your judgment will make it easy for you to secure this additional work.



**THE BARNETT
SYSTEM OF**

Guaranteed Lightning Protection

is the easy way to more profits on the same job. Our rods are in big demand and there is a big profit in selling them. They are made of pure copper cable, with attractive fixtures that are easily put on any building.

Why not equip yourself to take advantage of the opportunities for this work which are continuously arising? Let us show you the way to more profits on the same job.

**FREE CABLE SAMPLES, PRICE
LIST AND CATALOG**

Jos. A. C. Barnett & Co.

WRITE FOR THEM TODAY

Riverside, Iowa



\$13.95


per doz. 4 footers

—if you send cash
with order.

Absolutely Safe; two of them will carry a ton, and they last a lifetime. Think of the time you save! One man alone can put them up and take them down easily and quickly.

No Side Swing if you purchase our new fixture at 60c extra per dozen brackets: these keep the brackets absolutely rigid.

Write for Catalog of Builders' Specialties!



About clamps—the sliding jaw on each of ours can be moved in an instant **DIRECTLY AGAINST** the work operated on, so that half a turn of the fine specially threaded screw will apply the power.

Think of the time this saves!

The grip is positive, and special grade of steel in the bar more than doubles the strength of the clamp.

Our No. 10 catalogue shows some very interesting price reductions on four of the most wanted styles. It will pay you to write for it at once.

James L. Taylor Mfg. Co.

Poughkeepsie, N. Y., U. S. A.

C. E. JENNINGS & CO'S


71-73 MURRAY ST., N. Y., U. S. A.

TRADE MARK.

COMBINATION SET OF SAWS No. 131

This set of saws is just what you need. Takes up very little room in the kit and is less expensive than if you bought all the saws separately.

Each blade is fully backed by our guarantee both as to quality and workmanship. The saws are hand-forged from extra refined spring steel, hand filed and set. Warranted to hold edge and set for longest possible time and to run smoothly and easily.



An adjustable lever in the handle operates the screw that holds the blade. Blades may be removed from the handle instantly and another blade substituted. Blade is held firmly and evenly.

Combination Set No. 131 consists of:

- 1—Garland Adjustable Handle
- 1—18-inch Hand or Panel Saw
- 1—18-inch Rip Saw
- 1—16-inch Double Edge Pruning Saw
- 1—15-inch Hack Saw
- 1—14-inch Compass Saw
- 1—12-inch Keyhole Saw

A Waterproof Canvas Case for this set with seven pockets—one for each blade and one for the handle, will be furnished at a slight extra cost.

Ask your hardware dealer to show you Set No. 131. It is so handy and the price so reasonable that you'll like it. Write us for descriptive Circular.

The Multiplication Table Says

2X0=0 BUT 2X4=8

Every contractor is keen to get workmen who can "speed up". If a man drives two nails where another man drives one, other things

being equal, he earns twice as much for the boss.

Now machines are like men--only more so. A slow machine--say a hand floor scraper--uses up just as much of a good workman's time as an improved scraper and only does a fraction of the work. A machine that is not the very best that can be bought is a poor investment at any price.

Now a Weber Double Acting Floor Scraper makes two shavings grow where only one grew before. And it makes them grow in every nook of the floor of many corners, getting close to the baseboard everywhere.

It is the multiplication of small savings and small efficiencies that makes your profit. Probably you will call the saving made by a Weber Floor Scraper large after you have given it a trial. But whether small or large, it is amply worth while.


Here's what I'll do. Tell me you want a Weber Floor Scraper to test its profit multiplying feature. I'll send you one for a five-day free trial. If you don't like it send it back at my expense and we'll part friends.

John F. Weber, Pres.,

Weber Mfg. Co.

670 71st Ave., West Allis, Wis.

Get This Floor Scraper



The **WEBER** DOUBLE ACTING Floor Scraper

TRIPLE "A" the Adjustable Floorsmoothen

Here is a successful floorsmoothen. It is adjustable in weight, depth of cut and shear of cut. Surfaces and finishes flush with the baseboard.



The
MACHINE
that
makes
the
MONEY

With the TRIPLE "A" SPRING DRIVEN FLOOR-SMOOTHER an inexperienced man can easily make from \$12 to \$20 a day refinishing old, new, painted, varnished, oiled or gritty floors. It is the only hand power machine that has a spring motor. Just as good as a power machine. Costs much less.

WRITE FOR DESCRIPTION

and complete illustrated circulars. We will also send you interesting data on the earning power of the Triple "A." Figures based on actual work done. You can earn from \$12 to \$20 a day. Write us.

TRIPLE "A" MACHINE COMPANY
Room 323- 300 W. Grand Ave., CHICAGO, ILL.

Straight-grained cedar that cuts like cheese; smooth, tough leads that make clean-cut, strong marks—that's the way Dixon's Carpenter Pencils are described. Send 16c for generous sample lot 183J.

JOSEPH DIXON CRUCIBLE CO.

✂ JERSEY CITY, N. J. ✂

THE NEW SASGEN PORTABLE 1-TON STIFF LEGGED DERRICK

THE ONLY DERRICK OF ITS KIND
ON THE MARKET

Built Strong and Light of all Crucible Steel Fittings, including Double Drum Geared Winch. Can be used hand or power. Price very low, according to length of boom.



SASGEN
PEERLESS
STEEL
DERRICK
For hand
and power.
Full Circle
Swing,
1800 lbs.
capacity,
with self
Lubricating
Bushings.

SASGEN DERRICK CO.


2053 N. Racine Ave., Chicago.
Canadian Office, 1 Wabash Ave., Toronto

Price only \$45.00 complete ready for use, \$43.00 for hand power only. Write for Circular No. 2.

Satisfaction—Prompt Shipment Guaranteed.

A Good Elevator

Is a Good Investment
Saves Time and Labor



Our product includes *Dumb-Waiters, Carriage, Auto and Store Elevators* — Hand and Power.

These machines are serviceable and will pay for themselves in a very short time. Being practically self-contained, they can be erected by any carpenter or "handy man" in a few hours' time. Plans for erecting furnished with each elevator.

The Reasonable Cost Will Interest You

Write to us today stating your requirements, giving style of machine wanted, size of platform and number of feet travel and we will name you a money-saving price on equipment made to serve you well.

SIDNEY ELEVATOR MFG. WORKS, SIDNEY, OHIO

You Can't Afford to Install Inferior DUMBWAITERS!

Because there is not sufficient profit in them to make it worth while. And the annoyance and disgust they cause will hurt your reputation.

The BEST is none too good!

"THE SEDGWICK IS THE BEST."

Send for Catalogue L.

It is unique.

It will help you to get business.

It will help you to hold business.

It will solve your DUMBWAITER Problems.

Write for copy now.

SEDGWICK MACHINE WORKS

132 Liberty Street

NEW YORK CITY

WARNER ELEVATORS and DUMB-WAITERS

HAND POWER and ELECTRIC

SEND FOR CATALOGUE

The Warner Elevator Mfg. Co.
Cincinnati

New York

Indianapolis

Birmingham

Dayton

PHOENIX INSIDE SLIDING BLINDS

WILKES BARRE, PA.

The Phoenix Sliding Blind Co.

Enclosed find my check for blinds. I am pleased with them and sorry I did not have them put throughout the whole house.
C. W. BURT.

Comfort!

Economy!

Convenience! **PHOENIX SLIDING BLIND CO.**

BRIDGE & CANAL STS.

PHOENIX, N. Y.

The lately improved springs and corrugated steel rods put the "PHOENIX" far in lead of less improved styles. Write for Catalogue "C" and free samples, showing construction.

NO FALLING WINDOWS
SMASHING GLASS
POCKET FRAMES
SASH WEIGHTS
RATTLING
BINDING
CORDS with
**AUTOMATIC
SASH HOLDERS**



**SPECIFY
USE
DEMAND**

Automatic Sash Holders
and save labor, lumber and money.

Send for trial set (\$1 prepaid) stating approximate weight of sash, or our circular
Automatic Sash Holder Mfg. Co.
52 Church St., New York.



CARPENTERS WANTED AS AGENTS
During Fall and Winter Months. Big Money!
Ready Seller.

SANITARY AUTOMATIC DUMBWAITER

saves carrying food to and from the cellar. Perfectly ventilated; screened openings; finished inside with durable white enamel. Keeps food perfectly. Top lies flush with kitchen floor. You can walk over it. Operates with push button or lever. Also furnished as a Refrigerated Dumb Waiter. Write for Particulars and Price.
YORK AUTOMATIC DUMBWAITER WORKS
639 W. Market St. **YORK, PA.**



THE COLUMBIA

DUMB WAITERS ELEVATORS
CELLAR HOISTS
JUMPER DISAPPEARING DUMB WAITERS
CHAIN HOISTS, CRANES and TROLLEYS

SEND FOR CATALOGUE.

J. G. SPIEDEL, Reading, Pa.

STORM Dumbwaiters and Hand Elevators

No stock sizes. Built to fit the place. Ask your hardware dealer and write us for catalog. Let us send you our new Catalog with Discounts.

THE STORM MFG. CO.

Herman & Vesey Sts.

NEWARK, N. J.

The Master Mixer ↑ for the Master Builder

The selection of a Concrete Mixer demands only the same "horse sense" you use when you buy any other tool—you don't take chances on "unknowns" or imitations—you've cut your wisdom teeth.

You know that the original **LITTLE WONDER** opened to your profession a source of great profit by enabling you to quickly and easily do concrete work that previously had been awarded to others.

You've heard many good things about the **LITTLE WONDER "FIVE"**—possibly something like this, taken from the recent letter of a purchaser:


"I had two other mixers before buying the Little Wonder, and now I wish they were all LITTLE WONDERS."

We have thousands of similar letters on file.

LITTLE WONDER "FIVE"

With Side Loader and Automatic
Water-Measuring Tank

Capacity
WITH
Side Loader
5 Cubic feet
per batch—
70 to 100
cubic yards
per day



Capacity
WITHOUT
Side Loader
5 cubic feet
per batch—
35 to 50
cubic yards
per day

"The Mixer that Makes the Money"

Now, you've long wanted a mixer. You want the **master machine**. You want the one that the experience of many Master Builders shows pays the largest dividend on investment—the mixer of widest known efficiency, of greatest durability, of absolutely guaranteed satisfaction, or no sale, and one that will mix mortar.

The **LITTLE WONDER "FIVE"** with Side Loader, meets the requirements of any sized job and extracts the last cent of profit by its smooth, rapid work. Mixes one batch while the following is loaded. Loader takes barrows endwise or side-

wise on ground level—no inclines to climb, no staging to build. Drum is wide mouthed, no movable parts inside and easily cleaned. Mix visible, consistency easily regulated and neither slops nor clogs. Double drive bearings. One lever control. Work it with any crew you chance to have.

First-class gasoline engine runs the mixer for about 35 cents per day, and is detachable for other work. Only one sprocket chain. Frame and axles steel I-beam section. Steel wheels, wide tires, standard tread. Easily moved about or shipped.

TEN DAYS' FREE TRIAL, with or without Side Loader, and we pay the freight if you're not satisfied

WATERLOO CEMENT MACHINERY CORPORATION

103 VINTON STREET, WATERLOO, IOWA

NEW YORK
11 Broadway

PHILADELPHIA
The Bourse

CHICAGO
9 S. LaSalle St.

KANSAS CITY
Commerce Bldg.

MONTREAL
Corestine Bldg.

"A Mix A Minute"


At an Operating Cost of But
3 Cents per Hour

Entire batch, wet or dry, folded against itself and thoroughly kneaded $2\frac{1}{2}$ times with each drum revolution. 12 to 20 drum revolutions per minute.

Two wheelbarrows per batch.

DAILY CAPACITY up to 75 yds. with loader.

DAILY CAPACITY up to 50 yds. without loader.



Goes to Any Part of the Job on the "Double Quick"

No motley processions of "soldier" laborers to bring the job to the mixers. It's small enough to be placed almost any place on the work, and it's a mighty easy matter to "put it right where you want it."

Two "Big-an'-Little" Mixers on a big job means **you'll accomplish as much in one-third the time** and with less men and less expensive delays.

The "Big-an'-Little" with Side Loader

Time and money saved by increasing output.

Capacity one batch; loads while other batch is mixing, and operates by regular, quick-acting "Big-an'-Little" Hoist directly connected with engine.

Our Catalog, sent on request, will give you a lot of valuable ideas on the concrete mixing experience of men who have tried all sizes of Mixers.


Send for illustrated literature now.

THE JAEGER MACHINE COMPANY

318 W. Rich St.

COLUMBUS, OHIO

Blystone Batch Mixer For Plaster - Concrete - Mortar



A saving of \$25.00 per day was made in mixing hardwall plaster for the big Machinery Palace for the Panama Pacific Exposition.

The Cement Tile & Block Mfg. Co., of Osgood, Ohio, paid for their Blystone in three months work in their block plant.

One man slaked lime and made mortar for ten masons and had time to spare for other work on a job recently done by G. Ed Berry, of Harrisburg, Ills. Mr. Berry also says he got 10% more mortar per barrel of lime.

H. A. Farmer, St. Petersburg, Fla., recently wrote us as follows: "I am so well pleased with mixer, I want another just like it. Ship me another one as soon as possible."


Write for catalog today.

BLYSTONE MANUFACTURING COMPANY

286 Carpenter St.,
CAMBRIDGE SPRINGS, PA.

ARCHER CONCRETE MIXER

Capacity $4\frac{1}{2}$
cubic feet wet
concrete per
batch. Just
the mixer
for
economical
work on
large or
Small Jobs.



Saves the Work of 5 Men

The Archer Mixer by fast mixing and by discharging the concrete directly into the forms saves the work of five men. No wheeling is necessary. Loading platform is low. Barrow dumps into the charging hopper which is strongly braced so it will not bend or "give" under weight.

The price of the Archer makes it an attractive investment for the Carpenter and Contractor. It is built of first quality iron and steel with blue annealed steel plate drum. $3\frac{1}{2}$ H. P. Gasoline Engine. Platform 5 feet long by 38 inches wide and 21 inches high. Can be used anywhere on the job—in the basement or on the roof. We agree to refund your money if the Archer does not do all we claim. Write for full description and price.

Archer Iron Works
2430 West 34th Place

CHICAGO,
ILLINOIS

You Have Seen This Name



on the many mixers in constructing homes and buildings, along public highways in making curbs, gutters, roads, bridges, streets and in fact every possible place where concrete is used.

The use, of both the small mixer known as the "SSS," capacity 3 to 5 cu. feet, and the larger called "The STANDARD," capacity 3 to 40 cu. feet, from coast to coast, as well as those shipped to foreign countries, has given international prominence to their makers,

The Standard Scale and Supply Co.

In every mixer, thousands throughout the United States, you see the product of this company. Their owners investigated their many merits and many advantages:

Low-Charging, 24" from ground.
No Complicated Loading Hoist.
Open drum for constant inspection.
Batch type design which municipal engineers are demanding, etc., etc.

These features have added dollars in greater profits to the users of this line—it will to you.

The scope of our product goes still further. We manufacture most every equipment for contractors. We maintain a duplicate part system. Every piece of machinery is protected by the prestige of the name and the guarantee of the maker. Our experience has covered almost twenty-five years.

Therefore, when you invest in a Standard engine, hoist, material elevator, cart, barrow or other equipment, you may be assured that you have obtained as good as can be procured.

Correspondence Invited

from contractors considering big or little machines who are interested in bigger profits. Our Catalog No. 448, will be mailed to you tomorrow.

THE STANDARD SCALE & SUPPLY CO.

Chicago, 1345-47 Wabash Ave. Pittsburgh, 243-45 Water St. New York, 136 W. Broadway
Cleveland, 1547 Columbus Road Philadelphia, 35 South Fourth Street



Supplies the Demand for a Small Perfect Mixer



McCracken Batch
Mixer

The McCracken Portable Batch Mixer

is designed and built to meet the demand for a strong, simple, durable and practical mixer, that is large enough for all ordinary contract work, yet light enough to be profitable on the small job as well as on the large. Mounted on good steel trucks, EXTRA LARGE DRUM OF THE PROPER SHAPE, equipped with our own high-grade 2-HP. SIOUX engine, enclosed in a good steel housing (not a cheap box), also has friction clutch, so that drum can be started and stopped without stopping the engine. Capacity, thirty to forty yards per day. Cost for power, twenty-five cents per day. The largest, best and most complete mixer on the market for the money.

Write for Further Particulars

SIOUX CITY ENGINE & MACHINERY COMPANY 9th and Division Sts.
SIOUX CITY, IOWA

Capacity
3 to 5 Cubic Feet
Per Batch

Weight, 800 Lbs.

On Trucks,
1000 Lbs.

On
Trucks
with
Engine,
1400 Lbs.

THE WINNER MIXER



Will make money for you even if you don't have work enough to keep it running all the time. The cost is very small, and one gallon gasoline will run it a day.

Mixes 4 and 5 cubic feet per batch
Daily capacity, 30 to 40 cubic yards

Ask for our FREE Catalog

THE CEMENT TILE MACHINERY CO.
133 Rath Street Waterloo, Iowa

GET ORDERS for the UNIVERSAL RAT CATCHER




EVERY farmer, merchant and lumber dealer in your locality will buy one of these Rat Traps. It's a sure and quick way to rid all buildings of the pests. One of these Catchers placed in a livery stable in Scranton, Pa. caught over 100 rats in ONE MONTH. Trap made of galvanized iron; can't get out of order; lasts for years; always clean. 18 inches high, 10 inches diameter. One delivered prepaid upon receipt of \$3. Rats and mice die; no marks left on them.

My proposition requires no time from your work. I can show you how to make money easily. Don't be afraid to ask how. Cost you nothing to find out. I'll guarantee you can sell these Universal Rat Catchers easily.

WRITE TO ME AT ONCE.

H. D. Swarts, Inventor and Manufacturer, Scranton, Pa.



Standard Practical Plumbing

By R. M. STARBUCK

450 pages, 347 illustrations. Of the three hundred and forty-seven illustrations contained in the book, one hundred of them are full-page illustrations. The illustrations all being drawn expressly for this work, show the most modern and best practice in plumbing construction.

Plumbing in all its branches is treated within the pages of this book, and a large amount of space is devoted to a very complete and practical treatment of the subject of Hot Water Supply and Circulation and Range Boiler Work.

Another valuable feature is the special chapter on Drawing for the Plumber.


It Contains the Following Illustrated Chapters

1. The Plumber's Tools.
2. Wiping Solder, Composition and Use.
3. Joint Wiping.
4. Lead Work.
5. Traps.
6. Siphonage of Traps.
7. Venting.
8. Continuous Venting.
9. House Sewer and Sewer Connections.
10. House Drain.
11. Soil Piping, Roughing.
12. Main Trap and Fresh Air Inlet.
13. Floor, Yard, Cellar Drains, Rain Leaders, etc.
14. Fixture Wastes.
15. Water Closets.
16. Ventilation.
17. Improved Plumbing Connections.
18. Residence Plumbing.
19. Plumbing for Hotels, Schools, Factories, Stables, etc.
20. Modern Country Plumbing.
21. Filtration of Sewage and Water Supply.
22. Hot and Cold Supply.
23. Range Boilers; Circulation.
24. Circulating Pipes.
25. Range Boiler Problems.
26. Hot Water for Large Buildings.
27. Water Lift and Its Use.
28. Multiple Connections for Hot Water Boilers; Heating of Radiation by Supply System.
29. Theory for the Plumber.
30. Drawing for the Plumber.

Price, Postpaid \$3.00

Radford Architectural Co.

1827 Prairie Ave. : : : Chicago, Ill.



FRAMING

HOUSE FRAMING, BARN FRAMING ROOF FRAMING

By W. A. Radford. 338 (6x9 inch) pages, 182 illustrations dealing with house, barn and roof framing, covering the subject in its multitude of forms and designs in a most thorough manner. Nothing is omitted that will help and guide on the construction of houses, barns, roofs, etc., while particular care has been taken to exclude any and every method of framing that has not been given a thorough and convincing test by experienced builders.

Have you received your copy?

No contractor or builder can afford to go without this book. A copy will be sent Free, postage paid, to anyone sending us their renewal or a new subscription. Regular subscription \$2.00 per year.

AMERICAN CARPENTER AND BUILDER

1827 to 1833 Prairie Avenue
CHICAGO, ILL.



The BABY GRAND CONTINUOUS MIXER


combines all the good features of *mixer* and *hoist* at the price of *one* machine.

The BABY GRAND is a logical investment for the Carpenter and Contractor because both mixer and hoist are greatly used in modern construction. You can afford the Baby Grand. It is portable; capacity, 4 to 5 cu. yds. an hour. 2½ H. P. Gasoline Engine furnished with the machine.

The HOIST is mounted on the frame (see illustration). Operates with or independent of the mixer. Simple friction clutch for starting and hand brake for holding load. Capacity of hoist, 400 pounds. Lifts load 100 ft. per minute.

Our latest CATALOG gives a complete description. Send for it. We also make the HARTWICK TWO TROUGH MIXERS for heavy construction work.

HALL-HOLMES MFG. COMPANY
436 Oak Street Jackson, Mich.



Think of It!

This HELPER mixer that will mix mortar and concrete, only \$35.00

It will mix two cubic feet at a time. The measuring box enables you to get another batch ready while one batch is being mixed. Requires 1½ h.p. engine to run it. Daily capacity 15 to 20 cubic yards.

Send us your order now, or ask for FREE catalog giving more information.

THE CEMENT TILE MACHINERY CO., 132 Rath St., Waterloo, Iowa

THE BEST CEMENT BLOCK IN THE WORLD



Continuous open air space; reinforced all around; staggered bearings. Makes strongest buildings and silos at least cost.

Block Machines, Automatic Tampers, and Continuous Mixers made by the

BRAGSTAD CONCRETE MACHY. CO. - CANTON, S. D.

Write for Catalog and Prices

See our Exhibit
Space 4 Building
Material Exhibit.
Insurance Exchange
Bldg. Chicago, Ill.



A New York Contractor Says:

"Yesterday morning I started an Atlas 5-foot Batch Mixer and six men on a Machine Show Room floor; when the gong sounded last night, eleven men were hustling to keep up with the machine and it had turned out 57 cubic yards of excellent work.

I didn't think it possible to buy so much mixer for the money."

That's one man's endorsement of the

Atlas MIXER

Measured by service and durability, the Atlas is the lowest priced 5-foot Batch Mixer on the market.

Channel iron frame—splendid lubricating and double-bearing system—expanding ring clutch—low charging hopper—malleable blades and buckets in heavy boiler plate drum and an exceptionally powerful and mechanically perfect engine.

The Atlas can be sold at a low price because we specialize on mixers—every part standardized.

Don't buy a mixer for any purpose until you get the Atlas Mixer Book—just ask for it.

We will be glad to make a proposition to responsible dealers in open territory.

Atlas Engineering Company
780-790 30th St. Milwaukee, Wis.



90 Cubic Yards Per Day

Saves 60 to 90 cents on every yard. Pays for itself several times each season. Gives you the edge on your competitors. So light that two men can carry it. Big savings in freight and handling. Can always be set to discharge direct into forms. Saves all wheeling from machine. This alone saves one-third the labor necessary to operate other mixers.

Not a Man-Killer
Has an enormous capacity

SIMPLE—COMPACT—HANDY—SUBSTANTIAL

New Principle—Quick Charging—Quick Action—Quick Discharge

Its mixing blades have a criss-cross, kneading, plowing, hoeing motion which press and fold the entire batch over upon itself many times every second. Insures a quick and thorough mix. You will be proud to say you have a Northfield Hand Batch Mixer, once you see its work.

The SLUSH mixer mixes 4 cu. ft. of finished concrete per batch. A batch per minute or 90 cu. yds. per day is easily possible under favorable conditions. 30 to 60 cu. yds. per day is a fair average on ordinary abutment, floor, wall or bridge work. Over 10 cu. yds. per hour have been averaged. When operated by power—one man alone can mix mortar fast enough for a crew of 20 brick layers.

The DRY or WET mixer is good for any kind of mixing—either Dry, Wet or Slush. Is extra fine for brick or block plants, core sand, plaster, brick mortar, chemicals, etc. Capacity—2 to 3 cu. ft. per batch—or 15 to 45 cu. yds. per day. Is just like the SLUSH mixer except a slight change in the drum heads and agitator. Is the best for an all-purpose mixer. The SLUSH mixer is best for big jobs and rapid contract work where slush mixtures are used.

Two men turn either machine easily and do not work as hard as the shovellers. A pump engine will run them. It is not necessary to have a big expensive power mixer to economically mix concrete. No job is too big or too small for the Northfield. No better mixer can be had, even at ten times its price.

Write direct to factory for catalogue, prices and terms.

NORTHFIELD IRON COMPANY

402 Water Street Northfield, Minn., U. S. A.

Buy The SIMPLEX 1914 Model MIXER



Combining the good features of both batch and continuous mixers in the one machine.

The best feature of the Batch Mixers is the rolling of the materials. The greatest advantage of the Continuous Mixer is the automatic measuring and feeding of the materials.

Only one machine combines these two features—the SIMPLEX. It's the happy medium between the two types of mixers, giving the points of advantage claimed by each, and eliminating the faults of both.

Write for New Complete Catalog.

The Miles Mfg. Co.

309 E. Franklin St.

JACKSON, MICH.

"I Don't Think They Can Be Equalled"



No. 9 Coltrin Mixer.

Clara City, Minn., March 9, 1914.

THE KNICKERBOCKER CO.,

JACKSON, MICH.

Gents:—I purchased a No. 9 Coltrin Mixer last spring from your Minneapolis agency. Will say that I don't think they can be equalled. Mixed most every day last summer as high as 225 sacks of cement, 1 to 4, in a day. By attaching an 8-inch pulley, I am pumping water for stock and am also running a small Wonder feed mill, grinding feed for my stock. Works fine, and not an extra needed during time except a change of batteries. All seems as good as new. What machine can duplicate this? I have never seen one.

If you wish to print this, you have my permission. Trusting you may sell me another some time, I am,

Yours very truly,

CHAS. GEIST.

The Coltrin Continuous Batch Mixers

Shipped anywhere on trial. Write for Catalog.

THE KNICKERBOCKER CO. :: JACKSON, MICH.

The Right Kind of Mixer for Building Contractors

The merit of Dunn Mixers lies in their **adaptability**. They are just as desirable for mixing mortar as for concrete—the unusually long drum and unique mixing arrangement assuring absolutely perfect results. They are low enough in first cost and upkeep to be **economical** for the small contractor, and their capacities are large enough to bring manufacturing costs down on the big jobs. They are strong enough to withstand the severest service conditions, and light and compact enough to be easily transported.

Prices from \$67.50—On 15 Days' Trial

From the Dunn No. 0 on skids, costing \$67.50, to our No. 1 on steel trucks, complete with engine and power discharge feature, selling for \$224, the Dunn line contains the style that **exactly** fits your needs. **And we don't ask you to buy any Dunn mixer until you have used it for two weeks on your own work.** Write today for the complete Dunn mixer catalog.




DUNN No. 1
with Power Discharge

Patent
No. 842262
and 782700

Make Concrete Fence Posts

Here's a business for your spare time—a business that pays more for every dollar invested than any side-line you can think of. Concrete fence posts are always ready sellers at prices that leave an unusually large profit.

Dunn Molds make the strongest fence posts—and make them in less time and with less labor than ordinarily. The special **Vibratory Base** eliminates air and water pockets and saves tamping. The molds are furnished in batteries of four and ten, and the vibratory base will tamp as many as one hundred posts at one time. Price of 4-mold battery, \$12.50; sold on 15 days' trial.



Cement Block Machine

Makes three styles of blocks. Costs only \$40. Sold on 15 days' trial.

Interesting book on the concrete industry, also describing Dunn Block Machine, Porch Molds, Sewer Pipe Molds, etc., sent free.



W. E. Dunn Mfg. Co.

4132 Fillmore St., - Chicago



You use but one hand to operate the "YANKEE" Bench Drill

With the new automatic features the friction feed brings the drill down quickly to the work, then the ratchet feed operates and prevents breaking of the drill point. This leaves free use of the left hand to hold the work. The quickest and most convenient Bench Drill Made.

Send for the "YANKEE" Tool Book

NORTH BROS. MFG. CO.

Dept. A.

PHILADELPHIA, PA.



No. 1003

Drills
holes
up to
1/2 in.



Two
Speeds

No. 1005

Drills
holes
up to
1/2 in.

1853



1914

Fine Beveled Edge
Shank and Socket

Chisels

**Tang and Socket
Butt Chisels**

Plain and Beveled Edges

Send for illustrated Catalog


Buck Bros., Millbury, Mass.



**MADE
TO ORDER**

Fly Screens and Screen Doors

We use the best grades of wire cloth, black enamel, galvanized, pearl and copper bronze, fastened by the improved Standard Shoulder Strip Method, which makes the wire drum tight and firm, can not sag or pull away.



See
That
Corner?

Notice how stiles
are fitted into rails.


Dealers, Carpenters, Contractors and Builders,
write for a free copy of our 1913 illustrated catalog

STANDARD SCREEN CO., 1848-50 W. 14th St., Chicago, Ill.

Our screens are all mortised, tenoned, joined with waterproof glue and pinned with steel pins, will last a lifetime.

INTERLOCKING MASTER SLIDE RULE—Takes Inside Measurements Correctly

Newly invented and **improved**. Has inter-locking device on every slide. Rigid when extended. Opens and closes easily when key spring is pressed. One side is used for taking inside measurements of sash, frames, doors, windows, cupboards, etc. The other side for lineal measurements of outside surfaces. Made of selected boxwood trimmed with brass plated steel. Cannot rust. All sizes, 2 to 8 feet. Price 15 cents per lineal foot. Get one from your dealer or send price and we will send you a Master Slide Rule, by return mail.

**DAHL MFG. CO.**51-G East 42nd St.
NEW YORK, N. Y.**The "EUREKA" Spiral Screwdriver**

Made in Two Sizes. No. 1—14 inches long, opened; 9 inches closed.
No. 2—19 inches long, opened; 12 inches closed.

Push on the end and the screw goes in. Can be used as an ordinary screwdriver. The simplest and best made. Durable and powerful. Send for Circulars.

**DECATUR COFFIN CO., Decatur, Illinois****If You Like It, Buy It***If You Don't Like It, Send It Back*

Those are the only terms attached to our liberal

10-Day, Free Trial Offer

We want to convince you that it will save you time and money, and better the quality of your work if you have a

CHAMPION MORTISER



Perfectly designed and equipped with ball bearings, large gears and automatic stop. Cuts mortises in three minutes. Any size, any shape from a perfect round hole up to 6 1/4-in. slot. Price very reasonable.

TELL US YOU'D LIKE TO TRY THE CHAMPION
FOR 10 DAYS FREE OF CHARGE.

Colgan Machinery & Supply Co.

616 New Hayden Bldg.

COLUMBUS, OHIO




FOX

"UNIVERSAL TRIMMER"

TRADE MARK

A
Machine
For
Every
Need



6A. FOX "UNIVERSAL TRIMMER"

A
Need
For
Every
Machine

**You Will Never Know What Perfect Work is Until You
Use a Fox "Universal"**

*The fitting of interior finish is greatly improved
by using a Fox Universal.*

Write TODAY for Our New Catalog

FOX Machine Co.22 FRONT AVENUE N. E.
GRAND RAPIDS, - - MICHIGAN

"Straight to the Mark"

THE **FAMOUS** LINE

You are trying to hit the mark of greater success. The Sidney "Famous" goes straight to that mark! With a "Famous" Wood-worker in YOUR shop you will find business **pick-
ing up right along.**



THE SIDNEY TOOL CO.
Sidney, Ohio

Gentlemen: Show me how your line
will enable me to hit the mark of
greater success. Send Catalog No. 12.

Signed.....


Address.....

The Famous "31" Universal Woodworker saves time, cuts cost, eliminates much hand labor—PAYS!


BUY WITHOUT RISK

So far as risk has ever been eliminated from the purchase of machinery we have eliminated it. Every one fully guaranteed. Every one made up to rigid demands—of the best materials, by careful workmen. TESTED and found RIGHT before shipped. Guaranteed to please. Our marvelous success with "Universals"—the fact that we are the world's pioneers on this line—the fact that exceedingly few complaints have been made, and, on the other hand, that we have received hundreds of ringing letters attesting to the profit possibilities found in our wood-workers—these things speak highly of SIDNEY wood-workers. Send your pencil "straight to the mark" in the upper right corner of the

ad—fill out the coupon and mail it today. Paste it to a Post-card. It will come straight to us. You will thus be aiming a little closer to the "bull's eye" of more money.



**THE SIDNEY
TOOL CO.
Sidney, Ohio**



Some Distinctive Features
of the

“AMERICAN” Contractor's Portable Variety WOOD-WORKER

A ribbed iron top, 30x54 inches, carefully planed.

Will rip a 26-inch plank through the center without removing the saw guide.

Has an adjustable bevel ripping gauge, with fine adjustment and solid locking device.

Has an independent hand jointer with every adjustment found on the highest-priced machines.

Has a 6-inch jointer head slotted on two sides for all kinds of bits and knives.

Has heavy chain-oiling arbor bearings, yoked together by a solid casting.

Gauges can be removed in a few seconds, for cross-cutting.

Four men can work on it at four operations at one time, without interference.

Engine or motor of ample power for the heaviest work.


Construction strong enough and heavy enough to stand the most severe service.

Send for the “American” Pamphlet No 47

American Saw Mill Machinery Co.

80 Main Street
HACKETTSTOWN
NEW JERSEY

1360 Hudson Terminal
NEW YORK CITY
NEW YORK



No. 10 Ball Bearing

“Grand Rapids”

**BALL BEARING
ALL STEEL**

Sash Pulleys

Fasten automatically.
No Nails. No Screws.
Just bore four holes.

The automatic saw tooth fastening feature and the simple and easily made mortise will save in labor enough to pay for the pulleys.


The Bearing contains eleven 1/4-inch Solid Steel Balls running in lubricant.

NOISELESS EVERLASTING

Write for FREE Samples

Grand Rapids Hardware Co.
MANUFACTURERS

158 Eleventh St. :: Grand Rapids, Mich.



COMPLETE OUTFIT

**Hand and Foot-Power
MACHINERY**

Our No. 3 Wood Turning Lathe can be speeded from 1,000 to 2,000 revolutions a minute with perfect ease. Stopped or reversed at will of operator.

Write for Particulars

W. F. & Jno. Barnes Co. 74 RUBY ST., Rockford, Ill.

Parks Portable Shingle or Combination WOODWORKING OUTFITS


are the most practical—the most efficient—the most economical woodworking equipment you can buy

This machine is a combination of circular rip and cross cut saw, 6 or 12-inch jointer with tilting guide, boring attachment, jig saw with tilting table, sand disk, and gasoline engine, guaranteed to do the work.

Angle steel frame—the strongest structural material known. Machines are made in large quantities which allows us to sell at lowest prices and make prompt shipment. WRITE FOR CATALOG

PARK'S

Ball-Bearing Machine Co.
Fergus Street and C. H. & D. Ry., CINCINNATI, OHIO



No. 256-T

An Investment in a Lifetime of Satisfaction

The day of the power wood-worker is here. Carpenters and Contractors who watch conditions closely, agree that competition makes a power woodworker necessary for modern building.

All about you you will find Carpenters and Builders who are using wood-workers. They are making a success of it. They have found it profitable to get out their dimension stuff and all their millwork quickly. They have found out that a power woodworker saves time and the wages of a good-sized crew.

A Crescent Universal Woodworker will save you all the delays, the disappointments and the "bum" work you have had to put up with for years. It is the means of getting ahead on your contracts. It enlarges your capacity for handling contracts. It makes you independent of others for material. Above all, it cuts down your wage expense and turns into your own pocket the profits you have been handing to the material dealer.

For the Shop, the Job or the Lumber Yard

The Crescent is approved by shrewd men because it has its place wherever building material is being prepared. Use it in the shop, winter or summer, getting material in shape for your jobs. No matter what is needed—framing timbers, braces, door or window frames, sash, stair work, porch work, moulding—anything and everything in the nature of wood work for your contracts. Use it right out on the job when advisable. Many Lumber Dealers have purchased a Crescent because it gives them all the facilities of a fully equipped planing mill.

Four Men Can Work at the Same Time

The different parts of the machine are so arranged that each one is easily accessible. Four men can work on the Crescent at the same time without in any way hindering each other. Each part of the Crescent can be started or stopped at will. It is not necessary to run the whole machine when only one part is in use. Each unit is distinct and separate from the others and can be so used.

Crescent Universal Woodworker


Is a combination of machines which includes Band Saw, Jointer, Shaper, Saw Table, and Borer. Other attachments may be added when wanted to make the Crescent adaptable as a Re-Saw, Hand-Feed Molder, Tenoner, Panel-Raiser, Pole-Rounder, Disk-Grinder, Knife-Grinder, Plain Grinder and Hollow Chisel Mortiser. The base is one single casting on which the various parts are mounted. For variety of work, construction, durability, and price, The Crescent is really an investment for a lifetime of service and satisfaction.


New 1914 Catalog

—a book of 142 pages, well illustrated and full of information about the Crescent Universal Woodworker and our complete line of woodworking machinery is ready to distribute. We suggest that you write for your copy now. It pays to be a leader in the building field.

Investigate the Crescent NOW!

**The Crescent
Machine Co.**
224 Main Street
LEETONIA OHIO



"OHIO EXTRA" AUGER BITS

are High Grade Single Twist Bits, carefully made from specially selected auger bit steel. They are the **Most Rapid Cutting and Perfect Clearing Bits** on the market today and are fully warranted.

"OHIO" CHISELS, PLANES, ETC.

All "Ohio" Tools are made with the same painstaking care that has built up our present reputation for making only high grade tools. We use in our Edge Tools high grade steel, treated and tempered by the most improved process, which insures **Uniformity and Correctness of Temper, and a Keen, Tough and Lasting Cutting Edge.** If you appreciate Good Tools it will pay you to insist on having "Ohio" Tools from your Dealer.

Write for our special Carpenters' Catalogue of High Grade Tools and Benches


OHIO TOOL CO. (Dept. 15) Charleston, W. Va.

**Articles Every Carpenter Needs**

Boxwood Folding Rules

Spring Joint Rules

Steel Rules



Steel Tapes

Woven Tapes

Pocket Tapes

We guarantee to YOU absolute satisfaction
CATALOG ON REQUEST


When in need of these
say to the hardwareman

THE LUFKIN RULE CO.

New York

Saginaw, Mich.

LUFKIN

CALDWELL SASH BALANCE

Does away with weights and cords, and **VASTLY** more durable.


Makes sashes work perfectly.

Permits greater window space in new work, as box frames are not necessary.

May be applied to old windows without altering sashes or frames.

Write for circular to the

Caldwell Mfg. Co.
15 Jones Street, - Rochester, N. Y.

BLAKE QUICK ACTING VISE

For Cabinet Makers and Wood Workers. Simplest—Strongest—

Cheapest—Best

Send for Catalogue of all kinds of Vises

PRENTISS VISE COMPANY, MAKERS

106-110 La Fayette St., New York, U. S. A.

Miller's Lock Mortiser
TWO MINUTES

Will cut an opening in a door for a mortise lock
IMPROVED AND UP-TO-DATE

cuts true, in any kind of wood for any size lock from $\frac{1}{2}$ " to $1\frac{1}{4}$ " thick. Easy to operate; durable in construction. Builders use it everywhere.



Sent subject to trial.

A. W. Miller Mfg. Co.

Riverside, Calif. - Cincinnati, Ohio



Our Butt Mortiser and Rule Gauge for 75c., Postpaid

GENUINE BANGOR

**Roofing Slate
Structural Slate
Blackboards**

Large Facilities, Prompt Deliveries
EAST BANGOR CONSOLIDATED SLATE CO.


East Bangor, Pa.



**Standard Portable
Combination
Woodworker**

**9 Machines in 1
6 H. P. ENGINE**


**SEND FOR CATALOG G
ATLANTIC ENGINE CO.
Meadville - Penna.**



WHEN WRITING ADVERTISERS PLEASE MENTION THE AMERICAN CARPENTER AND BUILDER

WRITE US

FOR OUR NEW
1914 CATALOG




AS PIONEERS in the manufacture of **PORTABLE SAW RIGS**, we are entitled to claim that we manufacture the **BEST Portable Saw Rigs** on the market today; in fact, we make them complete in five different sizes to meet every requirement of the trade.

We also manufacture hoists, pumps, elevators, mortar mixers, concrete chutes, air compressors, gasoline engines, etc.


Write Us for our new 1914 attractive Catalog

C. H. & E. MANUFACTURING CO., Inc.
322 Mineral Street MILWAUKEE, WISC.




Section of Main Floor Exhibit and Salesroom

Everything in wood working machinery and supplies for Contractors, Carpenters, Builders, Interior Finish, Sash and Door, Planing Mills, Furniture, etc.



Chicago Band Saws
27-32-36 inch wheels



Chicago Jointers
8-12-16 inch

*Write us Your Wants
and Get Our Special Price*



Chicago No. 9 Combination
Saw


Chicago Machinery Exchange
1215-1223 Washington Blvd. :: CHICAGO

**EVERLAST***The Handle Never
Loosens***HYNALER HAMMER**

A very high grade tool that will suit you in grip, bang and hardness of head. Illustration shows nail-holding device for high nailing. Hollow steel handle that will not loosen. Fitted to the head in a way to absorb all the shock of driving.


We manufacture High Grade Socket Joint Tools with Hollow Steel Handles exclusively. Get the Everlast Hynaler Hammer from your dealer, or send \$1.25 and get one direct by parcel post. Catalog of tools free.

HAWTHORNE SALES CORPORATION, Mfgs.,
220 W. 42nd Street New York, N. Y.

**Say SHELBY "CHIEF"**


When you ask for a double-acting, ball-bearing, surface floor hinge. "The hinge without woes, as the wise buyer knows." The cheapest floor hinge money can buy, when quality and efficiency is considered. Shelby Chief should be on the floor plates, accept no other.

THE SHELBY SPRING HINGE CO., SHELBY, O.



**Something Every Man With Any Mechanical Ideas
Should Have for Himself—And As an Agent**

With Compass the New Improvements Now Make
The American Combined Level and Grade Finder
Most Practical, Durable and Convenient Instrument Made



At one glance you can get the true slant on any line or grade either in degrees, inches or percentage, or all at the same time, and will at once give the exact distance needed to plumb up to a true level. The additional spirit level glass now placed in middle of instrument with points on dial will give 3 grades for leveling. The longitudinal recess shown in cut is well worth the low price of the instrument. Write AT ONCE for circular and Testimonials. Special Introductory Price given to First Applicants with privilege of taking Agency. ADDRESS

Edward Helb, Mfr., Box 255, Railroad, Penna.

Henderson House and Barn Builder

The best designed machine for framing all material for any building. All material, including bridging braces for a two-story, hip roof residence 16'x32' was prepared in 3 hours and 20 minutes. 4 h.-p. engine gives necessary power to run all the machines at the same time. Hand jointer, rip saw, swing saw, boring machine and work bench 9' long x 32" high, all complete. Handles heavy or light timber. Write for description and price.



Perfect in every way. Makes moulding, stops, frames, jamba, studding, joists, sleepers, rafters, braces, etc. No marking necessary.

Lock
Box
184

Henderson-
Traylor Mfg. Co.
KENIA, ILL.

**For Store Fronts****The Petz Metal Store Front**

is the safest made. It's had the test.

It held up plate glass windows to an 86-mile-an-hour gale when flimsier fronts gave way.

The **Petz** front is insurable at the lowest rate.


Other worthy facts in our booklet, "Metal Store Front Construction."

Send for it.

Detroit Show Case Co.

491 West Fort St.

Detroit, Michigan



When
you want
tools of any kind
—tools that you
can bank on to be
just the kind and qual-
ity you want them to
be, insist on the Swan
Trade Mark.




It's a plain guide to all that is best in carpenters' tools and your assurance that you are dealing with an old, reliable firm that makes tools as good and solid as its reputation.

ASK FOR CATALOG
The
JAMES SWAN CO.
Seymour,
Conn.

DIAMOND EDGE TOOLS

For Originality, Quality and Service



Black Enameled Cast Iron Frame; Face of Bottom and Sides Ground True and Smooth; Composition Rubber Handle; Ebonized Wood Knob; Full Polished Cap and Cutters; Highest Grade English Tool Steel, Thinbit Cutters; Oil Tempered, Ground and Hand Sharpened; Screw and Lever Adjustment.

ASK YOUR HARDWARE DEALER—HE CAN SUPPLY YOU—IF NOT, WRITE US—DEPARTMENT "W"

SHAPLEIGH HARDWARE CO.

Established 1843

ST. LOUIS

"DIAMOND EDGE IS A QUALITY PLEDGE"

Trade **SIMPLEX** Mark
Reg. U. S. Pat. Office

ROOFING NAILS

FOUR NAILS at PRICE OF ONE
When You Buy Them.

ONE NAIL in place of FOUR
When You Drive Them.

BECAUSE the Simplex has four times the head area of an ordinary roofing nail—hence four times the holding power, as head area is the all-important point in laying prepared roofing or sheathing papers.

Demand Simplex Nails from your hardware dealer. Don't buy prepared roofing unless Simplex Nails are packed in the rolls. FREE samples sent on receipt of request accompanied by dealer's name.

H. B. Sherman Mfg. Co.


Battle Creek, Mich.

RED DEVIL BITS

SINGLE OR DOUBLE TWIST

HONED LIKE A RAZOR, NOT SIMPLY GROUND, BUT TRUED ON A LATHE
Red Devil Bits are made with 10% greater clearance than any other. Will drill with or against the grain, in any kind of wood, and under any conditions.
If your dealer can't supply, send \$5.25 for set No. 2401 of 32 1/2 quaters in wooden box.
At any rate, send for Booklet of 3,000 Red Devils.

SMITH & HEMENWAY CO.
156 Chambers St., NEW YORK CITY

*The Red Devil Bit—Always Makes a Hit***DON'T SWEAT!**

There is no use in sweating all summer when good tools will lighten your labor. You want tools that are suited to your work—tools that are built on correct principles—tools that are made of materials giving the longest wear. Of course, this means

Goodell-Pratt's


We make more than 1,500 tools for carpenters and machinists. We sent you a little booklet showing a few of them. If you forgot to write for our complete catalog then, sit down and do it now.

**Goodell-Pratt Company***Toolsmiths*

Greenfield, Mass., U. S. A.



A Star Among Boring Machines



Your profits on that job you are doing depend upon the quantity and quality of the work you get for the wages you pay. **Efficient tools** are the first step in the road to success, and no tool of its class excels, in efficiency,

"MILLERS FALLS" Boring Machine No. 146

It is made to do more and better work—and it does it. All metal; bores vertically or at any angle within an arc of 50 deg.; has adjustable stop for regulating depth of hole; automatic suspension device and adjustable cranks. Bores 12 in., but can be made for greater depths if so ordered.

Reliable dealers, everywhere, carry "Millers Falls" Tools. Ask yours. If he cannot serve you, write us and we'll send you the name of a dealer who can. New catalog on request.

MILLERS FALLS CO., MILLERS FALLS. MASS.



WHITE'S IMPROVED LEVEL

SHIPPED ON APPROVAL



Our No. 2011 improved level, illustrated herewith, is especially designed for work where a general purpose level is required. Telescope is 12 inches long with magnifying power 25 diameters, and is capable of detecting an error of 1-16 inch in 300 feet. We ship this level out on approval, express prepaid, in order that you may try it out on your own work before deciding to keep it. Ask today for your circular and special net price sheet. Ask today!

DAVID WHITE COMPANY

No. 2011 419 E. Water St. Dept. C Milwaukee, Wis.

Two Instruments for the Price of One

When in need of an Architect's Level or a Builder's Transit do not fail to investigate our

Transit-Level

It is convertible and will serve as a first class Builder's Transit as well as an Architect's Level. If you should have use for an instrument at all you should buy this accurate, durable and most serviceable instrument which is without question the leader as to general usefulness among all instruments on the market. It has no equal for Efficiency and Economy.

To keep abreast of up-to-date methods send for Catalogs and Circulars and be informed as to the latest and best.

GEIER & BLUHM

672 River Street, Troy, N. Y.



(Pat. Pending)



Patented: Nov. 29, 1892
July 19, 1910

A Huther Bros. Dado Head Fits Any Saw Rig


Cuts perfect grooves with or across grain. Simple, no-screw adjustment. The choice of experts.

Huther Bros. Saw Mfg. Co.

1101 University Ave.

Rochester, N. Y.

"Last a Lifetime and Give Satisfaction To the End"



BUTT CHISEL

The celebrated Barton Planes and Edge Tools for carpenters and all other woodworkers are unequalled by any other made for keen, hard, smooth cutting edges. If your hardware dealer does not handle




THE CELEBRATED BARTON TOOLS

Send direct for catalogue and our free story book, True Stories. Be sure to specify "CARPENTER'S CATALOGUE."

MACK & COMPANY,

20 BROWN'S RACE
ROCHESTER, N. Y.

Architects Convertible Level



For builders. An instrument of the highest type of accuracy and efficiency—Combines the ordinary contractors level with a transit. It has all the usual Beckmann nicety of manufacture and accuracy.

Guaranteed in Every Way.

Write for Builders Manual "Y"

THE L. BECKMANN CO.
7500 Adams St., TOLEDO, O.

CONTRACTOR CLEARS \$450 IN 10 DAYS

M. H. Ireland,
Anamosa, Ia.

Contractor—
cleared above by
using LITTLE
WONDERS—
What one man
can do with Little
Wonders you can
do—Get next to
this LITTLE
WONDER
TRUCK—it will
triple your profits.



**10 ROOM HOUSE 5 MILES 10 DAYS
MOVED IN**

Let us furnish your complete House Moving Equipment—everything from Little Wonder Trucks to rollers, jacks, etc. Get our catalog "B" right away. Don't delay. Just a post card brings it in a hurry.

HOUSE MOVERS SUPPLY COMPANY 620 Eastlark Court
Cedar Rapids, Iowa

"Sterling" Convertible Level

The 1914 Model is of reinforced construction throughout. Strong, compact and light in weight, and for the Contractor and Builder the most practical and efficient instrument made.



Send for Catalog S. W., and investigate why after careful comparison "Sterling" Levels are invariably selected.

WARREN-KNIGHT CO.


Makers of

"STERLING" TRANSITS AND LEVELS

136 No. 12th St., Philadelphia, U. S. A.

Successors to Izzard-Warren Co.

LEVEL WORK



**Architects
Builders
Contractors**

Insure against mistakes in leveling by using our Architects' and Builders' Level. We make a specialty of this instrument. It will give positive, accurate service. Saves its cost in a short time.

We manufacture a complete line of surveying instruments in various sizes and at a wide range of prices.

Our circular No. 27 will explain our instruments to you in detail. It will pay you to get it before deciding upon any surveying instruments.

KOLESCH & CO.

Surveying Instrument Makers. Established 1865.

138 Fulton St.

NEW YORK



Rent This Level 10 Months Then It is Yours

Builders --- Contractors --- Architects

This is not the old style Architect's Level. It is the newest model convertible level. There is not a single Builder, Contractor or Architect who has not almost daily need of this instrument. For laying out buildings, locating foundation piers, leveling up foundations, walls and floors, aligning shafting, walls, piers, etc., for getting angles, locating levels anywhere, ditching, laying streets and walks, running straight lines, and a hundred other uses.

Instruction Book Free

Complete illustrated booklet, telling how a builder, contractor or architect can use the convertible level, sent free on request.

WARNING

The Level we offer is the new Alooe Convertible Level. Don't confuse the Convertible Level with the ordinary style Architect's Level. The only work that can be satisfactorily done with the ordinary Architect's Level, is the determining of elevations. But the Convertible Level, besides its use as a level, is a modified transit and broadens the use of the level 100%. You can't afford to buy any but the Alooe Convertible Level.

HALF CENTURY REPUTATION

We have been manufacturers of transits and levels since 1863, and our instruments are the standard of the world.

FREE TRIAL

We allow you to convince yourself by a trial of the instrument before you obligate yourself.

THE RENT BUYS IT

No large cash outlay needed. Just pay the rent for a few months and the instrument is your absolute property.

Send Coupon—No Obligation

Send the attached coupon today and we'll send illustrated booklet and complete details of how you can own the Alooe Convertible Level for 10 months' rent.

A. S. Alooe Co., 621 Olive St., St. Louis, Mo.

COUPON

A. S. Alooe Co., 621 Olive St., St. Louis, Mo.

Please send free instruction book on the use of the Convertible Level and complete details of your rental plan. This request in no way obligates me.

Name

Occupation

Street

City..... State.....

Am. C. & B. AUG. 14

Accuracy in Long Measurements

When you are taking long measurements, don't stop to use a rule, with its possibilities for error, or a cloth tape, which may stretch, but get your distance quickly and exactly by using a

Starrett Steel Tape

You can rely on your measurements when you use a Starrett, because Starrett tapes are carefully graduated and marked so as to prevent error in reading. The convenience of handling a Starrett and the time saved will be well worth the price of the tape.



Starrett tapes are made in a wide variety of styles and lengths. There are little fellows 3 feet long for pocket use and big ones 100 feet long. Some are contained in leather cases, some in nicked steel cases, and some come on handy reels. The new patent push-button tape shown here, is a great convenience in opening the handle.


Our free catalog No. 206 shows the styles, sizes, and prices for each. You can buy Starrett Tools at all good hardware stores.

The L. S. Starrett Co.

WORLD'S GREATEST TOOLMAKERS

Athol, Mass.

42-367



"A Bit of Utility"

Guided by its circular rim—instead of its centre—the Forstner Labor-Saving Auger Bit will bore any arc of a circle, and can be guided in any direction.

Doesn't matter how hard the wood is, no consequence whether it is full of knots, or the grain awkward to negotiate. The Forstner Bit works with equal smoothness under any condition and leaves a true polished surface on every job.


Unequaled for Delicate Work

Supercedes chisels, gauges, scroll-saws, or lath tools combined, for all kinds of delicate work. Cabinet and pattern makers and carpenters are enthusiastic because they do more work than other bits and cost no more.

We can offer something special in the matter of price on sets packed in a sensible box. Send today for particulars and catalog.

The Progressive Mfg. Co.

Torrington, Conn.



ROOF SLATES

STRUCTURAL SLATE BLACKBOARDS

E. J. JOHNSON

38 Park Row New York

Quarry Operator

BLACK, GREEN, PURPLE, RED

Booklet, Samples and Prices on Application

WHEN WRITING ADVERTISERS PLEASE MENTION THE AMERICAN CARPENTER AND BUILDER

A BETTER BUILDING FOR LESS MONEY



That's what you can get if you use
KEES METAL BUILDING CORNERS

They are little galvanized iron corner pieces that fit over the ends of the weather-boards forming a perfect and lasting mitred corner. Cost less, look better, last longer than corners finished in any other way.

A card will bring samples and photos of attractive buildings on which they were used.

Ask for a set of Gossett Hinges for Full Length Screens.

ED. KEES MFG. CO. DENTON, NEB.


Box 552

The Richards Shingling Bracket

Something New for Contractors and Builders

IT HOLDS THE SHINGLES

Holds shingles upon roof exactly where wanted, no matter how strong wind is blowing. Easily removed at will of shingler. Weight bar quickly detached when not needed. Workmanship and material fully guaranteed. Write TODAY for descriptive circular and prices. Liberal proposition to dealers.



Richards Shingling Bracket Co.

Toledo, IOWA

Vanadium High Speed Steel Cabinet Scrapers

THE SCRAPER OF QUALITY



Mr. Mechanic:—

Try out the quality of steel in the **Vanadium Steel** saw, by using a scraper made from the same steel. Only the best of steel will make a scraper that will hold an edge, and the steel that will make good scrapers will make the best of saws. Send us 15 cents in postage and we will mail you any size scraper desired from 2"x5" to 3½"x6"

PENNSYLVANIA SAW COMPANY

::

Frackville, Penn.

Makers of the best Hand Saws. Quality guaranteed.

Bishops Refined "Greyhound" Steel Saw—A Masterpiece

Of the Saw Maker's Art. We are proud of its quality and guarantee it to cut faster and run easier in all kinds of wood, to hold its sharpness and set longer than any other good saws.

It's the Your-Money-Back-If-Not-Satisfied Saw

30 Days' Trial Will Prove Our Guarantee



The "Greyhound" is the result of years of experimenting to originate a purity of steel with fine grain and tough body.

Made in both Straight and Skew Back

Length Each	18	20	22	24	26	28	30	32	34	36	inches net
	\$2.35	\$2.50	\$2.65	\$2.80	\$3.00	\$3.30	\$3.65				

Packed One in a Box




GEO. H. BISHOP & COMPANY
LAWRENCEBURG, IND.

WHEN WRITING ADVERTISERS PLEASE MENTION THE AMERICAN CARPENTER AND BUILDER

SHARP TOOLS




TOOLS with the keen, smooth edge that will stay sharp on the job are found in the tool kits with



Carborundum Sharpening Stones


Just a few strokes and the edge is there, keen and smooth.



A Carborundum stone cuts—cuts clean, there is no rubbing—it gives an edge that is an edge—every stone is uniform and it won't fill or glaze.

There is a Carborundum stone for every edge tool.

Ask your hardware dealer.



The
Carborundum
Company

Niagara Falls, N. Y.



One Builder Orders Fifty Tuecs

In Portland, Oregon, there is a contractor who has discovered a sure way of adding to the sales values and the rentals of his buildings out of all proportion to what he adds to the cost. Recently he ordered fifty Tuecs at one time, to be used in fifty buildings now under course of construction. The

TUEC STATIONARY CLEANER

is priced so reasonably that every home costing \$3,000 or more should be equipped with this service. At only \$160 F. O. B. Canton, Ohio, complete with tools and hose, the Tuec 170 is meeting with a tremendous demand from home owners and builders alike, thousands of whom now regard the Tuec as being quite as essential to a modern home as a furnace or stationary plumbing.

*Write today for the Tuec Book.
Special inducements to Contractors and Builders.
Prompt deliveries.*

The Tuec is made in 15 sizes, providing for the requirements of all buildings.

THE UNITED ELECTRIC COMPANY
30 Hurford Street CANTON, OHIO

In Position "SAFETY FIRST"

Fold Compactly

Wheeler Safety Scaffold Brackets

Save Lumber—Save Labor—Save Nails—Save Accidents

Pay for themselves on two jobs and last a lifetime. Lock automatically. Men cannot be careless putting them up. Are rigid and firm when in place. Scaffold cannot swing. Write for our

FREE TRIAL OFFER

AMERICAN STEEL SCAFFOLD CO., Dept. 7, DETROIT, MICH.

Put a GOOD Lock on Your Tool Chest

—a good lock often prevents the theft of valuable tools. Put a Miller Lock on your tool chest and no one can pick it or break it open. Four secure levers; solid polished brass. For chests, automobile tool boxes, etc. $\frac{1}{4}$ " thick and up.


PROTECT YOUR TOOLS NOW.


No. CB495—
All Brass—
Full Size,
 $3\frac{1}{4}$ " x $2\frac{1}{4}$ ".

Price.
Postpaid,
\$1.25

**MILLER LOCK
CO.**

Frankfort,
Philadelphia, Pa.





No. 25-B

Broad Axe

The kind that will last and save you a lot of extra work in grinding

Cost a few cents more, but worth twice as much; and when you buy an axe, you want a good one, don't you? Have your dealer order a sample one so you can see for yourself how good they are. If he won't order, write us for prices. Do it today.



No. B-2

The New Chisel

A lot of our carpenter friends wanted us to make them a chisel shorter than the regular Firmer and longer than the standard butt, so we made for them

Our B-2 Chisel

It was so popular that we determined to put it on the market. So here it is. Blade $3\frac{1}{2}$ inches long, light and well balanced—and with the regular White quality.

We know it would just suit you

and be as handy as your pocket knife. Order a set of these through your dealer, or, if he don't want your order, send to us direct—we want it. Yours for quality.

THE L. & I. J. WHITE CO., 10 Columbia Street, BUFFALO, N. Y.



No. 5155

34c For This Lock Set


**No. 5155 Antique
Copper Finish**

FREE—No. 5. Builders Hardware Catalog and net price list to Contractors and Material Men.

We do not sell to contractors or carpenters in Cook County, Ill.

Rehm Hardware Co.
1501 Blue Island Ave.
CHICAGO, ILL

Wire Window Guards



Counter Railings
Elevator Enclosures
Circular Hand Rails
Staircase and Bronze Work

The Cincinnati Mfg. Co., Cincinnati, O.

RELIABLE FOLDING Scaffold Bracket




Strong and safe; requires only a few minutes to attach. No holes to bore. Four 10-d or 16-d nails fasten them securely. Positively rigid; no vibration.

The Low Price of these Brackets can be saved in time and material on the first two jobs.

ELITE MFG. COMPANY
100 Ohio Street ASHLAND, O.

GOODELL MITRE BOX



MADE OF STEEL - CANNOT BREAK



First in Quality and Improvements. Automatic Steps for holding up saw. Corrugated Backs Graduated. Gauge for duplicate cuts and many other features.

Send for Circular "C."

GOODELL MFG. CO., Greenfield, Mass.



The Disston Tools You Need to Sharpen Your Own Saws

A properly sharpened saw gives the most satisfaction and lessens the amount of labor required in pushing it.

With an equipment of Disston Tools you can do it as well as the professional saw sharpener. Often better, for you have a greater interest in your own tools.

We will send free our "Handsaw Booklet" with complete directions.

THE "TRIUMPH" SAW SET

enables anyone to properly set a saw. It is simple and easy to operate. Complete directions with each one.

THE HAND SAW JOINTER

is necessary to keep all the teeth to a proper and equal height. Cut shows how it is applied.

DISSTON TAPER FILES

give the best results. They cut fast, give a smooth finish to the work, and are the most durable files made.

THE FILING GUIDE

holds the saws in position and guides the file correctly. The most unskilled saw filer can get good results with his guide. Comes in two sizes. The heavy, D3, has 12½ inch jaws, while the lighter guide, D2, has 9½ inch jaws on clamp, and weighs only 7 pounds.




Reg. U.S. Pat. Off.

HENRY DISSTON & SONS
Incorporated

Keystone Saw, Tool, Steel and File Works

PHILADELPHIA, U. S. A.



Patents Pending

IF YOU HAVE NEVER USED SHARON No. 2 PARLOR DOOR HANGERS

Don't fail to try a Set

No Cutting, Grooving or Counter-sinking needed.

Fits any width opening. Simple and always accessible adjustment.


Its smooth, easy, absolutely noiseless running has never failed to please. Money-back guarantee.

Write the
SHARON HDW. MFG. CO. SHARON, PA.

"SYRACUSE" NAIL SETS The Standard for 15 Years

These nail sets are made by experts in fine tool making. The material is selected with great care. Finely knurled body gives firm grip. Points cupped. Every point fully tested on steel. Blued finish. They will stand hard usage.

SYRACUSE TWIST DRILL CO.




3 Sizes—2-32", 3-32", 4-32", points—Price, 10 cents each

Ask your hardware dealer for "Syracuse" Nail Sets. If he cannot supply you, we will send any number you want for 10 cents each. State size wanted.

SYRACUSE, N. Y.

SAMSON SPOT SASH CORD



Samson Cordage Works

--

Boston, Mass.


Made of extra quality stock, carefully inspected, and guaranteed free from the imperfections of braid and finish which destroy common cords so quickly. Samples and full information gladly sent.

WIRE LATHING

The Secret of the durability of the woven wire lathing is owing to the fabric being completely embedded in the mortar, and thus secured from the corrosive action of the atmosphere; and also to the fact that rust will not attack the smooth round wire as it does the thin cut edges of a metal fabric.

"Why not use the proper kind of lath that lasts?"

Before building, write for our Booklet No. 6 A and Prices.



Grimm's Galvanized Corrugated Wire Lathing

"Patent applied for"

Greening's Patent Trussed Steel Wire Lathing

BUFFALO WIRE WORKS CO.,
(Formerly Scheeler's Sons)

BUFFALO,
N. Y.

Send Us Your Plans for Estimates

—ORNAMENTAL IRON—




Iron Stairs
Railings
Balconies
Elevator Enclosures
Fire Escapes
Side Walk Doors
Etc.

OUR PRICES WILL
INTEREST YOU

THE MACK IRON & WIRE WKS. CO.
Sandusky, Ohio

RAILINGS

OF ALL KINDS




Elevator Enclosures and
Cabs, Bank Work, Iron
and Wire Guards.

Miscellaneous
ORNAMENTAL IRON
AND
BUILDERS' IRON WORK

DOW

Wire & Iron
Works

LOUISVILLE, KY.



City Investing Co. Bldg., New York

Another of the Mammoth Modern Buildings
Fitted with

"AMERICAN" Pressed Metal Sash Pulleys

because "Americans" pass the architects' tests for durability, economy, beauty and smooth operation.

"Americans" are made with plain, ball-bearing, and roller-bearing axles.

Face plates are lacquered, plated, or of solid brass or bronze, to match any hardware.


All wheels have combination groove for cord or chain.

Send for catalog.

THE AMERICAN PULLEY COMPANY


Philadelphia New York Boston Chicago

Stocked and sold by dealers.



WHEN WRITING ADVERTISERS PLEASE MENTION THE AMERICAN CARPENTER AND BUILDER

Stanley Tools



Stanley Doweling Jig

A new and most unique tool that will enable the user to bore dowel holes in the edge, end or surface of work with the greatest ease and with absolute accuracy.

A tool that will immediately commend itself to Carpenters, Cabinet Makers, Pattern Makers,—in fact to every artisan or amateur who has occasion to do any kind of doweling.

A postal brings you a special circular containing complete description and showing various forms of work in which the Jig will be found of great assistance.

Address

STANLEY RULE & LEVEL CO.
NEW BRITAIN, CONN. U.S.A.



FIRE—Excitement reigns supreme!
Panic—In a twinkling of an eye.
Exit—The terror-stricken rush.
Door—Though tightly closed—
Bolt—Columbia opens with a gentle push.

Full information upon request.

**The Columbia
Iron & Wire Works Co.**
Canton, Ohio

C. G. HUSSEY & CO.
Pittsburgh, Penna.

MANUFACTURERS
OF


COPPER

In Sheets, Plates, Rolls

CORRUGATED COPPER CONDUCTOR PIPE



Copper Nails, Copper Rivets, Conductor Pipe, Eaves Trough, Elbows, Shoes, Mitres, Soldering Coppers, Gaskets, Etc.



THE MYERS GIANT ADJUSTABLE TANDEM DOOR HANGER

for TUBULAR GIRDER TRACK is adjustable to and from the building, and up or down as necessary. Has flexible engine truck with steel rollers revolving on steel roller bearings. The adjustable features prevent trouble from weather conditions or sagging of building. Storms, sleet or ice do not affect it, owing to complete protection afforded by the tubular track. Track and Hanger are constructed to carry and operate heavy doors easily.

This and other styles of Tubular and "Stayon" Door Hangers are shown in our Door Hanger Booklet. Copy mailed on request.

F. E. MYERS & BRO.
ASHLAND, OHIO



**This Pearson's Automatic
SHINGLE NAILER
WILL PAY FOR ITSELF
ON FIRST JOB**

Do your nailing fast—faster than ever before. You can use this Pearson's Nailer on any pitch roof. Wear mittens, gloves, etc. This "Hand Nailer" is the only Nailer—throw nails in by the handful—then start nailing. Nails easily driven through tin or quite heavy sheet iron.


These nailers are made in two sizes—The BLUE Nailer for 3d. common No. 14 gauge wire nails.

The RED Nailer for 3d. galvanized No. 13 gauge 1 1/4-inch wire nails.

It will come right to your door, quick, by insured parcel post, all prepaid for only \$5.00.

IT MAKES GOOD.

PEARSON MFG. CO. - ROBBINSDALE, MINN.



No. 525 R-W
Faultless Sliding Door Lock


Locks and Latches

One of the most important attachments for the door is the lock.


The door must keep out the weather—the lock the night marauder.

R-W Locks and Latches

They can be used on your contracts with the knowledge they will do their work and protect your clients possessions.



No. 215 R-W Gravity Latch
For Swinging and Sliding Doors



No. 225 R-W Lion Steel Latch
For Medium and Light
Swing Doors

GET THEM AT YOUR DEALERS.

Richards-Wilcox

MANUFACTURING CO.
AURORA, ILL. U.S.A.

A hunger for any door that slides



SAND'S ALUMINUM LEVELS

Will Not Warp

Sand's Aluminum Levels are light, strong and durable. They will not warp, split or rust. Nothing to work loose or get out of order. Easy to handle. Need no adjusting. Made in 18", 24" and 30" sizes for Carpenters and 42" length for Masons. We also make a high-grade line of wood levels.

are honestly made of very high-grade aluminum specially prepared for this purpose. The finish is ideal and the greatest strength is placed where most needed. All unnecessary weight is left out. The plumbs are the best that careful experience can make. Each level is fully tested before it is offered for sale. You can count on Sand's Levels being perfect.

Ask Your Hardware Dealer


to show you Sand's Levels. If he does not sell them let us know and we will send you a circular showing full size view of our 24" Aluminum Level and 1/2 view of the 30". Just like seeing the actual levels.

J. SAND & SON

1027 Rivard St., Detroit, Michigan

Best Level to Use in Dark Places

The plumbs at each end and the double center level make it readable in any position and at arm's length. Pick it up anyway. It is always in position. Vials covered with heavy plate glass which keeps out water, dust and dirt. A Sand's Aluminum Level will last you a life-time.



Hammer Insurance SPECIAL

Our "VANDOR VANADIUM" Nail Hammers in four sizes, No. 21 1/2, 16 oz. Standard; No. 22, 13 oz. General Purpose; No. 22 1/2, 10 oz. Finishing; No. 22 1/2, 16 oz. Ripping Style. We will send either size Parcel Post for your Dealer's name and \$1. This Hammer we insure for life. Made for hard work and lots of it. You can return it any time if it proves defective and get a new one.

This Hammer is warranted to draw anything from a headless brad to a spike.

Drop Forged from the toughest Vanadium Steel. Second growth hand shaved Hickory Handle. Tempered in oil. Easy to work with. Get one today. Remember only \$1 and your dealer's name for either size, 16 oz., 10 oz., 13 oz., or 16 oz. Ripping. Mail your order NOW.


VAN DOREN MFG. CO., INC. Chicago Heights, Ill.
(Vanadium Dept.)

Shultz Corner Posts For Store Fronts

make a strong, handsome and practical joint. They are water-proof and dust-proof and never rot. No putty or filler is used. The glass is bedded on Spanish cork which prevents cracking or crushing. Not expensive.

Write us for description, prices or estimates.

All Steel Corner Post Co., St. Joseph, Mo.




A. STEEL.
B. GLASS.
C. CORK.
D. BRASS.
E. SPACE.
F. SLOT.



Uncle Si Says:

"There's a guarantee that goes with every Simonds Saw that I like to read over now and then. It goes this way: 'If at any time the user of a Simonds Saw finds anything wrong with it, he's got a new saw coming, or can have his money returned. You're the man that's got to be satisfied. You can't own a Simonds Saw and be dissatisfied.' Pretty plain English, isn't it? But then the Simonds is so good that it can stand a strong guarantee like that. You know where they sell them, don't you?"

Ask your Dealer. If he hasn't got a Simonds Saw, we will send you one for \$2.50, delivery charges prepaid. 26-inch Saw, Cross-cut or Rip, any number of points. Taper ground crucible steel blade. Carved and polished apple wood handle. Absolutely guaranteed against any defect whatever. Money back if not satisfactory. Try it



SIMONDS MANUFACTURING COMPANY
FITCHBURG, MASS.

17th St. & Western Ave.
CHICAGO, ILL.

40 Murray St.
NEW YORK CITY

SARGENT

Other Sargent Quality Tools are described in the Sargent Tool Book, a handbook for mechanics sent on application.

No. 53.

A light floor or veneer Scraper with wood face to lessen friction.

A useful and convenient tool, low in price.

For full description of this and other

SARGENT WARRANTED PLANES
SEND FOR SARGENT PLANE BOOKLET

SARGENT & COMPANY

Makers of Squares, Planes and Mechanics' Tools

1149 Leonard St. New York



Cash Prizes for Personal Experience Letters About EXTRA PROFITS

THERE are many ways in which carpenters and builders pick up considerable money "on the side." There are any number of popular building novelties and pieces of modern equipment for buildings that are being sold by carpenters and builders. Hustlers in the building field secure the agency for such building specialties and find it no trouble at all to work up a nice little business in connection with their regular building work.

We believe that a good many more of our readers might just as well be picking up these extra profits. Of course, conditions are not the same in all localities; but almost everywhere a wide-awake man can find sale for some of the special lines announced in our advertising pages.

New Department

We want to begin a new department next month under the illustration heading shown at the right, "EXTRA PROFITS, How Builders Make Money on the Side." We want to hear from all of our readers who have been handling agency propositions in connection with their building work. We want brief, straightforward letters that tell actual facts. Give us your personal testimonials about the way the agency business

goes and also what effect it has on your regular building work. All letters must be signed, but names will not be published if requested not to.

For the best letter each month we will pay \$10.00 (in goods selected from our advertising pages); also \$1.00 (in advertised goods) for every other letter published.

Study through our advertising pages and note the variety of interesting offers for carpenters and builders to act as local agents. There seem to be good opportunities for profits in connection with each of the following:

Extra Profits

How
Builders
make
Money
"On the side"



Dumbwaiters	Wall board
Store Fronts	Floor finishing
Ventilators	Steel roofing
Skylights	Waterproofing
Silos	Door and window screens
Furnaces	Lighting systems
Bath room outfits	Lightning rods
Vacuum Cleaners	Detachable hinges
Coal chutes	Keyless locks
Metal ceilings	Shinglers chairs
Metal shingles	Clothes driers
Weatherstrips	Pope corn machines
Wood mantels	

We would like to hear from builders who have had experience in handling any of these. Your advice and encouragement may be worth many dollars to other builders. Address EXTRA PROFITS Editor, American Carpenter and Builder, Chicago.

Contents for August 1914

	Page		Page		Page
Acceptance of Building—Forced Occupancy	43	Kinks, or a Few Tricks of the Carpenters' Trade Learned by Experience	72	Power Bungalow Builder on Wheels	40
Acoustics of Auditoriums	64	Large Tobacco Barn	85	Practical Carpentry	72
Adventures in Heating	76	"Liquidated Damages" or Penalty—Proportion of Sum of Stipulated to Actual Damage	43	Public Buildings	69
Behavior of Sound Waves in a Room	65	Loads on Roof Trusses	48	Reasonable Demands	37
Building Contract—Extra Work	42	Machine Woodworking	78	Revolving Damper Solves Ventilating Problem	63
California Bungalow	54	Methods Employed to Improve the Acoustics	67	Sawing Trim to Length	72
Cement Building Construction	51	Methods of Improving Faulty Acoustics	66	Shingled Gothic Church	85
Chute with Reservoir Helps Concrete-ing Gang	39	Modern School at Benton, Ill.	69	Significant Work in Trade School Education	68
Correspondence	80	More Light from B. Gonne	83	Simple Bookkeeping System	85
Court Decisions Affecting Builders	43	More Shop Kinks	78	Sliding Door Jambs	80
Crooked Line Shaft	71	Mortising Door Frames for Hinges	72	Something About Porch Building	81
Depth Gage for Saw	72	Mosaics in Cement Surfaces	51	Steel Square	70
Duty to Follow Specifications	43	Nailing Without Splitting	72	Terra Cotta for Modern Store Fronts	74
Echoes and Their Remedy	67	Neat Corner Joint for Mouldings	72	Terra Cotta Talks	74
Editorial	37	Neat Six-Room Story-and-a-Half Cottage	56	Three-Room Honeymoon Cottage	53
Five-Room Bungalow	58	Noon Hour Talks by the Boss Carpenter	48	To Save the Flagpole	82
Framing Hood Rafters	70	Novel Plan for Raising a Roof	82	Trade Notes and Items of Interest	86
Guaranteed Building Plans	53	Old Time Woodwork	83	Trouble with Leaky Hinged Windows	82
Laying Out Stair Winders	73	Out-Door Sleeping "On the Roof"	61	Troubled with Sweating Plaster	81
Handling Work to Advantage	39	Panama-Pacific International Exposition	44	U. S. Supreme Court Places Responsibility for Contract Statements	38
Heating and Ventilating a School Building	76	Photographic Record of Present State of Building Progress at the	43	Urge Fire Prevention	38
Helps to Bigger Business	40	Plea for Thoroughness	73	Nailing Guides on Stair Stringers	73
Improper Construction—Liability	43	Plan Shop	60	Well Planned House for a Narrow Lot	60
Is Serious About Bungalow Finishing	81			What is the Best Thing to Do?	84
Keeps Copies on Drafting Table	80			Which is Right?	80
				Yours for Safer Building	48

CHICAGO

SPRING BUTTS

REPUTATION

Do you specify a spring hinge with distinctive features which will appeal to your client and assure satisfaction to all concerned?



Chicago "Relax" Spring Hinges

are in great demand. They are substantial in construction and readily applied. The EXCLUSIVE FEATURE of spring action release, allowing the door to be placed at any desired position and automatically re-engaging when the door is closed,

is of recognized merit and utility.

Send for Catalogue C 29. It fully illustrates and describes the most complete line of Spring Hinges manufactured.


Chicago Spring Butt Company

CHICAGO




NEW YORK

Yes! the World does Move!
Facts are Stubborn Things



Don't Buy
SPRING HINGES
OF
OBSOLETE
CONSTRUCTION
ONLY



BOMMER


Double Acting **Spring Butt Hinges**

have the weight-supporting bearings correctly located to liberate the action of the springs, reducing breakage and increasing spring power, preventing unequal wear of the barrels, and giving practically unlimited durability. Bommer double-acting spring hinges open alike at both casings and both doors when both doors are opened.

The carpenter can avoid guesswork and save time when hanging double-acting doors in pairs, as he can scribe and fit both doors of a pair from the same side of the opening.

YOUR HARDWARE MERCHANT CAN SUPPLY THEM
Bommer Bros., Manufacturers Brooklyn, N. Y.

Cabot's Sheathing and Deadening Quilt



The Cold-proof, Heat-proof, Sound-proof and Fire-retarding Lining

"Quilt" is a matting filled with dead air spaces, and one layer is as warm as twenty-eight layers of common building paper. A house lined with it will always be warm and save coal. Floors and partitions lined with it will stop the passage of sound. Roofs lined with it will keep cool

in summer and prevent heat from escaping in winter. It will save coal enough to pay for itself every two winters as long as the house stands.

Send for a sample and catalog.

SAMUEL CABOT, Inc., Manufacturing Chemists, Boston
24 W. Kinzie St., Chicago - 1133 Broadway, N. Y.

Cabot's Creosote Shingle Stains; Stucco and Brick Stains,
Conserve Wood Preservative.


No
Guess Work
with a
MORRILL SAW SET

Simple and accurate. The only Saw Set a carpenter should use. Takes out the wrong set and puts in the right set at one operation.

The eccentrically beveled anvil is so indexed that you can see what you are doing. Gauge screw and locknut keeps work uniform.

FREE "Saw Points" a valuable Booklet.


Chas. Morrill, 94 Lafayette Street
NEW YORK



METALLIC BATTEN STRIPS

PRACTICAL—EVERLASTING—ECONOMICAL

These Batten Strips of Galvanized Metal will never warp, split, or draw away from the boards. Offer no obstruction to sliding doors. Allow for expansion and contraction of the siding. Made in 8-foot and 10-foot length with interlocking joint. Easily cut; no waste. Nailed directly to siding with small nails.



End view showing joint closed. A perfect fitting Batten at all times, in all weathers. Beautifies any building.



End view showing joint open. Provides for expansion or contraction of the siding so nails will not work loose.

Metallic Batten Strips make strong, neat joints. They make the building wind-proof, weather-proof and rat-proof. Also valuable for lining grain bins or wagon boxes.

Write for Free Sample and see for Yourself

METALLIC BATTEN COMPANY

Owensville, Indiana

AUG -7 1914

©CL8307052

Copyright 1914 by American Carpenter and Builder Company



The
**World's Greatest
Building Paper**

Important Notice

When your subscription expires, renew at once, using the blank enclosed in your final copy. If it expires with this issue your renewal must reach us before August 25, to avoid missing the September number. Use P. O. or Express Money Order if possible, but bills or 2-cent stamps may be sent at our risk.

The
**World's Greatest
Building Paper**

American Carpenter and Builder

Entered as second-class matter July 1, 1905, at the postoffice at Chicago, Ill., under the act of Congress of March 3, 1879.

Published on the first day of each month by

AMERICAN CARPENTER AND BUILDER COMPANY
RADFORD BUILDING, 1827 PRAIRIE AVE., CHICAGO

EDITORIAL DEPARTMENT

WILLIAM A. RADFORD, *Editor-in-Chief*
BERNARD L. JOHNSON, B. S., *Editor*
WILLIAM REUTHER } *Associate*
ADRFED W. WOODS } *Editors*
ALFRED S. JOHNSON, M. A., PH. D.
CHARLES E. PAUL, S. B.

BUSINESS DEPARTMENT

WM. A. RADFORD, *President and Treasurer*
E. L. HATFIELD, *Vice-President and General Manager*
ROLAND D. RADFORD, *Secretary*

New York Office: 345 Fifth Ave.
E. B. WOLFROM, *Eastern Representative*

SUBSCRIPTION RATES

One year, \$2.00; six months, \$1.00; payable always in advance. Single Copies, 20 cents. Canadian Subscriptions, \$2.50. Foreign Subscriptions, \$3.00.

ADVERTISING RATES

Furnished on application. Advertisements, to insure insertion should reach our Chicago office not later than the 20th of the month preceding date of publication.

PROTECTION FOR OUR READERS

The publishers of the American Carpenter and Builder will not knowingly publish any advertisement of a misleading character nor accept advertising from any individual, firm or company whose business methods are open to question.

We often receive inquiries from readers who desire information about concerns that formerly used the advertising pages of the American Carpenter and Builder, but are no longer doing so. They want to know if these former advertisers are still in business, if they can send them orders with the assurance that they will be filled, and a variety of other questions.

The American Carpenter and Builder will use every legitimate means to safeguard the interests of its readers and to protect them from fraudulent or unreliable concerns. Where the slightest doubt exists our readers should write the publishers for information. It may save them money, time and worry.

In all cases in writing to advertisers say: "I saw your advertisement in the American Carpenter and Builder."

VOL. XVII

AUGUST, 1914.

No. 5

Reasonable Demands

FOLLOWING is the accepted report of a committee appointed by the Carpenter Contractors' Association of Chicago to formulate and recommend changes in all building specifications under head of Carpentry.

The Chicago association has mailed this report to every local architect, asking that the same receive the hearty co-operation of the specification makers. The carpenter contractors feel that certain items generally contained in the carpenter's specifications should be eliminated or adjusted as follows:

- No. 1. Broken glass is specified to be paid pro-rata by the carpenter. Should be eliminated.
- No. 2. The patching of plaster by carpenter should be eliminated.
- No. 3. The protection of cut stone shall be specified so that the responsibility of the carpenter contractor ceases after covering same, and anyone removing covering be held liable for the damage thereto.
- No. 4. If carpenter is required to furnish watchman, specify time services of said watchman are required.
- No. 5. The delivery of hardware and responsibility of same shall be limited to the delivery of

boxes and cases, but no responsibility is to be assumed by the carpenter for contents thereof.

- No. 6. Priming of frames should be eliminated from carpenter's specifications as factories refuse to prime frames.
- No. 7. Lumber for bracing of iron will not be furnished by carpenter.
- No. 8. Carpenter will not clean the rubbish of other contractors.
- No. 9. Setting of iron should be eliminated from carpenter's specifications.
- No. 10. The carpenter contractor will not furnish any labor or material for work that is required and not specified or shown on plans, but necessary to complete the job.
- No. 11. The carpenter shall not be held liable for any damage to finished floor by other trades.
- No. 12. Carpenter will not be responsible more than 30 days after completion of building for fitting of doors, locks, or windows, caused by the settling of walls or joists and swelling or shrinkage of woodwork.



NO sharp bargains—do more, not less, than promised.—*Andrew Carnegie.*

U. S. Supreme Court Places Responsibility for Contract Statements

THE discussion of contract provisions oppressive to contractors has received a valuable addition from the Supreme Court of the United States in its recent opinion in the case of *Hollerbach & May*, where William B. King, of King & King, Attorneys, Washington, D. C., who is a member of the National Association of Builders' Exchanges, so successfully represented the contractor.

The Government called for bids for repairing an old dam on the Kentucky river. *The specifications said that the old dam was backed with broken stone, sawdust and sediment.* When the contractors did the work, it was found to be backed with *sound cribwork, filled with stones!* The removal of this cost far more than the removal of broken stone, sawdust and sediment would have cost. The contractors sued for this difference.

The Government relied for its defense on general cautionary clauses in the specification, saying that bidders must visit the locality, make their own estimate of all difficulties and contingencies, ascertain the nature of the work and obtain the information necessary for an intelligent proposal. The contractors responded that they were excused from doing this in regard to the backing of the dam, because the specifications told them exactly what would be found there and that they had a right to rely upon the statements on that subject in the specifications.

The Court of Claims agreed with the Government's contention. The Supreme Court took a view more liberal to the contractors. It said that the specifications unequivocally asserted what would be found behind the dam and that the contractors had a right to presume that the Government spoke with knowledge and authority. "We think this positive statement of the specifications must be taken as true and binding upon the Government and that upon it rather than upon the contractors must fall the loss resulting from such mistaken representations." Accordingly, judgment was given against the Government for the excess costs incurred by the contractors.

The decision is of general importance, because many contractors, particularly for foundation work, sewers, or plumbing, sign contracts stating particular facts in positive terms. When more costly conditions are found to exist, the contractors are told that these representations of facts are not binding on the owner because somewhere else in the specifications the contractors are told to be on their guard against everything. This decision of the Supreme Court answers this position. *It says that the contractors have a right to assume that positive statements in the specifications are true and, if not true, that the burden does not fall on the contractor, but on the owner, government, municipality or individual, which has misrepresented the facts.*

If contracts and specifications were properly drawn, the responsibility for local conditions should always fall on the owner. He furnishes the place for the work. He should state definitely what the conditions are for doing the work. He should not expect the contractor to gamble on these conditions. This decision is in line with enforcing a proper responsibility on the owner.



Urge Fire Prevention

THERE are many ways in which builders can fight the fire fiend. One of the most effective is to be thoroughly familiar with the approved fire prevention principles and to advise all who will listen—customers or prospective customers—telling them what to take care about, that their property may be safe.

While some building materials are unquestionably more fire-resisting than others, the important thing is really not so much what building materials are used, as how they are used. A building may itself be absolutely fireproof and yet its contents be under great danger from fire. A fireproof authority has likened such a building to a cast-iron stove. It cannot itself burn up, but the contents burn readily.

The National Fire Protection Association, through their fire prevention committee of which Mr. Powell Evans is chairman, has been doing a very praiseworthy work in instructing the public as to common sources of fire danger and how these should be guarded against.


A circular letter sent to all of the hardware dealers who are members of the National Hardware Association, signed by W. D. Taylor, president of the association, and by Mr. Evans, contains the following paragraphs:

Exposure Hazard: This danger from surrounding property is a heavy charge in every average city insurance survey and rate amounting often to one-third of the whole charge. Study your location and your exposure hazard thereon and the reasonable means of bettering your own property (such as fireproofing doors and windows and outside walls, extending fire walls above the roof, noncombustible roofs, etc.), so as to minimize this physical exposure hazard and consequent insurance rate.

Construction: A large part of your insurance survey and rate is always based on deficiencies in physical construction of your property. Study this (such as unprotected vertical and horizontal openings, too large areas undivided by fire walls, concealed spaces, etc.), and ascertain how they may be reasonably remedied, and how such improvements will reduce your insurance rate.

Protection: The best located and constructed property in the world without adequate fire alarm and extinguishing facilities on the average ultimately suffers undue fire waste, either in buildings or contents or both. A cast iron stove won't burn but it is burning up contents constantly. Study the deficiencies.

Management: Keep your property clean. Half of all American fire waste comes from careless accumulation of dirt and rubbish and disorder. Teach your people cleanliness and order and organize them to detect and extinguish fire and how to call the public fire department quickly when necessity requires.



HANDLING WORK TO ADVANTAGE

Labor-saving
arrangements
of power on the job

Important! Cash for YOUR Way!

This new department belongs to our readers. We invite you to fill it up with brief illustrated descriptions of the little labor saving tricks and methods you are using in connection with your concrete mixing, power hoisting, portable saw rigs, etc. Furnish us a little pencil sketch or photo with each letter if possible.

We want this department to be extra practical and interesting; and to make it more exciting we will pay \$10.00 (in goods selected from our ad pages) for the best letter each month; also \$1.00 (in advertised goods) for every other letter published. Address LABOR SAVING Editor, American Carpenter and Builder, Chicago.

Chute With Reservoir Helps Concreting Gang

INSPECTION OF A CLEVER LITTLE RIG IN USE BY CONTRACTOR VAN DER HORST, KALAMAZOO, MICH.

WE observed a worth-while idea the other day that was working out well on the new Science Building job at the Western State Normal, Kalamazoo, Mich. The building site was leveled on the top of a hill of clean sand and gravel; the excavated material thrown up in a big pile just outside the foundation wall. On top of this pile Contractor Van Der Horst placed his concrete mixer and built a chute or trough of planks from the discharging end of the mixer down to the foundation wall. The lower end of the trough was given extra depth to form a reservoir to hold about

enough concrete to fill two of the wheel carts.

The mixing gang, up above, work right along at their own gait, discharging the slush concrete into the trough where it flows down into the reservoir at the bottom. A man stationed below opens and closes the lift gate as the wheel carts are brought up to be loaded.





Diagram Showing Mixing Plant with Gravity Trough for Slush Concrete in Use at Western State Normal Science Building Job, Kalamazoo, Mich.

With this arrangement, four two-wheel carts are kept going, with no time lost waiting. The concrete mixer can run continuously, and gravity does a share of the work.

It impressed us as a good labor saving arrangement worth using wherever the concrete mixer can be placed above the level of the place where the concrete is to be deposited.



Power Bungalow Builder on Wheels

HOW I RIGGED UP A POWER WOODWORKING OUTFIT THAT IS AN EXTRA STRONG AD FOR MY BUSINESS—PAYS FOR ITSELF ON EVERY JOB

By W. S. Weaver

Builder and Contractor, Alhambra, Calif.

IN this part of California, building is mostly frame, and there is considerable cutting to be done on the job—due to the varied architecture of the classy bungalow designs, with their irregular roofs and porches.

I conceived the idea of building a portable saw that would be convenient as an office and store room as well as an advertisement. I bought a low four wheeled truck with wide rimmed iron wheels and on the platform of this I built an amateur bungalow with a flat, white asbestos roof. The sides I covered with shakes and shingles, using casement windows on three sides

nailed thereon to give the appearance of casement windows.

In Fig. 1 the mill is shown on the job, ripping a piece of 6 by 6-inch Oregon pine, showing the piece fed through the saw from the doorway and taken out through the window at the other end. In this photograph the reader can get a good idea of a southern California home, with flat roofs, which are covered with asbestos or sand coated roofing paper.

Fig. 2 shows the machine sawing studs. The material is handed in through the window opening on one side. With the aid of a gauge and platform they are




Fig. 1. Contractor Weaver and His Power Bungalow Builder on Wheels at Work on a Typical California Home Building Job.

and a pair of shutter doors on the rear, which are hinged top and bottom and made to swing out—the lower half being used as a platform or approach to the saw and the upper half forming a canopy supported by two braces.

The windows swing outward and are hinged at the top, in the same manner as the doors, which allows long material to be ripped and cut off without reversing the pieces.

In place of glass on the windows, galvanized iron was used so as to resemble glass with the muntins


sawed to the proper lengths and shoved out through the window opening on the other side, ready for use. After all the studs are cut the gauge can be set for cripples, trimmers, fire blocks or bridging, most of which are cut out of the scrap heap.

Rafters may also be cut, one end for the plumb-cut and the piece reversed for the show-end cut. It is very convenient in cutting out flare-out pieces—which are usually cut out of 1-inch stock, 4 inches wide at one end and tapering to a point and from 1 to 2 inches in length.



PORTABLE WOODWORKING SHOP FOR BUNGALOW BUILDING.

Fig. 2. W. S. Weaver, Contractor and Builder, Alhambra, Calif., has Enclosed His Portable Power Saw Rig in a miniature Bungalow—A Good Advertising Stunt for Him as He Builds Many Bungalows. The House is on Strong Iron Wheels. One side of the House Opens for a Doorway and the other Three Sides have Hinged Windows. Material can be Worked Through from any Direction to the Saw Table.



BUNGALOW IS BIG ENOUGH FOR CONSIDERABLE STORAGE AROUND MACHINE.

Fig. 3. Close-Up View of Shop Interior, Showing Saw Rig, Gasoline Engine, etc. The Building Locks Up Tight and Safe so that the Machinery is Protected from the Weather as well as from Vandals.

There are a thousand various pieces which can be sawed with an outfit like this. I am positive all builders appreciate this without my describing it in finer detail.

Fig. 3 shows the makeup of the machine in the interior. The power is a Fairbanks-Morse, three horsepower gasoline engine, direct drive. The saw is a combination rip and cut-off and is operated back and forth by a foot lever. When the rip saw is used the mandrel is held up in place, stationary,

All in all, Bro. Weaver proves himself a good business advertiser. His portable power plant, with its attractive housing, is one of the best business producing ideas for builders we have ever seen. Perhaps, though, you can beat it. What is your way of getting the public eye and so building a bigger business? We will be glad to pass along all good ideas for the benefit of other builders.—
EDITOR.

an Overland car, with which I pull the outfit from job to job.

Our city recently celebrated its anniversary in the way of a carnival, inviting commercial and industrial floats to take part in a parade. I entered my bungalow mill.

A double shaft was fastened to the mill after it was stripped of the machinery and a pergola was added to the front end as a place for the driver to sit in. I cut rose bushes and tied them on each side, which gave it a homelike appearance. I




Fig. 4. Contractor Weaver All Ready to Get Onto a New Job in a Hurry. His Auto has Side Brackets for Carrying Lumber and the Bungalow Power Woodworker Fastens on Behind. The Windows in the Little Bungalow are Galvanized Iron which Resembles Glass.

by a steel peg. The table is adjustable so as to regulate the depth of the cut.

The narrow belt shown on the right of the engine drives an emery wheel stand with a coarse and fine carborundum wheel, which I find saves lots of time and otherwise hard grinding for the boys, especially after chopping off 20d. nails with their hand axe, or when the mice get after their chisel edges.

There are shelves erected on the inside of my bungalow-workhouse-on-wheels for nail kegs and tool boxes, so they are always under cover as well as locked up at night. (There are always quite a few nails liable to crawl away into somebody's chicken coop or fence, when the nails are not locked up.)

Fig. 4 shows a row of three bungalows which the mill helped to turn out. An idea may be had of the fine wide streets and artistic lamp posts, front lawn and shrubbery that every one here prides himself in keeping up.

In this figure the reader can get an idea how the mill is used as an advertisement. Its nifty appearance causes lots of curiosity and amusement and talk.

This figure also illustrates the convenience of an auto in the contracting game. There are two brackets arranged on the side of the car on which I carry material to and from the jobs, which means quite a saving in time and economy by saving scraps for the next job. The mill is hitched to a bracket bolted to the frame of

was awarded a prize of \$25, which helped some toward the original expense of the outfit, and has been paying for itself ever since.

I hope this article will be received with as much appreciation as it is given and should any reader desire more information regarding wood workers on the job I will be glad to give it if possible.



Building Contract—Extra Work

A building contractor had a written contract for the construction of a building, which contained no provision for extra work. Payment was to be made on full completion. The contractor did not complete the contract. He had, under the owner's express orders, performed certain extra work entirely outside of and independent of the contract. In an action to foreclose a mechanic's lien for the balance claimed to be due it was held that no recovery could be had under the contract, but the extra work done did not come within the provision of the contract as to payment upon full completion, and the plaintiff was entitled to recover therefor. *Mitchell v. Dunmore Realty Co.*, 156 App. Div. 117, 141 N. Y. Supp. 89.



Miss Elderby—"Do you really think that women propose?"

Oldbach—"If they don't there are many marriages I cannot account for."

COURT DECISIONS AFFECTING BUILDERS

Mr. John Simpson, a well known legal authority, has been engaged to set forth in plain English certain important points of law that concern Builders. He will also through this department answer legal questions for Our Readers.—Editor.

Duty to Follow Specifications

In an action upon a building contract the owner counterclaimed for damages because of defective cement work. The specifications exacted that the floors of the first and second stories and of the hall to the third story of the building

"be furnished on top with a top dressing three-fourths inch thick put on at the same time as the body of the floor and composed of two parts of Chicago A. A. cement to one part of fine sand and one part of crushed and powdered marble dust or limestone. There is to be a cement base 3 inches high to project $\frac{3}{4}$ of an inch from plaster above and to be put in place by the concrete floor contractor at the same time and of the same materials as the topping . . . The lower section of each mackolite partition is to be put on first directly on the body of the floor, and the base then brought upon this."

The contractor contended that this method of construction was impossible of performance. The court was not satisfied from the evidence that this was impossible. Doubtless it would have been difficult, especially in the winter season, but this furnished no excuse for noncompliance with what had been agreed upon by the parties, nor did the oral assent of the architect justify performing the work in a different manner. The contract provided that there should be no changes in the specifications or drawings, and no deviations without the written consent of the architect, and that no alteration should be made except upon a written order of the architect, with amount of cost thereof. It was held that the architect's authority was limited, and that he could not direct the work to be done otherwise than as provided by the plans and specifications, except as authorized by the owner, nor relieve the contractor from following the specifications, so that the contractor, having followed a new plan in accordance with the architect's oral permission only, was liable for damages caused by the breach. *Volquardsen v. Davenport Hospital*, Iowa Supreme Court, 141 N. W. 432.

Acceptance of Building—Forced Occupancy

The owner of a building in course of erection who is forced by circumstances, as by the expiration of the lease of the premises then occupied by him, to occupy the building before its completion does not thereby accept it. *Japes v. Harmon* (Mich.), 141 N. W. 595.

"Liquidated Damages" or Penalty—Proportion of Sum Stipulated to Actual Damage


When a building contract stipulates for payment of a penalty of a specified sum per day in case of delay in completion, is that sum recoverable by the owner in case of delay, or only the actual loss sustained by the delay? There does not appear to be a satisfactory hard and fast rule laid down by the courts to govern this matter. If the damages are in their nature uncertain or incapable of being ascertained, the sum specified as a penalty will be treated as fixing by stipulation the amount of the recovery. But the difficulty arises when the damages can easily be ascertained. The principle would appear to be that if the sum named as "liquidated damages" (as opposed to actual damages) is so near the actual damages that it may be presumed to have been fixed upon as fair compensation for the loss to be sustained, that sum will be held to be the damages recoverable. But if the stipulation greatly exceed the actual loss, the actual damages should be the measure of the recovery. For example, a building contract stipulated for the payment by the contractor of \$20 per day for delay in completion after a certain date. The owner claimed, under the contract, \$3,468. The evidence showed that the loss sustained by the owner in being deprived of the use of the building was easy of ascertainment, and that the rate of \$20 per day was out of all proportion to the loss sustained. It was held that the provision was properly treated as a penalty and only actual damages, amounting to \$1,491, were allowed. *First Nat. Bank v. Smith* (Tex.), 100 S. W. 311.

Improper Construction—Liability

A subcontractor for the cut stonework of a building, in an action for the contract price against the general contractor, claimed that when he was nearly finished with his contract he was interfered with by the architect and prevented from finishing the work. A portion of the front wall was, under the architect's order, torn down and rebuilt by another contractor, and the general contractor claimed that the cost of this was chargeable to the plaintiff. The latter maintained that he was without fault in the matter, and that the trouble arose from the fact that the general contractor gave him the wrong line upon which to locate the wall. It was held that the trial court properly instructed the jury that if the plaintiff was at fault in locating the wall, or in putting up the stonework, then the contractor and owner were justified in having the wall taken down and rebuilt at the plaintiff's expense. But if they found as a matter of fact that the line as given to him was improperly located, then he was not responsible for that mistake; and, if the jury found that otherwise the work of the plaintiff was properly performed, he was entitled to recover. The jury found for the plaintiff. *Shoemaker v. Riebe*, Pennsylvania Supreme Court, 88 Atl. 662.

Photographic Record of Present State of Building

Photos Copyright 1914 by the Panama-Pacific International Exposition Co.



The "Dome of Philosophy," the main western entrance of the Palace of Education. The entrance is 113 feet in height and its interior vault is richly decorated with mosaics. The large central dome of the building seen on the left is 160 feet in height and 100 feet in diameter.




The forecourt or opening of the "Court of the Four Seasons" upon the esplanade along San Francisco harbor. On the left is the Palace of Agriculture; on the right the Palace of Food Products.



South facade of the Palace of Education. The Three portals shown in the photograph are studied from the Italian Renaissance. The tympanum within the arch of the central main doorway will be decorated with a bas relief by Gustave Gerlack.




The Palace of Food Products, upon the left, and Education upon the right, which show the half-domes known as the Domes of Vigor and Philosophy, respectively, which constitute the main entrances to the palaces. The half domes are each 113 feet in height.



The south entrance to the Palace of Food Products opening on the approach to the "Courts of the Four Seasons."




A View of San Francisco Harbor Glimpsed Between the Palace of Varied Industries Upon the Left and the Palace of Machinery on the Right.



One of the West Entrances of the Palace of Machinery. This Building in Architectural Composition is Roman and the Designer has been Influenced by His Study of the Old Roman Baths. The Decoration is Classic in Form but Modern in Expression and Suggestive of Machinery and Invention.


All Photos Copyright, 1914, by the Panama-Pacific International Exposition Co.



The largest building ever devoted to a display of plants and fruits. It is the Saracen type of architecture, modeled after the palace of the Sultan Ahmed, and constructed almost wholly of glass and steel. The great crystal dome, 152 feet in diameter and 185 feet high, is the largest hemispherical dome in the world.



One of the south entrances of the Palace of Education. The exterior finish of the Exposition buildings is in imitation Travertine marble and the old ivory shade of this material is the key color of the buildings and grounds. The composition used in this exterior finishing is a specially prepared gypsaum product.



One of the small southern entrances of the Palace of Varied Industries. There are three principal entrances upon the south, the central one a replica in part of the great portal of the Hospice of Santa Cruz at Toledo, Spain.



Noon Hour Talks by the Boss Carpenter

Talk No. 25—Loads on Roof Trusses

THE BOSS TELLS HOW TO DETERMINE THE AMOUNT OF LOAD CARRIED BY A GIVEN ROOF TRUSS AND EXPLAINS HOW TO DISTRIBUTE THIS LOAD OVER A TRUSS FOR USE IN CALCULATIONS

"YOU will remember," said the Boss, "that during the last two talks we have used imaginary loads on our roof trusses when we constructed the stress diagrams for same. Last time I told you that I would show you how to find the values of actual roof loads and ceiling loads such as you will meet in practice. Of course, these loads will vary in different instances and will depend upon the material from which the roof covering is made, kind of ceiling, and upon the material of the truss itself.

"Fig. 14 will show the general method of roof framing where the king post truss of Fig. 13 is used. As you will notice, the rafters are supported by purlins which rest upon the joints of the upper chord of the truss. These purlins extend along the length of the building from truss to truss and serve as a means of holding the roof in position. Thus, the weight of the sheathing and roof covering which is placed on the rafters will be carried directly to the joints of the truss for support. This is as it should be and is shown in Figs. 12 and 13 of Talk No. 24.

"In order to determine the amount of load which is carried at the different joints of the upper chord, we consider that each purlin carries to a joint an amount of load equal to the weight of a panel of roof extending half way between trusses on either side of the truss in question and half way between joints on each side of the joint in question. The dotted lines in Fig. 14 show two of the sides of the panel of roof which is supported at the joint A. The other two sides would be half way between the truss shown and the neighboring truss on each side. For instance, if the trusses in this building are spaced 12 ft. apart along the walls of the building, and if the joints of the upper chord are 10 ft. apart, then the joint A would support the weight of a panel of roof 12 ft. long and 10 ft. wide.

"Since the weight of the truss itself must be taken into consideration, it is common practice to determine by a formula the estimated weight of the truss and divide it into as many parts as there are joints in the

upper chord less one. One of these parts is divided again into two equal parts and allowed to act at the extreme ends of the truss. These loads are in addition to the panels of roof already referred to. The end joints of a truss support the weight of a half panel of roof referred to above as well as the half joint load due to the weight of the truss.

"Ceiling loads are determined in a similar manner. That is, in Fig. 14 each joint of the lower chord would be considered to support the weight of a panel of ceiling of a width equal to the distance between centers of panels on each side of the joint in question and of a length equal to the distance between the centers of the spaces between trusses on each side of the one in question. As in the above example, the width of the ceiling panel for the joints of the lower chord, if they are 9 ft. apart, would be 9 ft. and the length 12 ft. on account of the spacing of trusses.

"It now remains to see in any given case what the weights of these panels and ceiling are and to determine the weight of the truss itself if possible. The following table will show you fair values for the weights of different kinds of roofing materials:

WEIGHTS OF ROOFING MATERIALS			
	Weight in Pounds per Square Foot		Weight in Pounds per Square Foot
Asphalt on felt, without sheathing....	2	Sheathing, yellow pine, 1-in. thick	4
Ceiling, ordinary lath and plaster	6 to 8	Sheathing, white pine, 1-in. thick	3
Ceiling, stamped steel	2	Shingles, wood, cedar, 1½	
Ceiling, wood, ¾-in. . .	2½	Shingles, wood, cypress 2½	
Composition, 3-ply... 1		Shingles, metal, tin, painted	1
Concrete, per 1-inch thickness of slab... 13		Shingles, metal, copper	1½
Copper, sheet	1 to 1½	Skylight, glass, 3/16 to ½-in. with frames	4 to 10
Felt, roofing, two layers	½	Slate, 3/16 to ¼-in. . .	7 to 9
Gravel and felt, without sheathing....	8 to 10	Slate, diminishing courses	12
Iron, corrugated, No. 18	2½	Steel, standing seam..	1
Iron, corrugated, No. 20	2	Tar and gravel, 4-ply. 5½	
Iron, corrugated, No. 24	1½	Tar and gravel, 5-ply. 6	
Iron, flat, galvanized. 1	to 3½	Tiles, corrugated....	8 to 10
Lead, sheet	4 to 8	Tiles, flat	15 to 20
Sheathing, hemlock, 1-in. thick	2	Tiles, Ludowici....	8
Sheathing, spruce, 1-in. thick	2	Tiles, on concrete slabs	30 to 35
		Tiles, pan	10
		Tin, on felt	1
		Tin, without sheathing ½ to 1	
		Zinc, sheet	1 to 2

"The above table will give weights of roof covering and sheathing. The weight of rafters and purlins

will have to be figured separately and added to the weights given above. An easy way to do this is to determine the number of board feet of lumber in the panel of roof supported by one joint and reduce this quantity of lumber to pounds by the use of the table given below:

AVERAGE WEIGHT OF TIMBER			
	Pounds per Cubic Foot		Pounds per Cubic Foot
Ash	42	Pine, Norway	36
Chestnut	41	Pine, white	25
Hemlock	25	Pine, yellow, Northern ..	34
Hickory	53	Pine, yellow, Southern ..	45
Maple	49	Spruce	25
Oak	32 to 48	Walnut	48

"To find the weight of a board foot of these materials divide the weight given in table by 12.

"A rule for finding the number of board feet in a given piece of timber is as follows: Multiply the end dimensions together, divide this product by 12, and multiply this answer by the length of the piece in feet. Thus, a 2x12-in. timber 16 ft. long would con-

$$\frac{2 \times 12}{12} \times 16 = 32 \text{ board feet.}$$

"In determining the weight of the roof truss itself it is necessary to approximate this quantity at the start and then check up on it later after the sizes of members have been determined. The most complete investigation of this matter is that made by M. Clifford Ricker, results of which are given in his treatise entitled 'Design and Construction of Roofs,' from which the following is quoted:

"The weight of the truss varies with its span and rise, with the distance between centers of adjacent trusses, and further with the intensity of the snow and wind loads, that must be supported by the roof.

"The formula here given results from the careful designing and calculations of the actual weights of a large number of trusses of longleaf pine and steel rods,

for spans increasing from 20 to 200 feet, for rises from 1/10 to 1/4 the span, and for distances between centre planes of trusses increasing from 10 to 30 feet. It may therefore be assumed to approximate the actual weights of roof trusses within the given limits, required to safely support the sum of permanent, snow and wind loads on the roof.'

"The weight of the truss is given in pounds per square foot of the area of the horizontal projection of that portion of the roof supported by one truss.

$$W = \frac{\text{span}}{25} + \frac{\text{span}^2}{6,200}$$

"This would mean that each joint of the upper chord would be holding up a weight equal to this value of *W* multiplied by the same area as used in determining the ceiling loads supported at the joints of the lower chord. This truss weight should be added to the weights which are found for the joints of the upper chord when the diagram is constructed and for use in laying off the load line.

"As an example of the application of the above principles, let us suppose that we have a roof which has trusses like Fig. 14, spaced 12 feet apart and of 36-foot span. This truss has 2 by 8-inch rafters spaced 16 inches on centers and resting on 8 by 10-inch purlins, which are supported at the joints of the upper chord. Roof is sheathed with 1-inch spruce sheathing and covered with metal shingles. The trusses also sup-




Fig. 14. Method of Supporting Roof Loads at Joints of Truss.

port a lath and plaster ceiling, held in place by 2 by 6-inch ceiling joists spaced 16 inches on centers. We will say that the joints of the upper chord are 10 feet apart, measured along the chord and that the joints of the lower chord are 9 feet apart, measured along the length of the lower chord. This means that each joint of the upper chord supports an area of roof 10 by 12 feet, or 120 square feet of roof. The weight of the roof and purlins on this 120 square feet of roof surface will be found by determining the number of board feet of material used in this space. One piece of 8 by 10-inch yellow pine, 12 feet long, will contain 80 board feet of timber; 120 square feet of roof will contain nine pieces of 2 by 8-inch yellow pine 10 feet long or 120 board feet. Thus, the total amount of timber in rafters and purlins will be 200 board feet of yellow pine. The table above gives the weight of one board foot of yellow pine as about 4 pounds, thus making the total weight for the 120 square feet of roof about 800 pounds, or about 7 pounds per square foot of roof surface. From the formula given above, the weight of the truss itself would be about $1\frac{3}{4}$ pounds per square foot of the area of the horizontal projection of that portion of the roof supported by one truss. This projection will be 36 by 12 feet or 432 square feet in this case. Each of the three joints of the upper

chord between the ends will support $\frac{1}{4}$ of this area, or 108 square feet, thus making the weight of that part of the truss which is carried at each of these joints $108 \times 1\frac{3}{4}$ or 189 pounds per joint.

"Now we will add up the total roof load which occurs at each of the upper joints of the upper chord excepting the ends.

Metal shingles	1	lb. per sq. ft.
Sheathing	2	lbs. per sq. ft.
Rafters and purlins.....	$7\frac{1}{2}$	lbs. per sq. ft.

Total $10\frac{1}{2}$ lbs. per sq. ft.

"Then $120 \times 10\frac{1}{2}$ will equal 1,260 pounds for the weight of the roof framework and covering. To this add the weight of the roof truss itself per joint, which makes a total of about 1,450 pounds for each of these joints.

"In a similar manner the weight of the ceiling would be obtained by finding the weight of the 2 by 6 rafters which support the ceiling, and adding to this quantity the weight for ordinary lath and plaster ceiling per joint of the lower cord. These quantities may be obtained from the tables given above.

"Next time we will go a step further and start the calculations for the ordinary type of queen truss such as is found in many types of building construction."



ELEPHANT PILING TEAK LOGS—TIMBER YARDS OF RANGOON, BURMA.

One of the most wonderful displays of animal intelligence and training that can be seen anywhere in the world is that of the timber-yard elephants of Burma. At daybreak every morning the good-natured giants are at work, hauling and piling the teak logs. Kneeling or bending down before a log, the elephant, at a sign from his "mahout" or driver, will push a log with his trunk and tusks, rolling it over and over until the stack is reached. Then, putting his powerful trunk underneath, he will lift it high in the air and deposit it neatly upon the stack, after which he goes to the end of the stack, and if it projects beyond the others, pushes it carefully forward until it is exactly in line.

After many years at this work, these elephants display a most extraordinary intelligence in the way they handle their heavy burdens. And truly heavy they are, too, for an ordinary teak log weighs about two tons.

The story is told of one of these old veterans who, after a quarter of a century of service, had the habit of shutting one eye, while he judged the alignment of his logs, but of course we cannot vouch for the truth of this.

—J. M. CUMMINGS.



CEMENT BUILDING CONSTRUCTION

Mosaics in Cement Surfaces

NEW METHOD OF ORNAMENTING CONCRETE AND CEMENT PLASTER BUILDINGS

By B. S. Brown

THE use of glazed tiles in large pictures for the decoration of broad walls of public and semi-public buildings, has proved an inspiring example for the builders of dwellings partly surfaced with cement. Many houses are now seen with the blank cement expanse broken here and there by a small square color spot—the spots distributed irregularly, or in geometrical design. Indeed, there seems to be a distinct tendency, in the effort to decorate the monotonous blanks of cement walls, to attain a design. And one sees therefore, the wooden trellises tacked against the walls, which provide the design and relieve the blankness, but which are almost grotesquely out of place in their concrete environment.

Combining the notion that the blank space should be decorated with a design, with the idea that a bit of color should be provided to relieve the grayness of the cement, one finds used a sort of colored cement paint to make small designs to be inset in walls. Pronounced advancement in the art of cement decoration is observable, in the fact that these designs do not fill the whole blank wall space and that the colors are

especially devised to harmonize with the gray cement. As a small picture on an interior wall may be most effective any place except in the middle of that wall, so the design for an outer wall should be given a place carefully selected. In one of the pictures herewith, the colored design is placed above the porch, while colored tile are set above the windows of the second story.

Carrying still further the stained-glass-window example above referred to, the makers of colored cement



A Pictorial Cement Slab over Doorway.




Slab of Cement Bearing an Ornamental Colored Design inset over Porch.


designs have used them in transom spaces most effectively. The curved panel above the door, shown in the illustration, is a block of cement on the surface of which lines have been laid with a thick cement paint or paste. The colors used in the paste are blacks, crushed mulberry, reds, and yellows for the design slabs; and the lines are not flat upon the surface of the cement, but raised in the manner of highly "impressionistic" oil paintings. The pigments are mineral, and the secret of their successful use lies more in the skillful mixing with cement than in any formula. There is no effort to arrive at "natural stone" colors, for colors natural to stone, don't seem to look natural for cement.



A Modern Living Room Designed and Finished in the Best Taste. Woodwork is White Enameled, Except the Window Sills which are Mahogany. The Furniture is all Mahogany which Makes a Very Strong, Agreeable Contrast. The Fireplace Mantel is a Simple, Rich Design of Reddish Brown, Unglazed Tile, with Wooden Shelf and Side Columns. On Each Side of the Fireplace are Double, French Windows Opening Onto a Screened Porch. Open Book Shelves are Built-In at the Corner of the Room.



GUARANTEED BUILDING PLANS





Three-Room Honeymoon Cottage

A dandy little home is represented in this design. It contains everything necessary for comfort for a small family, together with facilities for entertaining guests in the evening or afternoon.

A splendid feature about this design is the large combined dining room and living room, 13 feet by 23 feet, with plenty of windows and a very attractive fire place. A room like this is appreciated in any house.

The kitchen, 7 feet 6 inches by 11 feet 6 inches, with a table in front of the window and a good cupboard opposite the sink, makes an easy kitchen to work in for the housewife. Another feature is the screened porch, which is also intended as an outdoor dining room.



Three-room stucco bungalow. Size 31 feet 6 inches by 28 feet. We can furnish complete set of blue-printed working plans and typewritten specifications for only \$5.00 per set. Blue-prints consist of basement plan; roof plan; floor plan; front, rear, two side elevations; wall sections; and all necessary interior details. Specifications consist of twenty-two pages of typewritten matter. When ordering, ask for Design No. 6610.

California Bungalow

California is the home of the bungalow. Cool evenings and cold mornings, green winters and brown summers characterize the climate from south to north and from the Sierras to the coast range.

A little fire in the grate feels comfortable once or twice a day in spring and fall and a little heat is absolutely necessary to a tenderfoot in winter.

But about this particular bungalow design—there is no law against building it in any other state and that is why we have planned a cellar the full size of the house.

In California the natives are too proud to admit that they need a cellar, but sensible fellows in other states build after this plan and take great pains to make the cellar a very important feature.

The plans call for 7½ feet of head room in the cellar, to give the proper depth for a warm air furnace, which is usually placed about in the center of the plan, some 10 feet from the kitchen chimney; so the shortest and most direct heating pipes will lead to the large living room and to the dining room.

This big living room is a very attractive feature. In size it is 19 by 14 feet, with

plenty of light and with a nook for books and a cozy corner in which to read them; both placed conveniently at the sides of the fireplace.

A triple casement window is built high enough in the exposed wall to place a fine big davenport under it and still have room in the outside corner for a large easy chair.

The proper placing of furniture is receiving more attention from architects than formerly. Comfort depends upon many little details. Life


is made up of little things which in the aggregate amount to more than the big things, because there are so many of them.

The front door opens into a rather large, comfortable reception hall which really is an adjunct to the living room and is in very close connection with the dining room.

The rear porch with its cove to hold an ice box, also the large pantry, would be appreciated by every housekeeper.

There is a box window built on the side of the kitchen that adds a great deal to the pleasure of doing kitchen work. It is seldom that a kitchen table is treated to the luxury of having sufficient light. A lemon pie always goes together in the proper proportions when the ingredients are mixed together in a nook like this.

A real bungalow requires a lot of veranda room; and this plan supplies it in abundance. Any good housekeeper would take great delight in furnishing a good bungalow veranda as an outdoor reception room. The many inventions in porch and loggia furniture offer materials sufficient for many interesting dreams of such summer parlors.



Arrangement of Bungalow, Size 44 by 29 feet.



A Typical California Bungalow Design. It is 44 by 29 feet in size, having five rooms and a bath room, with a good cellar and a stairway to the attic. We can furnish complete set of blue-printed working plans and typewritten specifications for only \$7.00 per set. Blue-prints consist of basement plan; roof plan; first and second floor plans; front, rear, two side elevations; wall sections; and all necessary interior details. Specifications consist of twenty-two pages of typewritten matter. When ordering, ask for Design No. 6607.




Interesting seven-room house containing many modern conveniences. Size, 24 feet by 30 feet 6 inches. We can furnish complete set of blue-printed working plans and typewritten specifications for \$8.00 per set. Blue-prints consist of basement plan; roof plan; first and second floor plans; front, rear, two side elevations; wall sections; and all necessary interior details. Specifications consist of twenty-two pages of typewritten matter. When ordering, ask for Design No. 6578.

Convenient Seven Room House

There are three special features in this house design that will appeal to every good housekeeper. They are the outside entrance to the cellar, the linen closet in the bath room, and the splendid attic for storage purposes.

The manner of building the stair gives an opportunity to utilize space to the best possible advantage. All stair landings are so placed that they are convenient to the different floors. Each flight is well lighted and there is very little room taken up in hallways. In fact, the upper hall is just big enough to make room for the doorways and the stair landing. The stairway is lighted by a glass door at the bottom, a central window and a dormer window in the attic. A stairway that is thoroughly well lighted is a great comfort.

It will be noticed that all rooms in this house are commodious, well lighted and well arranged. Each bed room has wall space sufficient to accommodate bed room furniture without appearing awkward or seeming crowded.



Arrangement of house, size 24 by 30 feet 6 inches.

Neat Six-Room Story-and-a-half Cottage

A pleasant little dwelling that will go nicely on a narrow lot is illustrated. It is just about as simple and free from complicated features, that run up the cost, as any house could well be. Its rooms are all pleasant and convenient and there is no waste space.


A house of this kind is inexpensive to build and can be rented or sold at a reasonable price and still give a margin of profit to the owner or builder. As the width is only 22 feet, it will go on a narrow lot very nicely. A narrow lot usually means houses crowded in rather close together; and so in this design the principal lighting is from the front and rear.

The outside appearance of this little dwelling is very attractive; a frame house, with wide clapboard siding, resting on a cement foundation.


The front porch is generous in size and has neat porch rail and three turned columns. Entrance is into a square reception and stair hall; from this one

can pass into the parlor, through a cased opening to the right, or directly back

into the kitchen. The dining room is just back of the parlor.



First Floor Plan.



Second Floor Plan.

Arrangement of six-room house. Size, 22 by 28 feet.



Six-room, story-and-a-half, frame dwelling. Size, 22 by 28 feet. A cozy, substantial home. We can furnish complete set of blue-printed working plans and typewritten specifications for only \$6.00 per set. Blue-prints consist of basement plan; roof plan; first and second floor plans; front, rear, two side elevations; wall sections and all necessary interior details. Specifications consist of twenty-two pages of typewritten matter. When ordering, ask for Design No. 6584.



Six room house with good cellar and very pleasing front veranda. Size 26 feet by 30 feet. We can furnish complete set of blue-printed working plans and typewritten specifications for only \$6.00 per set. Blue-prints consist of basement plan; roof plan; first and second floor plans; front, rear, two side elevations; wall sections; and all necessary interior details. Specifications consist of twenty-two pages of typewritten matter. When ordering, ask for Design No. 6580.

Low Cost Village House



Conditions sometimes are such that a house must be built for a stipulated price. That price must come within the means of the builder. This design is intended to offer as much house for the money as possible. For this reason, the house is plain and straight and all the carpenter work is square and straight forward, so that every cut of the saw and every blow of the hammer shall count in the building.

A good solid wall under a house is an economy; so this design calls for a good cellar as a proper support for a plain house. In front a good veranda adds very much to the appearance as well as comfort. It is quite possible to embellish a low cost house with a veranda in such a way as to add several hundred dollars to the value of the property.

Sometimes when there are old persons in the house, a bed room on the first floor is a great convenience. Besides this lower bed room, there is a good kitchen, a fair sized dining room and a pleasant, comfortable parlor. Up-stairs, the plan shows two

large bed rooms with any amount of closet room. Where there is no attic extra large storage closets like these are appreciated.

A person can build a house like this and screen the front porch with climbing vines, plant shrubbery along the sides and give it a neat, attractive appearance such as many expensive houses do not possess.



Arrangement of house, size 26 by 30 feet.


Six-Room Bungalow

A six room cottage with a good attic is illustrated in this design. The size is 37 feet 6 inches by 42 feet.

Owing to the shape, it divides nicely into six very comfortable rooms. About half of the floor space is thrown into the living room and dining room with sliding doors between. When these doors are wide open, these two rooms are like one, but there are times when comfort requires that the doors shall be closed.

The dining room, 14 by 20 feet, is unusual except in country houses, where there is plenty of ground space. Added to this, the living room, 14 by 17 feet 6 inches, gives an idea of the commodious planning of this attractive cottage home.

A very comfortable feature both in appearance and utility is the long veranda, 8 feet wide, reaching clear across the front of the house and half way down the side. On the first floor there are three



Floor Plan of Bungalow, size 37 feet 6 inches by 42 feet.

bed rooms and a den, which is intended for a bed room when necessary. For extra occasions there are two gables in the attic which may be worked into sleeping rooms. The cottage however is supposed to be complete without using the attic except for storage purposes. For this reason the stairway is placed pretty well to the rear.

Especial attention is called to the bath room, with its large window and linen closet. Modern civilization requires more bathroom facilities than ever before. Modern plumbing is better and cheaper than it was ten years ago, so that every new house may have modern plumbing conveniences at very little additional cost.

It is a country style house and it requires plenty of room. The words "country comfort" are spread all over this design and look out from each window with an invitation for a more intimate acquaintance.



Country bungalow containing six rooms and a splendid attic. Size 37 feet 6 inches by 42 feet. We can furnish complete set of blue-printed working plans and typewritten specifications for only \$7.00 per set. Blue-prints consists of basement plan; roof plan; floor plan; front, rear, two side elevations; wall sections; and all necessary interior details. Specifications consist of twenty-two pages of typewritten matter. When ordering, ask for Design No. 6609.



Hip roof, six-room house. A splendid design, showing the arrangement of rooms in a two story house, 27 feet by 31 feet on the ground. We can furnish complete set of blue-printed working plans and typewritten specifications for only \$10.00 per set. Blue-prints consist of basement plan; roof plan; first and second floor plans; front, rear, two side elevations; wall sections; and all necessary interior details. Specifications consist of twenty-two pages of typewritten matter. When ordering, ask for Design No. 6582.

Hip Roof Six-Room House


A very pleasing design has been worked out for this interesting little six-room house. The demand for six-room houses has resulted in the production of many splendid plans. The one here illustrated contains many desirable features.

In the first place, it is pleasing in appearance; which effect is enhanced by standing the house up well above ground on a concrete cellar wall. The hip roof designed with the "L" shaped extension gives an opportunity to vary the roof design in this respect. The main outside feature is the front veranda, which gives considerable room for porch furniture, as well as an extra entrance to the house through the dining room.


This dining room, by the way, is designed for a very comfortable living room. It is here the open fire is lighted when the evenings become cool in the fall and the front veranda is deserted. There is a hominess about a fire place in a room a little back from the front of the house which is impossible to get in the front parlor. This room is intended to be used, while parlors are too often kept nice just to look at.

The arrangement down-stairs of the parlor, dining room and kitchen, with a very comfortable reception hall is all that could be desired in a house of this size. There is a doorway at the back of the hall to close off the entrance to the cellar stairway. Plac-

ing it here gives more room in the kitchen, and the hall is plenty large. This plan also provides a grade entrance to the cellar and to the kitchen, but the back porch is not used much except for the family. Grocery parcels are delivered at the side door.



First Floor



Second Floor

Arrangement of House, Size 27 by 31 feet.

The Plan Shop

Practical House Designs

"That are Different"

Well Planned House for a Narrow Lot

By Charles Alma Byers


It is often more or less difficult to satisfactorily plan a house for a narrow lot. Nevertheless, it is a problem which architects are frequently called upon to solve. The house here shown was especially designed to meet such restrictions, and the interior arrangement, in the opinion of the writer, is particularly good. It should at least offer many valuable suggestions to others confronted by this problem. The lot, in this case, is forty by one hundred and twenty feet in its dimensions, and the house has a frontage of but thirty feet. This naturally leaves ten feet to be divided for the space at each side of the house, and it will therefore be seen that, when compulsory, the same plan could be used for a still narrower plot.

This house has recently been built in Los Angeles, California, and was designed by Henry L. Wilson, a well-known architect of that city. It is strongly and warmly constructed, being suitable for duplication in almost any locality, and, complete with furnace and other modern equipments, represents a total expenditure of but approximately \$3,800.

In style of architecture it is somewhat along the lines of the modern

California bungalow. It possesses such characteristics of the type as irregular roof lines, roofs with comparatively little pitch, wide overhangs in the eaves and gables, and unsurfaced framing and finishing timbers, as well as a sort of

general appearance of rusticity. It has six rooms, besides the bath room, on the first floor, and but a single sleeping room, with a small dressing room in connection therewith, on the second floor. This upstairs arrangement not



First and Second Floor Plans of Los Angeles Bungalow.



Seven-Room Bungalow with Novel Roof Bed Room, Built at Los Angeles, Calif., for \$3,800. Architect, Henry S. Wilson.

only provides an ideal bed room which may be opened on three sides, but also prevents the house from seeming unattractively low and rambling in its structural lines.

An admirable feature of the outside is the porch or veranda, shaped like the letter L, which extends across the entire front and for a considerable distance along one side. The front portion is eight feet wide and the side portion six feet wide, and the combined length is forty-six feet six inches. The main entrance leads from this porch directly into the living room, but from the rear end of the side portion French doors provide direct access to the dining room. The foundation, walls and pedestals are of well-selected cobblestones, coped with concrete, and the flooring is likewise of concrete. The construction of this flooring, as well as of all walks and steps, consists of concrete three inches thick, surfaced with cement one-half inch thick.

There is a small pergola, four by thirteen feet in its dimensions, on one side, which is of similar construction, and on the opposite side, but nearer the front, is an outside chimney, of massive proportions, surfaced with cobblestones. This chimney is for the living-room fireplace. Another chimney, on the inside, is located near the back of the house, which serves as a flue for both the kitchen and the basement furnace. The former is eight by twelve inches on the inside and the latter eight by eight inches, and both are plastered on the inside. The one in the back part of the house is constructed of brick.

The foundation of the house is of concrete, the mixture for which consisted of six parts of clean, sharp, coarse sand and gravel to one part of best Portland cement. The ingredients of the cement used for surfacing the walks, steps and porch flooring consisted of two parts of screened sand to one part of Portland cement.

Sizes of Timbers Used

The dimensions of some of the principal timbers in the construction are as follows: Mud sills, 2 by 6 inches; girders, 4 by 4 inches; floor joists, 2 by 6 inches; second floor joists, 2 by 10 inches; floor joists over basement, 2 by 10 inches; ceiling joists, 2 by 4 inches; rafters, 2 by 4 inches; collar ties, 2 by 3 inches; ridge poles, 1 by 6 inches; plates, 2 by 4 inches; studs, 2 by 4 inches; underpins on piers, 4 by 4 inches; underpins on outer walls, 2 by 4 inches; shingle lath, 1 by 3 inches. All of these are of Oregon pine, except the mud sills, which are of California

redwood. The siding consists of sawed redwood shakes, laid with fourteen inches of their length to the weather.

The color scheme of the house is very effective, being composed of greens and grays. The siding and all exposed framing timbers of the first story are stained a soft green color, and the second story is done in gray, which harmonizes with the roofing and the masonry work. The trim around the doors and windows is painted a still darker shade of green.

Details of Interior Finish

While the outside of the house is of good style, it is in the interior that one is apt to find the more commendable points. The accompanying floor plans, for this reason, will merit close inspection. There is a large number of admirable built-in features, and the arrangement of the rooms is particularly convenient. The rooms are also comfortably large, and the large number of windows not only create very charming interiors but make possible the admission of plenty of sunlight and fresh air.

The living room possesses windows on three sides, and between it and the dining room intervene folding glass doors, which aid still further in making it light and airy. A large fireplace, in one end, with a built-in book case on one side and an L-shaped seat on the other, is a prominent feature of this room. The mantel of this fireplace is of clinker brick, and its hearth is of three by six inch tile brick. The book case has removable shelves and leaded-glass doors, and the tops of the seats are hinged so that the space underneath may be used for fuel or other purposes. The book case reaches only to a height of about five feet, and above it, corresponding with a similar one on the other side of the mantel, is a small window.

The dining room contains an excellent buffet, with cupboards and drawers—the former possessing leaded-glass doors. Above its counter shelf is set a broad plate mirror, and above the entire feature are four tiny windows. The walls of this room are wainscoted to a height of four feet six inches, above which runs a grooved plate shelf. This wainscoting is of seven-eighths by twelve inch boards, rabbetted and stripped. A French door leads from this room into the little side pergola, and other doors connect it with the kitchen and a small hall.

The kitchen contains the usual sink and cupboards, as well as a draught cooler and boiler. Back of the kitchen are the screened porch, with its stationary wash tubs, and a small breakfast room. The latter has two of its walls entirely taken up by casement windows,

and a door from it leads into the pergola.

There are two bed rooms on this floor, each with a roomy closet, between which intervenes the bath room. The bath room is particularly interesting for the reason that it contains, besides its customary fixtures, two small corner cabinets and a built-in seat. Above each of the cabinets is a small window, and above the seat is a plate mirror. These rooms are all connected by the hall, already mentioned, from which ascends the stairway to the second floor and descends the steps to the basement. This hall also contains a small linen closet.

All rooms on the first floor, except the living room and dining room, have three-eighths by two-inch clear white maple flooring. The flooring in the living room and dining room is of quarter-sawed oak, of the same dimensions. The kitchen is plastered with hardwood plaster, finished smooth, and the walls of the bath room, to a height of five feet, are similarly plastered, except that they are ruled into three by six inch blocks to imitate white tile. The woodwork in the living room and dining room, which is of slash-grain Oregon pine, is stained to represent weathered oak, in the breakfast room it is stained a soft light green color, and in all of the other rooms it is enameled white.

Out-Door Sleeping "On the Roof"

The second-floor sleeping room is ideal for its purpose. Having a total of fifteen casement windows on the three exposed sides, it may be easily converted into virtually an open-air room, becoming the equal if not superior to the ordinary sleeping porch. The little dressing room is also an admirable feature, and provides the desired privacy.

Of course, should one want only a one-story house this second-floor arrangement, while it is especially interesting, could be easily omitted without changing the first-floor plan in any detail. In fact, this would constitute a complete and very satisfactory little home without this feature. Even the small breakfast room on the main floor might be eliminated if desired, or it might be converted into a very cozy den, probably with built-in book cases and other features. When it comes to alterations, however, there are any number of possibilities, and this is a feature of the plan which makes this house so interesting.

The basement beneath the house is fourteen by sixteen feet in its dimensions, and is therefore large enough to not only house the furnace but to be used as a convenient storage place. The flooring and walls are of concrete; the former surfaced with cement one-half inch thick.



A Beautiful, Inexpensive Dining Room, Finished with Wall Board Paneling from Base to Plate Rail. The Room is Lighted with a Group of Three Casement Windows.

Revolving Damper Solves Ventilating Problem

SIMPLE SYSTEM IN WHICH FOUL AIR IS EXHAUSTED FROM CEILING IN HOT WEATHER AND FROM FLOOR IN COLD

By Harold L. Alt

ONE of the most debated questions of ventilation is the point of air entrance and point of exit from the room. Numerous good and substantial arguments can be advanced as to why the fresh air should be put in from high registers and drawn out from low points, either in or near the floor.

Other authorities are equally strong in advocating the supply of fresh air from below and the removal of foul air from the ceiling or at other high points. Arguments without number can be found in favor of either method, and it is largely a matter of personal preference as to which scheme is employed.

It is fair to assume, however, that if hot air at a temperature of 100 degrees Fahr. is put into a room, say at 70 degrees Fahr. it will naturally seek the higher portions of the room until its temperature has cooled down sufficiently to drop the air toward the floor. This movement goes on gradually as the air temperature continues to lower, and it is easy to understand from this that when the supply of fresh air is put in at a temperature higher than the room temperature its natural course will be downward.

On the other hand, suppose outside conditions in warm weather raise the room above 70 degrees Fahr., then the air supply should be cooler than the room, owing to its constantly increasing temperature.

Good ventilation always follows the natural movement of air unless certain imperative reasons require otherwise.

Therefore, during cold weather, it is better to supply hot air at the top of the room and draw the cooler foul air off at the bottom, but in the summer time the cool supply should be at the bottom and the hot, foul air removed from the top. Yet we cannot change our ventilation ducts with the season.

There is a method whereby it is possible to do this




Fig. 1. Revolving Damper, Turned so that Warm, Fresh Air comes in at Ceiling; Foul Air Exhausted from Floor.

very thing so easily, conveniently and satisfactorily that it is surprising that a greater number of buildings are not so equipped. This scheme is illustrated in Figs. 1 and 2, the desired end being accomplished by the revolving damper. Fig. 1 shows the damper set in what is often called the normal position. This is so as to supply air at the top of the room or auditorium and to draw it off from the bottom.

The fresh air enters the supply fan, passes across the heater, is warmed, and then goes through the




Fig. 2. Revolving Damper, Turned so that Warm, Fresh Air comes in from Floor; Foul Air Exhausted from Ceiling.

revolving damper to the duct leading to all the registers in the upper portion of the ventilated space. The exhaust from all the low registers is carried to the revolving damper and then to the exhaust fan, which discharges it to the outer air.

In Fig. 2 the revolving damper is shown reversed, resulting in the supply air being directed into the duct leading to the lower registers and the duct from the upper registers directed into the exhaust fan, thus making the high registers exhaust and the low registers supply.

With this scheme, top and bottom supply can be had at will by the simple turn of a single damper.

SPEAKING ABOUT CHRISTMAS. I have often thought of the number of odd and useful things a wood-turner can make for presents, such as rolling pins, potato masher, baseball bats, croquet sets, drum sticks, gavels, spinning tops, turned cups and saucers, jewel cases, napkin rings, candle sticks, puzzles, Indian clubs, dumb bells, police clubs, canes, checkers, pincushions, cups, pipes, spindle waste baskets, comb racks, and many other scores of things, I cannot think of just now. I have made many of the above and then some.

WM. C. JASBURY.

Acoustics of Auditoriums

HOW THE EXTREMELY POOR ACOUSTICAL PROPERTIES OF THE AUDITORIUM AT THE UNIVERSITY OF ILLINOIS WERE ANALYSED AND IMPROVED

By F. R. Watson

Asst. Prof. of Physics

An Authoritative Article Reproduced by Special Permission from Bulletin No. 73 of the University of Illinois Engineering Experiment Station.

MUCH concern has arisen in late years in the minds of architects because of the faulty acoustics that exist in many auditoriums. The prevalence of echoes and reverberations with the consequent difficulty in hearing and understanding on the part of the auditor defeats the purpose of the auditorium and diminishes its value.

The Auditorium at the University of Illinois presents such a case. The building is shaped nearly like a hemisphere, with several large arches and recesses to break up the regularity of its inner surface. The original plans of the architect were curtailed because of insufficient money appropriated for the construction. The interior of the hall, therefore, was built absolutely plain with almost no breaking up of the large, smooth wall surfaces; and, at first, there were no furnishings except the seats and the cocoa matting in the aisles. The acoustical properties proved to be very unsatisfactory. A reverberation or undue prolongation of the sound existed, and in addition, because of the large size of the room and the form and position of the walls, echoes were set up.

If an observer stood on the platform and clapped his hands, a veritable chaos of sound resulted. Echoes were heard from every direction and reverberations continued for a number of seconds before all was still again. Speakers found their utterances thrown back at them, and auditors all over the house experienced difficulty in understanding what was said. On one occasion the University band played a piece which featured a xylophone solo with accompaniment by the other instruments. It so happened that the leader heard the echo more strongly than the direct sound and beat time with it. Players near the xylophone kept

time to the direct sound, while those farther away followed the echo. The confusion may well be imagined.

Thus it seemed that the Auditorium was doomed to be an acoustical horror; that speakers and singers would avoid it, and that auditors would attend entertainments in it only under protest. But the apparent misfortune was in one way a benefit since it provided an opportunity to study defective acoustics under exceptionally good conditions and led to conclusions that not only allowed the Auditorium to be improved, but also indicate some of the pitfalls to be avoided in future construction of other halls.

An investigation of the acoustical properties of the Auditorium was begun in 1908 and has continued for six years. It was decided at the outset not to use "cut and try" methods of cure, but to attack the problem systematically so that general principles could be found, if possible, that would apply not only to the case being investigated, but to auditoriums in general. This plan of procedure delayed the solution of the problem, since it became necessary to study the theory of sound and carry out laboratory investigations at the same time that the complex conditions in the Auditorium were being considered. The author spent one year of the six abroad studying the theory of acoustics and inspecting various auditoriums.

The main echoes in the Auditorium were located by means of a new method of tracing the path of sound, the time of reverberation was determined by Sabine's method, and a general diagnosis of the acoustical defects was made. Hangings and curtains were installed in accordance with the results of the study so that finally the acoustical properties were improved.



The Auditorium at the University of Illinois, a Magnificent Architectural Monument but an Absolute Failure in regard to Acoustics. How this Acoustical Problem has been Studied Out and Solved is Clearly Explained by the Author.



Interior View of Auditorium at the University of Illinois.

Behavior of Sound Waves in a Room

When a speaker addresses an audience, the sounds he utters proceed in ever widening spherical waves until they strike the boundaries of the room. Here the sound is partly reflected, partly transmitted, and the rest absorbed. The amounts of reflection, absorption and transmission depend on the character of the walls. A hard, smooth wall reflects most of the sound so that but little is transmitted or absorbed. In the case of a porous wall or a yielding wall, the absorption and transmission are greater, and the reflection is less. After striking a number of reflecting surfaces, the energy is used up and the sound dies out.

The reflection of sound produces certain advantages and disadvantages for the acoustics. When it is considered that sound travels about 1,100 feet a second, it may be seen that a room of ordinary size is almost immediately filled with sound because of the many reflections. In a room 40 feet square, for instance, the number of reflections per second between opposite walls is $1,100 \div 40$, or approximately 27. The number is really greater than this, since the sound that goes into the corners is reflected much more frequently than out in the middle where the distances between walls are greater. The result is that the sound mixes thoroughly in all parts of the room so as to give the same average intensity; that is, the sound is of the same average *loudness* for all auditors, even for those in the remotest corners.

Though the reflection of sound has the advantage of fulfilling the conditions for loudness, it introduces at the same time possibilities for setting up defective acoustics. For instance, when the walls of the room are hard and smooth very little energy is lost at each impact of the sound and many reflections take place before it finally dies out. This slow decadence of the sound, or *reverberation*, as it is called, is the most common defect in auditoriums.

If a speaker talks in such a hall the auditors have difficulty in understanding. Each sound, instead of dying out quickly, persists for some time so that the succeeding words blend with their predecessors and set up a mixture of sounds which produces confusion. The cure for the trouble is brought about by the introduction of materials, such as carpets, tapestries, and the like, which act as absorbers of sound and reduce the time of reverberation.

When music is played in an auditorium with a prolonged reverberation, the tones following one another blend and produce the same effect as that of a piano when played with the loud pedal in use. A reverberation is more advantageous for music than for speech, since the prolongation and blending of the musical tones is desired, but the mixing of the words in a speech is a distinct disadvantage. When curing this defect for halls used for both music and speaking, a middle course must be steered, so that the reverberation is

made somewhat long for speaking and somewhat short for music, yet fairly satisfactory for both.

Curved Wall Always a Menace

Going back to the consideration of the reflection of sound, it is found that another defect may be produced, namely, an *echo*. This is the case when a wall at some distance reflects the sound to the position of the auditor. He hears the sound first from the speaker, then later by reflection from the wall. The time interval between the direct and reflected sound must be great enough to allow two distinct impressions to be made. This time is about $1/15$ of a second, but varies with the acuteness of the observer. The farther off the wall is, the greater is the time interval and the more pronounced is the echo. If the wall is not very distant, the time interval is too short to allow two distinct impressions to be made, and the effect on the auditor is then much the same as if his neighbor at his side speaks the words of the discourse in his ear at the same time that he gets them directly from the speaker. In case the reflecting wall is curved so as to focus the sound the echoes are much more pronounced. A curved wall wherever it may be placed in an auditorium is thus always a menace to good acoustics.

There are other actions of the sound that may result in acoustical defects. The phenomena of *resonance*, for instance, may cause trouble. Suppose that the waves of sound impinge on an elastic wall, not too rigid. If these waves are timed right they set the wall in vibration in the same way that the bell ringer causes a bell to ring by a succession of properly timed pulls on the bell rope. The wall of the room will then vibrate under the action of this sound with which it is in tune and will reinforce it. Now suppose a band is playing in a room. Certain tones are reinforced, while the others are not affected. The original sound is then distorted. The action is the same on the voice of the speaker. The sounds he utters are complex and as they reach the walls certain components are reinforced and the quality of the sound is changed. This action of resonance may also be caused by the air in a room. Each room has a definite pitch to which it responds, the smaller the volume of the room the higher being the pitch. A large auditorium would respond to the very low pitch of the bass drum. In small rooms and alcoves the response is made to higher pitched tones, as may be observed by singing the different notes of the scale until a resonance is obtained.

Another action of sound causes the *interference* of waves. Thus the reflected waves may meet the oncoming ones and set up concentrations of sound in certain positions and a dearth of sound in others.

Summing up, it is seen that the effects of sound which may exist in a room are *loudness*, *reverberation*, *echoes*, *resonance*, and *interference*, and that the most common defects are reverberation and echoes. We now turn to the discussion of the methods of cure.




Fig. 1. Longitudinal Section Showing the Chief Concentrations of Sound, the Diffraction Effects Being Disregarded.




Fig. 2. Plan of Auditorium Showing Concentration of Sound by the Rear Wall.

Methods of Improving Faulty Acoustics

A. REVERBERATION AND ITS CURE

Everyone has doubtless observed that the hollow reverberations in an empty house disappear when the house is furnished. So, in an auditorium, the reverberation is lessened when curtains, tapestries, and the like are installed in sufficient numbers. The reason for this action is found when we inquire what ultimately becomes of the sound.

Sound is a form of energy and energy can not be destroyed. When it finally dies out, the sound must be changed to some other form of energy. In the case of the walls of a room, for instance, it has been shown in a preceding paragraph that the sound may be changed into mechanical energy in setting these walls in vibration. Again, some of the sound may pass out through open windows and thus disappear. The rest of the sound, according to Lord Rayleigh, is transformed by friction into heat. Thus a high pitched sound, such as a hiss, before it travels any great distance is killed out by the friction of the air. Lower pitched sounds, on reaching a wall, set up friction in the process of reflection between the air particles and the wall so that some of the energy is converted into heat. The amount of sound energy thus lost is small if the walls are hard and smooth. The case is much different, however, if the walls are rough and porous, since it appears that the friction in the pores dissipates the sound energy into heat.




Fig. 3. Transverse Section Showing How Most Pronounced Echoes Are Set Up by the Two Concave Surfaces.

It should be pointed out in this connection that any mechanical breaking up of the sound by relief work on the walls or by obstacles in the room will not primarily diminish the energy of the sound. These may break up the regular reflection and eliminate echoes, but the sound energy as such disappears only when friction is set up.

The following quotations from Rayleigh emphasizes these conclusions: "In large spaces, bounded by non-porous walls, roof, and floor, and with few windows, a prolonged resonance seems inevitable. The mitigating influence of thick carpets in such cases is well known. The application of similar material to the walls and roof appears to offer the best chance of further improvement."

Experimental Work on Cure of Reverberation.—The most important experimental work in applying this principle of the absorbing power of carpets, curtains, etc., has been done by Professor Wallace C. Sabine of Harvard University. In a set of interesting experiments lasting over a period of four years, he was able to deduce a general relation between t , the time of reverberation, V , the volume of the room, and a the absorbing power of the different materials present. Thus:

$$t = 0.164 V \div a \quad (1)$$

For good acoustical conditions, that is, for a short time of reverberation, the volume V should be small and the absorb-




Fig. 4. Perspective Section Showing how an Echo Is Formed on the Stage by Two Reflections. Diffraction Effects Are Not Considered in this Drawing.

ing materials, represented by a , large. This is the case in a small room with plenty of curtains and rugs and furniture. If, however, the volume of the room is great, as in the case of an auditorium, and the amount of absorbing materials small, a troublesome reverberation will result.

Professor Sabine determined the absorbing powers of a number of different materials. Calling an open window a perfect absorber of sound, the results obtained may be written approximately as follows:

One square meter of open window space.....	1.000
One square meter of glass, plaster, or brick.....	.025
One square meter of heavy rugs, curtains, etc.....	.25
One square meter of hair felt, 1 inch thick.....	.75
One square meter of audience96

These values, together with the formula, allow a calculation to be made in advance of construction for the time of reverberation. This pioneer work cleared the subject of architectural acoustics from the fog of mystery that hung over it and allowed the essential principles to be seen in the light of scientific experiment.

In a later investigation Sabine showed that the reverberation depended also on the pitch of sound. As a concrete example, the high notes of a violin might be less reverberant with a large audience than the lower tones of the bass viol, although both might have the same reverberation in the room with no audience. Again, the voice of a man with notes of low pitch might give satisfactory results in an auditorium while the voice of a woman with higher pitched notes would be unsatisfactory.

These considerations show that the acoustics in an auditorium vary with other factors than the volume of the room and the amount of absorbing material present. The audience may be large or small, the speaker's voice high or low, the entertainment a musical number or an address. The best arrangement for good acoustics is then a compromise where the average conditions are satisfied. The solution offered by Professor Sabine is such an average one, and has proved satisfactory in practice.

B. ECHOES AND THEIR REMEDY

An echo is set up by a reflecting wall. If an observer stands some distance from the front of a cliff and claps his hands, or shouts, he finds that the sound is returned to him from the cliff as an echo. So, in an auditorium, an auditor near the speaker gets the sound first directly from the speaker, then, an instant later, a strong repetition of the sound by reflection from a distant wall. This echo is more pronounced if the wall is curved and the auditor is at the point where the sound is focused.

To cure such an echo, two methods may be considered. One method consists in changing the form of the wall so that the reflected sound no longer sets up the echo. That is, either change the angle of the wall, so that the reflected sound is sent in a new direction where it may be absorbed or where it may reinforce the direct sound without producing any echoes, or else modify the surface of the wall by relief work or by panels of absorbing material, so that the strong reflected wave is broken up and the sound is scattered. The second method is to make the reflecting wall a "perfect" absorber, so that the incident sound is swallowed up and little or none reflected. These methods have been designated as "surgical" and "medicinal" respectively. Each method has its disadvantages. Changing the form of the walls in an auditorium is likely to do violence to the architectural design. On the other hand, there are no perfect absorbers, except open windows, and these can seldom be applied. The cure in each case is, then, a matter of study of the special conditions of the auditorium. Usually a combination of the surgical and the medicinal cures is adopted. For instance, coffering a wall so that panels of absorbing material may be introduced has been found to work well in bettering the acoustics, and also, in many cases, it fits in with the architectural features.

C. POPULAR CONCEPTION OF CURES.—USE OF WIRES AND SOUNDING BOARDS

A few words should be written concerning the popular notion that wires and sounding boards are effective in curing faulty acoustics. Experiments and observations show that wires are of practically no benefit, and sounding boards can be used only in special cases. Wires stretched in a room scarcely affect the sound, since they present too small a surface to disturb the waves. They have much the same effect on sound waves that a fish line in the water has on water waves. The idea has, perhaps, grown into prominence because of the action of a piano in responding to the notes of a singer. The piano has every advantage over a wire in an auditorium. It has a large number of strings tuned to different pitches so that it responds to any note sung. It also has a sounding board that reinforces strongly the sound of the strings. Finally, the singer is usually near the piano. The wire in the

auditorium responds to only one tone of the many likely to be present, it has no sounding board, and the singer is some distance away. But little effect, therefore, is to be expected.

The author has visited a number of halls where wires have been installed, and has yet to find a case where pronounced improvement has resulted. Sabine cites a case where five miles of wire were stretched in a hall without helping the acoustical conditions. It is curious that so erroneous a conception has grown up in the public mind with so little experimental basis to support it.

Sounding Boards.—Sounding boards or, more properly, reflecting boards, have value in special cases. Some experiments have been made where pronounced effects were obtained. The sounding board should be of special design to fit the conditions under which it is to be used.

Modeling New Auditoriums after Old Ones with Good Acoustics.—Another suggestion often made is for architects to model auditoriums after those already built that have good acoustical properties. It does not follow that halls so modeled will be successful, since the materials used in construction are not the same year after year. For instance, a few years ago it was the usual custom to put lime plaster on wooden lath; now it is frequently the practice to put gypsum plaster on metal lath, which forms an entirely different kind of a surface. This latter arrangement makes hard, non-porous




Fig. 5. Parabolic Reflector Showing its Action on Sound.

walls which absorb but little sound, and thus aggravate the reverberation. Further, a new hall usually is changed somewhat in form from the old one, to suit the ideas of the architect, and it is very likely that the changes will affect the acoustics.

(Note: The author here gives a detailed report of the acoustical investigation in the auditorium at the University of Illinois, including the tracing of echoes.—Ed.)

Conclusion Drawn from the Acoustical Survey


The results of the survey show that curved walls are largely responsible for the formation of echoes because they concentrate the reflected sound. It seems desirable, therefore, to emphasize the danger of using such walls unless their action is annulled by absorbing materials or relief work. Large halls with curved walls are almost sure to have acoustical defects.

Methods Employed to Improve the Acoustics

Reflecting Boards.—The provisional cure was brought about gradually by trying different devices suggested by the diagnosis. In one set of experiments sounding boards of various shapes and sizes were used. A flat board about five feet square placed at an incline over the position of the speaker produced little effect. A large canvas surface, about 12 by 20 feet, was not much better. A parabolic reflector, how-

ever, gave a pronounced effect. This reflector was mounted over a pulpit at one end of the stage and served to intercept much of the sound that otherwise would have gone to the dome and produced echoes. The path of the reflected sound was parallel to the axis of the paraboloid of which the reflector was a quarter section. There was no difficulty in tracing out the reflected sound. Auditors in the path of the reflected rays reported an echo, but auditors in other parts of the Auditorium were remarkably free from the usual troubles. The device was not used permanently, since many speakers objected to the raised platform. Moreover, it was not a complete cure, since it was not suited for band concerts and other events, where the entire stage was used.

Sabine's Method.—The time of reverberation was determined by Sabine's method. An organ pipe making approx-



It was Found that these Huge Curtains Hung in the Dome Eliminate the Echoes. Absorbing Materials have also been Hung Under the Arches, Against the Walls.

imately 526 vibrations a second was blown for about three seconds and then stopped. An auditor listened to the decreasing sound, and when it died out made a record electrically on a chronograph drum. The time of reverberation was found to be 5.90 seconds, this being the mean of 19 sets of measurements, each of about 20 observations. The reverberation was found also by calculation from Sabine's equation, taking the volume of the Auditorium as 11,800 cubic meters and calculating the absorbing power of all the surfaces in the room. This calculation gave 6.4 seconds. The agreement between the two results is as close as could be expected, since neither the intensity of the sound nor the pitch used by the author was the same as those used by Professor Sabine, and both of these factors affect the time of reverberation.

Later the time of reverberation was again determined after certain changes had been made. A thick carpet had been placed on the stage, heavy velour curtains 18 by 32 feet in area hung on the wall at the rear of the stage, a large canvas painting 400 square feet in area was installed, and the glass removed from the skylight in the ceiling. The time of reverberation was reduced to 4.8 seconds. With an audience present this value was reduced still more, and when the hall was crowded at commencement time the reverberation was not troublesome.

Method of Eliminating Echoes.—Although the time of reverberation was reduced to be fairly satisfactory, as just explained, the echoes still persisted, and were very annoying. Attempts were made to reduce individual echoes by hanging cotton flannel on the walls at critical points. Thus the shaded areas in Fig. 4 were covered and also the entire rear wall in the balcony. Pronounced echoes still remained, and it was evident that some drastic action was necessary to alleviate

this condition. Four large canvases were then hung in the dome in position suggested by the results of the diagnosis. A very decided improvement followed. For the first time the echoes were reduced to a marked degree and speakers on the stage could talk without the usual annoyance. This arrangement eliminated the echoes not only on the stage, but generally all over the house. A number of minor echoes were still left, but the conditions were much improved, especially when a large audience was present to reduce the reverberation.

Proposed Final Cure.—The state of affairs just described is the condition at the time of writing. Two propositions were considered in planning the final cure. One proposition involved a complete remodeling of the interior of the Auditorium. Plans of an interior were drawn in accordance with the results of the experimental work that would probably give satisfactory acoustics. This proposition was not carried out because of the expense and because it was thought desirable to attempt a cure without changing the shape of the room. The latter plan is one now being followed. It is proposed to replace the present unsightly curtains with materials which will conform to the architectural features of the Auditorium and which will have a pleasing color scheme. At the same time, it will be necessary to hold to the features which have improved the acoustics.




Significant Work in Trade School Education

IOWA STATE COLLEGE HOLDS FIRST STATE-CONDUCTED COURSE IN TRADE TRAINING IN THE UNITED STATES

From January 6th to 10th, occurred one of the most unique movements of recent years toward a sane education in the trades. The newly organized Department of Engineering Extension of the Iowa State College conducted a very successful Short Course for Painters and Decorators, given in co-operation with the Master Painters' Association of Iowa. In spite of the incomplete announcement to the painters of the State, fifty-eight students registered for the course outlined, which included instruction in graining and sign painting and in blending and stenciling. The students registered, were eager for this kind of instruction. The apprenticeship system is no longer applicable to the painting craft, the time of a high priced mechanic cannot be spent in instructing an apprentice, nor can the job be risked in his hands for practice. The need of some other agency to equip competent journeymen, is everywhere apparent. Ten million dollars is spent annually in Iowa on interior painting and decorating. It reaches every corner of the State, in both public and private buildings. There are over nine thousand painters in the State and on account of the fact that most of them live in the smaller towns, a much great versatility is demanded of them. They are called on to do all kinds of work and, conversely, the grade and variety of work in the decorating field which finds its way into any community is largely the same as that which the local decorator can do. Hence the need for a greater breadth of training.

The instruction in graining was given by Mr. J. W. Luthe of Cleveland, and the stenciling and blending by Mr. Chas. Mollendorf of Chicago, both men of wide experience in their line. That the need for this kind of instruction is pressing, was the uniform testimony of the students in attendance, who ranged from the beginner who had scarcely had a brush in his hand before, to the seasoned mechanic and master painter employing from one to twenty workmen. One veteran mechanic of sixty-six years, enrolled. The average was above thirty years. The painting and decorating trade appears to be mostly "tricks of the trade" and there seems to be no "standard practice." To standardize this practice and make it available to every workman in Iowa, is a task of no small magnitude and of no small service as well.—*Brush and Pail.*




Modern School at Benton, Ill.


A model of modern school house planning and construction is the new Benton School at Benton, Ill. It is in the form of a standard 10-room school building, but on the second floor two of the class rooms are made into one double size room for general assembly. A rolling partition divides this large room when required.

The main entrance of the building is handled in the classical style, constructed of white limestone. The balance of the exterior trim is white enamel terra cotta, which contrasts effectively with the dark brown brick work.

The building is typical of modern efficiency in school building work—neat and dignified, but not at all fussy or over-ornamented.



First Floor Plan.



Second Floor Plan.



New Benton School at Benton, Ill., Designed by G. W. Ashby, Architect, Chicago.



Framing Hood Rafter

HOW TO FIND THE CUTS FOR THE HOOD RAFTER TO SET WITH EITHER PLUMB OR RAKE SIDES—THE STEEL SQUARE CLEARLY EXPLAINED FOR THIS WORK

By A. W. Woods

WE are going to take the hood rafter for our subject this month, though on several occasions we have answered questions on it, or rather *tried* to diagnose the subject. Others have tried to do the same thing and we dare say did equally as good a job at it as we accomplished, or rather thought

stand in the same position as would be required for the hood rafters; consequently the cuts must be the same, with the exception of the seat cut, which is not used in this case, as there would be a plumb and side cut at each end,—the side cuts being right and left; and to make the hood rafter properly member onto the side of the common rafter, it would have to be backed on both top and bottom.

This, of course, should be one way only; but this may be readily found by setting off on the plumb cut the amount of the rise the roof has in the length of the side cut taken on a level line.

But custom seems to have settled on another way, and that is, to just make a miter cut on the foot of the hood rafter to fit against the side of the common rafter. This brings the top of the hood rafter in the plane of the roof, without any backing whatever and the lower end cut of the jacks for the hood is simply a square cut; but where the real trouble comes in, is in making the cut at the top or peak end of the hood, so that they will exactly member onto the ridge. Now, this is the part that we want to make clear.

If it was simply membering two pieces on a level plane, as shown in Fig. 2, all that is necessary to take is half of the spread, as at A B, and the projection as at C B, on the square; and the side on which the




FIG. 1

Two Straight Gables coming together at Right Angles require a Set of Hood Rafters.

we did; and it would seem that after so much has been said on the subject, any one who has been a reader of this family magazine for the past few years, could not help but know all there is about it.

It is one of those things that puzzles when it should not puzzle at all, for if a man knows how to frame a hip and valley roof, he should not experience any trouble at all; for we claim when it is properly built, it is a part of the roof, as shown in Fig. 1.

Here is a building joining onto a larger one, or in other words, the roof of the smaller building laps upon the roof of the taller building, and if the intersections of the roofs are formed by valley rafters, they




FIG. 2.




FIG. 3.

The Framing of Hood Rafters Explained.

latter is taken will give the angle, no difference what the angle formed by the two pieces may be.

The same principal holds good when there is a pitch given the two pieces, as in the case of the hood rafter. A B then represents the distance from the foot of the hood along the edge of the common rafter to the center of the ridge and C B, the projection as before, will give the required angle across the back of the hood. But in addition to this, there must be another angle across its side, and this is what puzzles, because it runs off into space and is therefore not so readily grasped. But to obtain correct results, it must be reckoned from just the same as the civil engineer lays off his railroad curves for his road bed, from a given center—which may be off in a corn field, in a lake or in the heart of a mountain,—it does not make any difference. There is an unseen point somewhere, and it must be reckoned from. In the case of the hood rafter, it is at D, as shown in Fig. 3, and is established by an extended line from the foot of the hood to a point intersecting a plumb line from the ridge at B. Thus forming A D as one of the parts to take on the square, while the other part is found by taking a line from D to the end of the projection as at C. D C then is the other part to take, and the side of the square on which the latter is taken, will give the cut.

The length of the hood rafter is found from its run and rise in the usual way, as that for the hip or valley.



The Crooked Line Shaft

By J. Crow Taylor

A man had a nice little gasoline engine, and a group of nice little machines, and the shaft was crooked, which made the whole thing look bad and run clumsily. It was quite a long shaft, though light, and had been made from two lengths with a coupling. It was evident that some effort had been made to set the shaft straight in the beginning, but the journals were flimsily supported and had pulled out of shape till one could see by a glance along the line that one end had pulled over a couple of inches. It was supported by stubs driven in the ground, and these had pulled over with the strain of the belts.

Now, it makes no difference if this was just a temporary set, it should have been worth while to put that shaft down straight and fasten it firmly enough to hold and stay straight. One not only wastes power in unnecessary friction when a shaft is crooked, but it is hard on the shaft itself, and enough of it will result in permanently springing the shafting.

Make your shafting straight and level, and see that the bearings are firmly enough supported that they will stay where you put them. Take more pains when it is a permanent setting in the shop, but even if it is a temporary set-up on some job, it is better to see that the shafting and machines are firmly fixed, and the shaft straight.



By a Foreman Shaver

I once had a crew of men working on a building. In laying the sheathing, one of the men dropped back in his row until he was about 6 feet behind the other men. When the sub-foreman of the crew called his attention to his work, he replied that a man got as much for working slowly as he did for working rapidly. "That is true," said the foreman, "but it sometimes is the cause of a man's pay being stopped." That was a prophetic remark, for the pay of that man was stopped that night. Indeed, there was no other course to be taken, for the retention of a man who avowed such principles was an open incentive to "soldiering" on the part of the balance of the crew. Of such men is the kingdom of no-accounts.



I had the misfortune at one time to work for a man who could not give the simplest order in an intelligible manner, his reason being that he "was h—l on working, himself, but a poor hand at trying to put brains into other people's heads." There is a good deal in the remark that has a bearing on the success or failure of a man in the position of foreman. Here is where the oft-quoted quality of tact is called into play; for to give intelligent directions to a workman and at the same time avoid too much minuteness of detail requires the exercise of all the resources of the best of foremen. True, there are some men who can get a lot of work of a certain kind out of men by the liberal use of words and bluster, but these men and methods are not to be considered as applying to the handling of skilled or semi-skilled labor. Getting ill-tempered over explanations does not help matters any, and is sure means of losing the respect and good-will of a crew of men.



The most expensive man I have in my crew is the one who gets things done the quickest. The efficiency which gets work done the quickest way to get good results had been drilled out of him on rough work so that he will do a piece of good work as hurriedly as he would nail up a hole in a barn-yard fence. That kind of efficiency results in poor work when the quality point is not kept in view.

H. C. HANER.



Kinks, or a Few Tricks of the Carpenter's Trade Learned by Experience

By Peter Hedstrom
Architect, Billings, Mont.

ANYONE who follows a trade for any length of time learns a few tricks which make the work easier and better, and while the following may not be new to the old "chips," it perhaps, will prove of some use to the younger ones.

NAILING WITHOUT SPLITTING. Nailing is a very simple operation, but even in that there are a few tricks which come in handy once in a while. In driving brads or nails in small mouldings or wherever there is danger of their splitting the wood, and one is not prepared to drill for them, cut off the point of the nail with a side-cutting plier or by hammering it against the sharp edge of the back of the hatchet. This gives the nail a chisel point which, if driven so as to cut the grain, will prevent any splitting. To drive a nail where one cannot reach to start it, drive the nail through a stick or lath and very near the end; holding the stick in the left hand, one can place the nail and drive it wherever one can reach with the hammer. When the nail is solid, pull the stick away and drive the nail home. When toe-nailing thin stuff, if the point of the nail is bent slightly in the direction it is wanted to go it will not come out on the back side. Yellow laundry soap or beeswax are great helps in driving nails and screws in hard wood, and for driving the larger sizes of screws there is nothing to beat a screwdriver bit in a brace.

DEPTH GAUGE FOR SAW. A home-made




Fig. 1. A Simple Gauge for Sawing the Depth.

depth gauge for the ordinary saw can be made very easily as shown in Fig. 1. Saw to the approximate depth with the body of the saw and finish to the exact depth with the point.

SAWING TRIM TO LENGTH. In cutting up random-length stuff for casings or jambs, it should




Fig. 2. Drive Nails into Board the Distance from Cut-off End You Wish the Trim Pieces to be Cut.

be cut with as little waste as possible. To do this quickly, put a 12-inch plank or board on a couple of "horses" and drive nails into it, as shown in Fig. 2, so that from each nail to the end is a proper distance for some piece of stock. Place the end of the piece against the nail which will give the proper length and saw off at the end of the plank. These lengths should be a little longer than the finished piece is required to be. Place another "horse" a little to the right to support the other end of the piece, so as not to break it when sawing.

MORTISING DOOR FRAMES FOR HINGES.

It is twice as quick and a lot easier to cut the mortise for the hinges on the jambs and transom bars on the bench before the frames are nailed together than to do it after they are set. It also shows exactly where to place the backing for the hinges when setting the frames. With the plans to work from, it is not difficult to get them correct for right and left-hand doors. If frames are made $\frac{3}{32}$ inch wider than the size of the door it will save a lot of planning when fitting the doors.

NEAT CORNER JOINT FOR MOULDINGS.

In putting down base which has no moulding, but

simply a rounded edge, coping does not make a very good job. The following way is better: The first board should be cut off square and of length to fit snugly against the plaster, and nailed in place. The next board should be 1 inch longer than the exact length required. Set this piece in place as near its permanent position as possible and scribe with a pencil set at $\frac{7}{8}$ inch. Cut off on this line to within $\frac{3}{8}$ inch of the top and then finish the cut at an angle of 45 degrees. Put board in place with the projecting piece resting on top of the board already in place, push tightly against the wall and mark along the bevel. Remove board, and with a chisel cut along the mark and about $\frac{1}{2}$ inch deep. Put plaster end of the board in place first and then shove the fitted end into place, allowing the projecting piece to rest on top of the board until it is tight against the wall, then drive it down into the place cut out. This makes a mitered joint for $\frac{3}{8}$ inch at the top and the rest of it is a butt joint. If made well, this makes an excellent joint and one that looks well. This method can be used for round edge chair rail with equal success.

LAYING OUT STAIR WINDERS. In building stairs with three winders, the following is a good and easy way to divide the wind into three equal parts: Lay out the full size plan of the stairs on the floor directly beneath the stairs, or if not convenient there, some other place where there is plenty of room. Draw the lines for the wall and the front stringer and locate the newel and the risers, A and B, as shown in Fig. 3. With the point C as a center and any convenient radius, draw the arc, DE. With the same radius and D as a center locate the point F, and with the same radius and E as a center locate the point G. Draw lines from C through the points G and F. These lines divide the wind into three equal parts, and each represents the face of a riser. If a newel is used at the angle, the point C should be inside the face of the newel a distance equal to or greater than the distance the treads project in front of the riser. If the stairway is entirely enclosed the point may be farther out, depending on the amount of room and the desired




Fig. 3. Each Winder Tread is a side of an Equilateral Triangle.

width of the winding treads. The line of travel is about 16 inches from the rail and the winders at this point should be of the same width as the rest of the treads. From this layout the exact size and shape of the winders can be gotten.

NAILING GUIDES ON STAIR STRINGERS.

While housing stair stringers, drive a nail through the stringer, from the housed side, in the center of the tread and near the front edge and in the center of the riser and near the top. Pull the nail out and the hole will mark the centers of the treads and risers on the back of the stringer and be good guides for nailing when putting the stairs together.

A GOOD TRICK. A brick mason had drawn on the floor of a full size elevation of a segmental arch and asked the carpenter to cut a center for it. Now, to some it might be a puzzle how to get the lines on the floor transferred to the board used for the center; but it was easy for this one. He took a handful of shingle nails and carefully placed them with the head on the line, at right angles to it, and about an inch apart. He then placed the board on the nails without disturbing them and jumped on it. On taking it up, the board had a line of marks corresponding exactly with the line on the floor and it was a simple matter to saw out the center.



A Plea for Thoroughness

By J. Crow Taylor

A business man who has for years made a pretty close study of woodworking said recently, while the subject of the modern idea in efficiency was under discussion: "The one common weakness in the workman of today, and the one common fault that I feel more like complaining of than anything else, is lack of thoroughness. The minds of today have been so centered on finding the easiest and quickest way, on reducing the cost, increasing the turnout, and finding ways and means to do the same work with less effort, that we have lost sight and touch of the old sense of thoroughness." Then he entered a strong plea, a plea that should be listened to, for more thoroughness.

He said that people as a rule are stronger for quality in work today than they ever were and are cheerfully willing to pay the price for work that is done in a thorough manner. And when we come to look at this matter right there is more lasting efficiency in doing work better than there is in doing more of it.

Moreover, the writer enjoys the acquaintance of a builder whose best asset in trade is this same quality of thoroughness. He is so strong headed for it that he will lose his profits on a job rather than turn it over in any skimpy or unsatisfactory shape—and it must satisfy his own critical judgment and not merely that of the man it is done for. The result is that every customer becomes a friend and warm advocate and he gets the preference on lots of work at figures above others, and gets many jobs without competition in figures.



Terra Cotta for Modern Store Fronts

FOUR STRIKING EXAMPLES OF EFFECTIVE USE OF TERRA COTTA FOR BUSINESS BUILDINGS

THE best income producing store properties present an immaculate, spick and span appearance—all shiny plate glass and clean vitrified tile.

There is advertising value in the bright, attractive appearance of a store building. The very looks of the place draws trade and inspires confidence.

The American house wife, who according to statistics purchases 80 per cent of all goods sold at retail, is a great stickler for cleanliness and sanitation. She likes to trade where everything looks clean and fresh.

All of this means white enameled terra cotta. Practically all new store buildings are being built with it and old buildings are being remodeled and turned into paying properties via the Terra Cotta Route.

The photographs show four typical Chicago suburban store buildings; one from each of the four quarters of the city. The designs are good, at the

same time, simple and inexpensive. Anyone can build business blocks like these anywhere, as the materials were all selected from stock patterns.

The first photograph shows a remarkably attractive two-story building, the front made up entirely of white terra cotta. Both the ornamental work and plain surface pieces are of this material. The window frames are painted dark green to give contrast. The second photograph shows a popular combination of white enamel brick and white terra cotta trim. The third photograph is of a conservative business building. The front is constructed of dark rough texture brick, and there is just enough white terra cotta work to give a contrast. The fourth picture is one of probably a thousand similar buildings now under construction in Chicago—a very popular type, because recent experience has proved it a money-making improvement.

If there is any store building to be done this year in your town, get around and recommend terra cotta. It will mean more business and satisfied customers for you.



Group of Three Stores on an Inside Lot; a Two-Story Building; Front is Entirely White Enameled Terra Cotta; a Combination of Plain and Ornamental Pieces.



One-Story Group of Stores Combining Ornamental Terra Cotta and White Enameled Brick in a Very Decorative Design.



An Attractive Business Place—One-Story High on an Inside Lot; Front Composed of Dark Rough Texture Brick with White Enameled Terra Cotta Trim.



A Corner Business Block Two-Stories High; Constructed of Brown Vitrified Brick and White Enameled Terra Cotta Trim. Photograph Taken During Construction.



Heating and Ventilating a School Building

HOW I PLANNED AND INSTALLED A WARM AIR SYSTEM WITH GRAVITY VENTILATION AT A SAVING IN EXPENSE

By Cecil F. Herington

"MY next adventure in heating," laughed the Old Builder, "was an adventure in building as well. You see I had obtained the contract for a small school house in which the local board had specified that a ventilating system which supplied not less than 20 cubic feet per minute per pupil should be installed. I did some careful figuring but kept my scheme to myself. After I was awarded the contract I found that while the other contractors had been spending their time obtaining prices on fans, heaters, steam boilers, piping, etc., I had gone right ahead and had determined a price which was enough less to make me safe on the lowest figure. In order to understand how I did this, I will have to explain something about the building.

"In the first place the building consisted of two wings, as shown in Fig. 1, each wing being divided into two school rooms, the idea being to keep the classes of boys and girls separate. On the second floor were located, as shown in Fig. 2, a study hall and an assembly hall which might or might not be used at the same time when the school was in session on the first floor. It was thought by the school board that the entire building should have an apparatus capable of heating it all at one time and not figuring that the assembly hall would require heating only when the first floor rooms were cut off.

Each room was estimated to seat thirty-five pupils and a teacher, making a total of thirty-six occupants who, at 20 cubic feet of air per minute, required 720 cubic feet per minute. In the assembly hall it was estimated that possibly as many as eighty-five could be accommodated so that the air supply for the second floor was about 82 by 20, or 1640 cubic feet per minute. The heat loss for each first floor school room approximated 28,400 B.T.U., while that for the assembly hall was 64,600, and for the entrance hall 8,500. This gives us a schedule as follows:

Room—	Heat Loss B. T. U.	Air Supplied Cu. Ft. Per Hr.
School Room No. 1.....	28,400	43,320
School Room No. 2.....	28,400	43,320
Hall.....	8,500	
Assembly Hall.....	64,600	98,400

"We see from these figures that if I had put in an ordinary furnace, supplying air at 120 degrees, it would require only about 1 cubic foot for each B.T.U. of heat loss; or in other words while our furnace would heat, it would not ventilate sufficiently to come up to the school board standards. If we subtract the 28,400 cubic feet of air required to actually heat either school




Fig. 1. Ground Floor Plan.




Fig. 2. Second Floor Plan.




Fig. 3. Basement Floor Plan.

Heating and Ventilating a School Building

77

room from the 43,320 actually required for ventilation purposes we have a balance of 14,920 cubic feet per hour, or an addition of about 53 per cent. Similarly subtracting the 64,600 cubic feet per hour required to heat the assembly hall from the 98,400 supplied for ventilation we have a difference of 33,800, which is also an excess of approximately 53 per cent. In the hall there is no ventilation required so that we will be perfectly safe in increasing our air supply throughout 53 per cent, and thus covering all the ventilation requirements. This gives us a schedule of:

Room—	Cu. Ft. Req. for Heating	53%	Totals
School Room	28,400	14,900	43,320
Hall	8,500	4,505	13,005
Assembly Hall	64,000	34,320	98,920

"It is usually customary on entrances and halls with outside doors to double the actual heat loss on account of draughts from open doors, so that I called the air supplied to the hall about 26,000 cubic feet per hour, or 433 cubic feet per minute. Dividing this by 260, velocity for first floor registers, we get 1.66 square feet required for the pipe area to the hall, which approximates a 16-inch diameter pipe. For the school rooms I divided the 43,320 cubic feet supplied per hour by 60, which gives approximately 720 cubic feet per minute; this, at the velocity of 260 per minute, requires a pipe area of 2.8 square feet. A 16-inch pipe which has an area of 1.4 square feet, will supply just about one-half the room, so that I placed two of these connections in each school room. For the assembly hall, I divided the 98,920 cubic feet per hour by 60, which gave me about 1,650 cubic feet per minute which, at 380, is approximately 4.4 square feet, so that a 20-inch pipe will supply about half the total quantity required. Therefore, I ran two 20-inch pipes to each of the 12 by 24-inch flues to the second floor assembly hall, using the 12 by 24-inch flues in the walls through the first floor. From these amounts we have the following total air supply:

	Cu. Ft. Per Hr.
Two School Rooms at 43,300 equal.....	86,640
One Hall at 13,005 doubled equals.....	26,010
Assembly Hall, 98,920, equals.....	98,920

Or a total of.....211,570

"In order to obtain the grate area of the furnace, I next figured out what the temperature of the air would be when this quantity of air was supplied to the room. This is done by taking the 28,420 cubic feet required for a school room for example when the air is at 120 or 50 degrees higher than the room temperature. If we supply 43,320 cubic feet instead, the temperature rise need only $28,420 \div 43,320 \times 50$ degrees, or 33 degrees rise. This gives the temperature of the incoming air as $70 + 33$ degrees, or 103 degrees. Therefore, the total number of B.T.U. required for one-half the building, is $211,570 \times 103 \div 50 = 435,834$ B.T.U.

"At 8,000 B.T.U. efficiency per pound of coal it will require 54 pounds of coal per hour and burning 6 pounds every square foot of grate this means a grate surface of 54, divided by 6 or 9 square feet.

"For the economical operation of this system in warming up the school room I arranged a recirculation

scheme, as shown in the basement plan, Fig. 3, taking the cold air from the floor of the school rooms near the windows and putting it into the cold air boxes so as to use this air rather than outside air when ventilation was




Fig. 4. Detail of Air Supply.

not required. I made the connection with a 46 by 10-inch duct which has an area of 460 square inches. This is approximately twice the area of a 16-inch diameter pipe, so that the air coming into the school rooms through two 16-inch diameter pipes would have no trouble in drawing an equal quantity of air out of the room through the circulation connection.

"The cold air intakes were run to opposite sides of the building with flap valves so as to take air from the windy side in every case, these flap valves being similar to those about which I previously told you.

"Where the recirculation joined the cold air box, a two-way damper as shown in Fig. 4 was placed so that either outside or inside air could be used or any desired proportion of each.

"Before I was through, however, I had to arrange to get rid of the superfluous air by some scheme of vents. It is, of course, safe to figure one complete air change per hour, finding its way through the windows and natural leakage. In the school rooms which had a cubic content of 9,400 cubic feet, this left $43,000 - 9,400$, or 33,600 cubic feet per hour, to be taken care of by venting. At a velocity of 250 feet per

minute in the vent flue this would require $\frac{33,600}{60 \times 250} = 2.3$

square feet of vent for each school room. I used two 12 by 16-inch vents which equal 2.6 square feet.

"For the assembly hall which had a cubic contents amount of 17,000 cubic feet, I had to take care of $98,920 - 17,000$, or 81,920 cubic feet per hour with the vents. At 150 feet per

minute velocity this means a vent area of $\frac{81,920}{60 \times 150} = 9$ square feet. I used for 16 by 21-inch vents which equal $\frac{4 \times 16 \times 21}{144}$,

which equal approximately 9 square feet.

"On the roof I placed common ventilators so as to have a combined area over each half of the building equal to my total vent areas, or approximately 14 square feet.

"The vents all had dampers so that they could be closed off when desired, which is a very good stunt to do, so that the building will not get cooled down during the night when the fires are low. I am glad to say that this system has worked well and been very satisfactory, although no gravity system of ventilation can obtain the positiveness of action which comes with the use of a fan. On the other hand, no mechanical ability or power was required for this school, and this was a most important factor in the country district where it was located."




More Shop Kinks

HELPFUL IDEAS AND SUGGESTIONS FOR CARPENTERS, CABINET MAKERS AND MACHINE WORKERS

By Wm. C. Jasbury

SOME time ago I was sent out from the shop to get instructions on some rollers wanted by a concern manufacturing waterproof fabrics. The rollers are made with a poplar core and California Redwood shell. The manager of the plant informed me the only roller that would stand up and make good, was as above; he had tried kiln-dried white pine and other woods and construction. The intense heat these rollers were subject to and their speed, was indeed a severe test. The steel shaft that passed through these rollers was 2 inches in diameter and 8 feet long. The core pieces were fastened on the shaft by grip only, same as a split pulley.

Why California Redwood is so well adapted for



this special and peculiar condition is, I think, it can be dried nearly to breakfast-food, contains an asbestos substance that defies excessive heat and can be had in large and clear pieces. This concern has a plant, the like of which I have never seen before; their working is so far from the ordinary routine of the shops I am used to; it seemed as though I had visited one of the other planets. But, as that may be, they must use the woodworkers' product in the shape of many rollers and other traps. The rollers I speak that only will stand the strain of their particular need are constructed as shown in sketch. These rollers make 300 revolutions per minute in a temperature of 110 degrees.

WHAT KIND OF WOOD IS THIS? We have oftentimes in a big shop some nice juicy arguments regarding the different kinds of woods. Some one will get hold of an odd piece and start the ball rolling. The wind-up is usually a few bets and send the accused sample to the U. S. Forestry Investigation Plant, at Madison, Wisconsin. Those gentlemen are very kind in sending back the answer, which is always final. So you see, if we do not have the knowledge, we know where to get it.

SPEAKING ABOUT WOODWORKING, the mechanic of today, to be classed as front seat, has to have a knowledge of reading plans and details. Take, for instance, the blue prints of a modern house where the electric wiring, plumbing and heating, and all that, make so many lines it looks like a bushel basket full of overgrown spider webs, mixed with New Orleans molasses and the notes, wording, names of various new-fangled parts and kinds, for instance—where they read Mezzanine floors, Callamine doors, Kopalia base, Cain floor, Alberene stone, Pantasote covered doors and many other hieroglyphics off the monument. Years ago the carpenter boss was an old chap with whiskers that had seen the Presidents back as far as John Adams, a pair of spectacles that were made from port-holes of the Santa Maria, etc. But today the foreman carpenter is a smooth-shaven male, with a white collar, a steel square and a scale rule. It only goes to show that we (I say we, because I have both—smooth shave and steel square) are living in an electric, gasoline age, where everything is in high gear and voltage of go-aheadness. Thanks to the printing presses and such.

We hear so much new stuff in the building trade nowadays, it is enough to make old man Webster come back to the old U. S. A. and have a few bay windows built on his dictionary. Some of the more velvety terms I have heard of late on architecture are frozen music. A skyscraper of today's construction is practically a bridge built on end; a hothouse conservatory is a season revolutionist; a garage is where the odor of gasoline and rubber is kept; a bathroom is a place used for the removal of scale from God's noblest animals. An ice house is a place where fresh water lakes are kept in chunks; a barn is a place where man keeps the earth's whiskers (hay) and the runabouts that eat such. A railroad station is a comma in the story of a railroad trip. A church is a building with a roof pointing in the direction of the manager's theme; a school house is a place where the coming generation spends about seven hours of the day listening to such tales

as the Burning of Rome and the Destruction of Reno. A City Hall is a place that uses iron bars in the foundation, placed so close together the lower elements of the city complain of the spacing of such; a tenement house is a box-like affair, thickly infested with foreigners and their pets. A hotel is where many homeless people are deprived of the privilege of putting their feet under their own table; an office is an instrument used to keep grandsons from baseball games. So you see, if it were not for the new buildings and new parts of buildings, our line would soon be a victim of fungus growth. I shall now get a period ready to place, but would like to say, that "He who has written something worthy to be read, has conferred upon mankind a greater blessing than the man who invented perspiration."

DOOR TRIMMING DEVICE. I recently had an occasion to visit a new building under construction. While there, I chanced to notice carpenters putting on furring-lath, or nailing lath on the door stud, for the masons to plaster to. There are so many different ways of doing this job; but on that particular job, Mr. Carpenter took two straight shingle ribs, 1 by 2-inch, about 6 feet long, and three pieces of 1 by 2-inch cross pieces. This material was nailed together in a sort of frame. This he stood up, or tacked against the door stud, a plumb line dropped from the top cross piece to below the bottom cross piece. The pieces were centered, or equally divided between the two long uprights. When the plumb line coincided with the center lines and the plumb-bob stood still, he tacked the top and bottom cross pieces to the door stud, then he put ordinary plastering lath on the door stud, projecting over the present lath $\frac{1}{2}$ inch. The lath was $\frac{1}{4}$ inch thick, the furring lath and plaster at the finish, $\frac{3}{4}$ inch, which seems to be the standard the country over. The reason this implement, or similar ones, are used, is to be sure to keep the wall at the doors the same thickness, so that the finished jambs will come same width, and the plumb-bob is to keep the jambs plumb, so that the door will hang properly. Everyone has seen doors that would not stay shut, or open, on account of being hung out of plumb; then again it gives the mason lines to plaster to.

EVERY LOCALITY HAS ITS STYLES. While I am collecting my thoughts as to woodworking

stunts, of which this article will consist, ultimately allow me a few moments of your valuable time to get some of the incidents and such out of my system. Will try to confine myself to woodworking and building. Some years ago, to be correct, 1893, I toured Europe, my first landing being at Southampton, England. I saw no wooden buildings, no wood fences, etc., in fact, I visited one farm in Ireland of which there was 300 acres and only one tree. One would naturally look upon a carpenter in such places as the Lost Chord. When I returned to the United States, having gotten used to the stone age, it looked to me as it did to the regular immigrant, everything built of wood, these people are only going to stay here a few weeks. Later years, I was in Denver, where shingles are only seen in museums, slate being the house covers. While standing on Market Street, San Francisco, before the earthquake and fire, I counted 336 octagon bay windows on the Palace Hotel. While in Mexico, the number of adobe houses would certainly convince you that they had no place for an architect to hang up his hat; and so it goes; everywhere the conditions in the building business seem to have been changed to suit the large or small fancies and pocketbooks of those living thereabouts.

SOME STICKER. Recently I heard a bunch of cabinet makers discussing various topics at some length. The odd part of it was they could not speak to each other very well in their own tongue; they were getting it out in alleged English. The question, or part of the epidemic that I caught was the word they used for dowel, ordinary dowel pins, such as mill work is sometimes put together with.

The German man called it *Deible*.

The Italian man called it *Keno*.


The Saxonian man called it *Dovetail*.

The Hungarian man called it *Minden*.

The Jewish man called it *Fleckal*.

Can you wonder the saloons do such a good business? And some of these mushrats will get rich while I am still trying to (like the old lady) mop up the tide.

HOW IS THIS? I have often heard mechanics argue on the odd tricks of the trade, such as a 1 inch plug will not enter a 1-inch hole. There must be some slight difference. While I am not yet a scientist, or professor in the higher geometry, I cannot explain this as would one of a finer mental texture, but my answer to the question would be, there must be some difference in the size of the plug, or holes, because if they were both the exact size, they would be as though a pair of compasses were taken to draw a very fine line, enclosing a 1-inch diameter circle; this of course, would represent the plug and hole, as they actually appear when the plug is in place, but to extract the imaginary plug would mean there would be a certain amount (very minute) of air space between plug and opening, therefore they are not the exact size.



CORRESPONDENCE



Questions Answered and Ideas Exchanged.

Our Readers Are Requested and Urged to Make Free Use of These Columns for the Discussion of all Questions of Interest to Carpenters and Builders.

Keeps Copies on Drafting Table

To the Editor:

Coquille, Ore.

I have just closed a fine contract for a nice little bungalow 46 by 51; cost, \$3,000. I made all my own plans and specifications and can give the AMERICAN CARPENTER AND BUILDER credit for most of my knowledge in this line. I have been a subscriber to your magazine for some time and have them all on my drafting table and refer to them very often.

F. A. CHILD.



Which is Right?

To the Editor:

Clarksville, Tenn.

Am sending you an outline of an argument to settle. It concerns the header over a window on a brick wall. I contend that No. 2 is the best, while the other party thinks different. No. 2 has a 6-inch bearing on the wall and the other has nothing except the ends of the two joist that support the header, which is connected by nails. All joist, except the two that support his header, hang on the header also; they cannot have the support and strength that No. 2 can. Which is more practical and best? Which would the modern




FIG. 1




FIG. 2

Two Ways of Seating Floor Joists in a Brick Wall.

carpenter framer use? It is only a matter of strength, not looks.

I say that the framing which will be dry always, will be as good and remain so as long as the brick work. He says it will decay, and it is best to build brick on brick, which is why he says to shift the header off the wall.

I am tearing down a brick structure built in 1841 and the wooden blocks in the brick wall are as sound now as they were the day they were put in, and it is all that way, except where it was exposed to an almost continual flow or drip.

Please settle this for us.

JACK H. AYRES.

Answer—If the decision were left to us, we feel that we would have to decide in favor of the other fellow, as being the best job, from a mechanical standpoint. However, others may think differently and we are willing to leave the subject open for further decision higher up.

Our objection to No. 2 is that it cuts out too much of the wall, thus weakening it. Take a 17-inch wall for instance, nearly one-half of the wall is cut away by the header when resting on the wall, and might as well be counted one-half as there is a two inch space left that can only be filled in with bats and mortar and often times not even that,—unless the boss is on the job to so direct. Then again, the brick do not always come out even with the top, thereby leaving more bats and mortar to be built on top to bring the courses right. Whereas the other way, brick is built on brick the full width of the wall with only the ends of the trimmers resting on the wall and the header being so close the bearing cannot weaken the joist for all ordinary purposes.

A. W. WOODS.



Sliding Door Jambs


To the Editor:

Fullerton, Pa.


In the May issue of the "A. C. & B." there appears an article on page 47, "How to Frame and Hang a Double Sliding Door," by E. J. G. Phillips, which will undoubtedly be of good service to many carpenters who have to do sliding door hanging. However, according to the sections shown, of the method of rabbetting the jambs, I would respectfully suggest to Mr. Phillips that according to my experience those jambs are made up wrong.

As may be readily corroborated by brother carpenters, it would be a rather difficult proposition to remove these self-same jambs after the doors were once hung. This may readily be verified by taking note of the way the rabbet is made. I am of the opinion that it should be made as shown

SLIDING DOOR JAMBS.



MR. PHILLIPS' WAY



A BETTER WAY

Cross Section through Sliding Parlor Door Jambs.

in the accompanying sketch, in order to be easily removable. I have invariably made them as shown and with satisfactory results.

Perhaps Mr. Phillips simply made a mistake in making his drawings; at any rate, I cannot see the advantage of making the sliding door jambs as he shows them.


JOHN WAVREK, JR.

Something About Porch Building

To the Editor:

Omaha, Neb.

My sketch shows the plan of porch column and rail and the elevation. What I wish to show more than anything else



in this is how to lay out the framing so that the porch beam will be properly centered on the column when they are set in position. There are porches built by the hundreds all over the country where the porch beam does not center with the column. In some cases the amount that the beam is off the center may be small and not very noticeable except to a trained eye. In other cases the difference is so great that most anyone can see it. When this is the case it makes the work look bad. For the work to

look right the center of the beam should center the column exactly.

In the sketch, A represents the outside of the bottom frame work and B the outside of the top frame work. In this case the top beam lines up with the bottom frame work, but there are many cases where the top frame work has to be set back an inch or more to make it center with the column. This depends upon the size of the columns and how they are set at the bottom. See the central line of the column in the sketch, measure from this line out to the face of the frame work both at bottom and at top, and you will be able to see readily if the top frame has to be set back any to make the work balance up right. I have seen many porches with the columns an inch or more off the center of the beam. I have even seen columns set out of plumb in an effort to overcome a portion of the amount beam was out of center.

These little troubles in porch building happen most to the carpenters who build without plans and details, but with a little care in laying off the frame work all trouble of this kind can be readily avoided and it is easy to have the work come out just right and the appearance more than pays for all the time spent in making careful measurements.

I. P. HICKS, Architect, builder and Estimator.

Troubled with Sweating Plaster

To the Editor:

St. Louis, Mo.

Will you kindly advise through your correspondence column a satisfactory method of treating moisture from plastered walls caused by reason of adding salt in freezing weather in the plaster before applying. We had a cottage plastered two years ago during freezing weather, and the contractor added a considerable quantity of salt before applying. We are troubled with sweating of the walls during each rain storm or during damp weather.

J. F. MCKELVEY.

Is Serious About Bungalow Finishing

To the Editor:

Maywood, Neb.

I am of the opinion that W. E. B., who asked advice concerning the casing of bungalows, must have received great benefit from that very intellectual (?) letter written by Mr. Noel Hogg.

I am personally acquainted with a carpenter (?) who practices just such artistic ideas with regard to anything new or up-to-date as this man's letter would indicate; he is now building 8 by 12-foot garages for farms, and small shacks; while the more wide-awake and up-to-date men are doing all the work of consequence.

We would like Mr. Hogg to inform us where good workmanship (or poor) will show up with better credit to the builder than on the low roofed, quaint, all-on-one-floor handy home of today.

Anybody that has the proper respect for the trade will not make a botch of it and then try to cover his mistake with black paint and by assuring a "meant to do it" air; and if the citizens of Sterling, Colo., will fall for such horse play they are a less advanced community than the world believes them to be.

In regard to the cupboard doors, Mr. W. E. B., I will say the right hand door facing the cupboard should lap over on the rabbet. As to the finishing inside, I prefer Colonial for myself, or Mission. C. L. MARSHALL



THE BOSS CARPENTER

Harry D. Forsyth, Bay City, Michigan can be proud of this young Builder. He's a chip off the old block and Harry says he is already the boss.


More Light From Bro. Gonne

To the Editor:

Highland, Mich.

Brother A. G. Brown described my method of setting door frames in the June number of *THE AMERICAN CARPENTER AND BUILDER*, as far as he went, but there is more to it, as I go at it. After framing my jambs, I put them together exactly even at the top and make a mark square across the edges of both, about 16 inches above the bottom. Exactly to this mark I nail my spreader, which I make by nailing a strip on the edge of a board about the width of the jambs. This board should be straight and just the right length to fit between the jambs. I always square my frames by making the distance between A and BM and C and D exactly equal; then I put the side casings on and set frames and I can do the work faster and more accurately than setting jambs alone.

The cupboard door shown here is made of ceiling and will not sag as quickly as one with cleats on the back. I used the beaded edge of the same material or run a bead on some strips, if I have them, and nail them with 8d. finishing nails across the ends of the ceiling board after they have been clamped up and cut square about $1\frac{3}{4}$ inch shorter than the opening. The strips should be about 1 inch wide, of pieces that will not split easily; and the nails should be staggered and set deep enough to allow fitting the door to the opening.




SPREADER FOR DOOR FRAMES

about any line of work that I have not done myself and that many times. If Mr. House had read the "Kinks" carefully, he could have seen that the sketches and reading matter did not correspond.

I am reminded of the story I once heard of the man who could not read. He thought there had been a great storm at sea, as the pictures of the ships were all bottom side up. He simply had his paper wrong end up. He said my bridge cutting was a joke. I think the joke is on him.

ALBERT GONNE.

The sketches shown in April number, with "Karpenter Kinks," were not reproduced as I made them and I am anxious to have them shown as they should have been. I have been actively engaged in building for almost 30 years, and, like Brother L. R. House, "I have built 'em and therefore I know." In fact, I have not written an article




CUPBOARD DOOR

NOTE: As the sketches referred to, were made from rough pencil sketches, submitted by the writer, it is im-

possible to say now whether the drawings as reproduced were exact copies of the originals, or not.

But there is one thing sure, if the writers would only send us half-way decent sketches we will guarantee to get them



Wood Forms for Concrete Stairs.

out in presentable shape. We pride ourselves on being pretty good in deciphering puzzles, but there are times we have to throw up our hands and make a wild stab, and guess at the rest.

EDITOR.



Old Time Woodwork

To the Editor:

The interior trim and wood finish of today, although more elaborate and put up with better or more modern tools, does not stand the test like the jobs of yore, and I am going to appoint myself a committee of one to discuss this state of affairs. There may be many readers of the *AMERICAN CARPENTER AND BUILDER* that will try to explain where I should have thrown in an adjective, or canned a few adverbs, etc., but this article is as the current strikes me. So listen to the band!

The woodwork in and outside of the George Washington homestead, Mt. Vernon, Va., is today in the finest state of preservation; joints are up, very little shrinkage, rarely a piece of rot, etc. The old "Tennant Church," Freehold, N. J., where the same George Washington sheltered his faithful men when he was doing a marathon across this state in pursuit of Mr. J. Bull's representatives, have the very same shingles on today that were on then. They are of cypress wood. The same benches, or pews, until recent years, had the blood stains still visible. And many other buildings that I have been in and inspected, show the woodwork in good condition.

Now comes the reason—my reason (mind you). When these houses were put up, the material was cut at the proper time of year; the seasoning was taken care of by those close to nature; the trees or logs that were healthy and worthy of such work were the only ones used. The work was put up by men who did not have to tear and jerk with a square-headed foreman over them. They were after quality, not quantity; buildings were made to live in in those days, not built to sell. The modern, or up-to-date methods of treating lumber, is to get the stuff out on the job as soon as possible.

Some concerns handle such bum material, they have to use an auto delivery so that it will not rot before it gets to the job. The grade of material of today has gone so far down and the price so far up, they look as though they had never met. It is getting so, nowadays, people are paying for Irish mahogany (hemlock), as much as they paid for No. 1 white pine thirty years ago, and to buy 1-inch lumber, the Western or Southern mills are planing to $\frac{3}{4}$ inch thick, also all other thicknesses, reduced so that a fellow has to have a rule that closes up like a telescope. I am inclined to believe one of the causes of the warping and shrinking of interior woods of today is the excessive heat in the homes. Whether or not the large manufacturing concerns making people, put as much blood in them as they used to, or whether they are using an inferior material, the twentieth century congregation do not seem to be contended unless they have a hot bath before supper, hot towels, hot-water heat, hotbed-sash for out in the yard, hot tamales for lunch, a hottentot for a servant. We are simply developing into a race of hot-house plants. What has become of the tough, old-fashioned folks? For instance, the old guy that could take a drink of water without removing his quid. That *quid* may spell *cud*, but it never looked good to me; quid sounds too much like the Back Bay dialect. (Been in Boston?)

But speaking about the old times, when they used to get their whiskers frozen in the wash basin out on the back porch and have to go in behind the stove with the hound-dog until they thawed out and when they had to go out in the A. M. and break the ice on a swill barrel before they could feed the pigs, "those were the good old days." The farmers of years ago, and perhaps some of the modern ones, put their oak and hickory that they want to season for wagon and farm implement work, in the hay-mow, claiming the odor of hay assists in curing or seasoning the wood with an extra amount of toughness. Air-dried lumber is superior to kiln-dried lumber, because the natural ingredients are not killed, or solidified by excessive heat. The air-dried variety is closer to nature. Take cypress, for instance; in a square 5 by 5 feet, or any other size, to cut off a piece from the end, you will find the center wet; to me it looks like a round of beef in a butcher shop immediately after Mr. Butcher cuts off a steak.

The reason cypress always seems wet inside, is this: It grows in the low or swampy ground, consequently water is its chief beverage. Then, when it is being dried, or seasoned, the peculiar part of cypress is, it contains a resinous substance. This resinous substance solidifies by being attacked by the air or heat, that makes the exterior or dry part impervious to the heat or air; consequently the water stays where it is, or in other words, stands pat. In the old houses where fireplaces and stoves supply the heat, you will find the wood-work in a much better condition than where hot air, steam or hot water is now used. The furniture of today will not stand up with that of yore, for the above mentioned reasons.

Now, this is, as I said early in my ravings, "my opinion" and idea; others may differ and contradict. Help yourself. Take the trim put up in a house that has just been plastered; of course, there are many barrels of water in the wall yet to evaporate; well, then, if the trim is kiln dried and put up against these seemingly dry but still wet walls, the drier part or trim will absorb the dampness like a blotter will take up ink. This swells the wood and when the heat we have been talking about dries out the trim, it shrinks again and there you have some open joints. Every practical carpenter seems to have an answer to this wood-drying and shrinking question; it could be carried on; in fact, Mr. Bryan could lecture on it, only he would not confine himself to oak, hickory and cypress, but would throw in a few grape vine pieces.

WM. C. JASBURY.

What is the Best Thing to Do?

To the Editor:

Winchester, Ohio.

As I see so much good information passing on to others in direct reply to their troubles through the Correspondence columns, I want to come forward with a query of my own; but first allow me to say, that while that information is passing through these columns,—volumes of it,—do not think I let it all pass. I try to glean some of it for my own use and profit by the experience of others, given for the benefit of others.

Now, for the information I want. Am enclosing a rough sketch of a two-story brick building, 13-inch wall, with galvanized iron front, which stands at the present time about 5 inches out of plumb, or sprung in the center, as clearly indicated by the dotted lines, which represent its present condition. There is a center wall through the building,



Store with Sprung Walls.

dividing same into two rooms below and two above. Upper rooms unoccupied and the building stands apparently as level as when first erected, which was several years past, without any cracks in the walls, or settling of same.

What I would like to have, is the opinion of some of the craft as to what would be the best remedy. It has been viewed by an authority on building, and he says that to take the old foundation out (which, by the way, is no good) and replace with a new one will stop the creeling of building; but I cannot see it that way. It looks to me as though the only way to remedy it with any degree of satisfaction, would be to tear down and rebuild. He thinks the creeling is caused by settling of foundation, but it seems to me if such were the case, there would be some cracks in the wall, or some other visible signs of settling; but there are none noticeable. The whole building just seems to be gradually springing sideways at the second-story line, as shown by the dotted lines.

Would like the opinion of some of the readers for my own benefit, or any comments they may feel disposed to offer.

Will say further, that I am one of the Charter members of THE AMERICAN CARPENTER AND BUILDER and have every copy of same handy for reference; and it has been seldom that I have ever consulted them in vain for any problem for which I needed assistance. I am not much of a correspondent but think I will be back some of these times in reply to one of the correspondents who thought our "calling" was something that it was necessary to "steer clear of." I cannot agree with him.

A. C. STIVERS,
Carpenter and Builder.

**Shingled Gothic Church**

To the Editor:

Clinton, Conn.

Some of the readers may be interested in the accompanying photograph of the new Catholic church I recently completed here. Whiton and McMahan, of Hartford, Conn., prepared the plans. It is a shingled building designed in the Gothic style. It shows several good features for an inexpensive church building.

I want to say that I am a charter subscriber to the AMERI-

ICAN CARPENTER AND BUILDER and like it very much. I find it extremely valuable in my work; think it is better now than ever.

ALVA H. PIERSON,
Builder and Joiner.

**A Simple Bookkeeping System**

To the Editor:

Council Bluffs, Iowa.

The Fred Tucker time slip shown in the July number is not a new one, but is a good one just the same. I not only keep time this way, but keep books as well; and one book is all I need. I use a fold over check book which has stub same size as check. On each stub there is room to state briefly what the check was given for. From my stub book I post into a separate ledger, which has headings similar to Fred Tucker's time book, as for instance Jones job, Opera House job, Incidental jobs, etc. I separate my household expenses in the same way, as for instance, Music, Coal, Shoes, Taxes, Club, Papers and Magazines, etc.; all at the top of page just like in the Tucker time book. My check book is posted once a day into this book, which keeps all the accounts separate. There can be as many of these as you please.

I also have a credit page for money received. I make original entry of money received right onto the backs of stubs in my check book, so that it is really the only book I have to carry.

I recommend this as a satisfactory system for an up-to-date small contractor. Just try it.

GEO. F. HUGHES,

General Contractor of Building and Public Works.


**Large Tobacco Barn**

To the Editor:


Gettysburg, Ohio.

Here is a photo of a barn I have just raised. It is 36 by 100 feet and 20 feet high to the square. Sixty-two feet is arranged to hang tobacco in. The remainder is to be fitted up for a modern barn and stabling room. It is to have an asbestos shingle roof.

W. R. INMAN,
Contractor and Builder.



Contractor W. R. Inman and His Gang at Work on a Heavy Timber Barn 36x100 feet, at Gettysburg, Ohio.



Through this department the editors aim to keep builders, contractors, carpenters and architects in touch with what their friends, the manufacturers, are doing for them in new or improved tools and machinery methods and materials—pertaining to building. Items for these columns must have real news value; they are offered here as interesting information for our readers; they are not advertising. No matter will be printed here simply because some advertiser wishes it. Likewise, no matter will be excluded simply because the article described is not advertised in this magazine. Suggestions for the betterment of this department are requested of our readers.

Birch for Interior Finish

By R. S. Kellogg

BIRCH trees are common in the Northern woods from Maine to Minnesota, and wherever found they are among the most striking and beautiful inhabitants of the forest. The Yellow Birch, which is the chief source of Birch lumber, reaches its perfection in Wisconsin and Michigan, and more than one-half of the total cut of Birch is manufactured in these two states. It is a well known fact that the individuals of a species attain their best development in the regions where that species is most abundant. For this reason the Birch lumber from Wisconsin and Michigan is of the highest quality. The trees are large, symmetrical, clear, and sound. A height of 80 feet and a diameter of 30 inches is not uncommon. Timber of this sort yields a finishing wood which has no superiors, and few competitors. The city dweller of today prizes Birch wood-work in his home as much as Hiawatha did a Birch bark canoe. Both are evidence of good judgment in the selection of materials.

The wood of Birch is close-grained, and heavy. In bending and crushing strength, stiffness, toughness, and hardness, it ranks above many hardwoods and stands with beech, hard maple, and oak—woods whose qualities in these respects are universally appreciated. It is the close, interwoven structure of Birch that gives this wood its strength, density, wear-resisting, and stain-holding qualities.

The sapwood of Yellow Birch is yellowish, the heartwood light to dark reddish brown. It is the heartwood of Birch that furnishes the beautiful Red Birch, which has no superior even in Mahogany. Both sapwood and heartwood take a brilliant, satiny polish. The figure of curly Birch is especially attractive, while the sparkling lustre of the finished wood gives a richness of tone such as is usually looked for only in the costliest imported woods.

Uses of Birch

Birch is one of the most widely useful woods. A recent tabulation of factory reports shows that Birch is used for nearly 200 distinct purposes, ranging from automobiles to zither bodies, and covering such diverse articles as barber chairs, billiard tables, wagon bottoms, cheese boxes, butter moulds, electrotype bases, wagon hubs, piano cases, refrigerators, shoe pegs, spools, farm implements, and interior finish.

More than half of the total output of Birch is used in the manufacture of furniture and fixtures, and for mill-work. The latter includes all kinds of interior finish, veneered doors and high grade flooring. In fact, it is in the field of interior finish that Birch finds its highest and most appropriate use. Employed originally as a substitute for Mahog-

any, Birch is now appreciated for many sterling qualities of its own, some of which are not possessed by Mahogany.

There are many styles of Birch trim as there are designers who wish to produce an unusual or particularly appropriate effect. In my office, I have 24 kinds of Birch moulding, casing and base, that are only a few examples along this line, while in the field of grille and stair-work the variety is even greater. My own preference is for the simpler styles which offer the fewest possible angles and corners to collect dust and at the same time give the largest uninterrupted surface to display the figure and sheen of the wood itself. For the same reason, my choice is for the softer hued stains, which bring out the qualities of the wood in harmonious fashion, rather than for more brilliant colors, or paints which completely obscure the natural beauty of the wood. We paint iron and brick for protective reasons as well as to give a more pleasing effect. When we work with wood it should be our purpose to enhance and not obscure its characteristics of figure, color and grain.

The perfecting of veneering processes, and especially of rotary cut veneer, enables us to get at a reasonable price a combination of large sizes and beautiful figures in panels that would be altogether impossible were we restricted to solid lumber. Moreover, the well built up panel is stronger and much less likely to warp or check than is a solid piece of wood of the same or even much greater thickness. Veneered panels may be obtained in almost any size desired, and where appropriate they provide a wonderfully effective means of interior finishing.

Recent years have seen a great advance in the manufacture of artistic doors, which are at the same time simple in design and reasonable in price. Here again, progress has been made by the use of veneer. There are many styles of doors to choose from. One of the most pleasing to me is a single panel Birch door stained silver gray, but other styles have many admirers.

Hardwood Flooring

Among the most useful developments of modern lumber manufacturing is the production of high grade hardwood flooring. This flooring is manufactured to exact sizes from selected, thoroughly seasoned stock, and is as carefully handled as is interior finish. In fact, a beautiful and durable hardwood floor is an important part of the inside of a building, now that carpets have been replaced by rugs.

Hardwood flooring is made from kiln-dried stock, is stored in dry sheds and shipped in closed cars to prevent the absorption of moisture, and the user should see that it is carefully handled, correctly laid, and properly finished. Some of

GORDON-VAN TINE

Fall Challenge Prices

To 10,000 Shrewd Buying Contractors

5,000 BARGAINS
For Building and Remodeling
SHIPPED ANYWHERE

QUICK DELIVERY
Subject to Approval on
Inspection

Highest "Graded Up" Quality

Surfaced Lumber—Not Rough. Even Widths—Not Uneven. Graded Up—Not Down. Highest Grade—Not Knotty or Crooked.

"Guaranteed Right" Cost Estimates FREE
Prices Low and Quality the Very Highest





Jap-a-Top Roofing

Beautiful—Durable. Surfaced with genuine Slate. 2 colors—Red and Grayish Green.

\$2.25 per roll of 108 Square Feet

Jap-a-Top Shingles
Price per sq. of 424 Shingles \$4.75

Also Other
Quality Roofing
as low per roll of 108 sq. feet, 90c.




Wallboard Bargains

Wallboard is The Great Modern Substitute for Lath and Plaster. Also fine for partitions to finish off rooms, attics, etc. Comes in sheets ready for use. Goes on dry. Cold-proof, vermin-proof, handsome, durable. **Beats Plaster. Costs Less.** Wallboard costs 50% less to lay. Lasts as long as the building.

Quality Wallboard

1000 Square Feet, \$22
See Special Wallboard Offers in Grand Free Catalog.

Prompt Service
Anywhere You Live--On
Any Size Order--
Write Today



LUMBER in Car Lots

Save \$100 to \$300 Our special Latest Lumber List and FREE Book above offer choice to you of millions of feet of clear, dry, clean, seasoned lumber at Wholesale Prices. Dimension, heavy Joists and Timbers, Drop Siding, Beveled Siding, Ceiling, Partition, Wainscoting, Finishing Lumber, Laths, Shingles, Boards, Posts, Poles, Battens, etc. All lumber graded in accordance with rules of the Lumbermen's Association. All Millwork of High Quality Standards, established by the Northwestern Sash, Door and Blind Mfrs. Ass'n. Every stick guaranteed up to standard quality. Estimates furnished FREE on guaranteed costs to you. **BARGAINS** in Moulding and Finish. Many special designs. All latest new stock. See big Reductions in 1914-1915 Grand Free Millwork Catalog, just out.

We ship promptly to anywhere you live by Fast Freight—Safe Delivery, Quality and Satisfaction Guaranteed or Money Back.

5,000 Bargain Catalog FREE

Our Grand 5,000 Building Materials Catalog has been the marvel of the building world year after year for years. 10,000 shrewd Carpenters and Contractors get it every year. Latests, biggest yet, "value-judging" and "quality-price-making" 1914-1915 Edition **just out.** YOUR COPY waiting only for your name and address. Writing for it does not obligate you in any way. Invaluable as a price record, idea suggester and economical building and remodeling authority in every home. **GET YOURS. WRITE TODAY.** Postal gets it by return mail quickly—**FREE.**

Doors as Low as 77 Cents

All Styles and Sizes
Quality Guaranteed

Hundreds of special designs—glazed and unglazed Oak, White and Yellow Pine, Cypress, Fir, Oak Veneer, solid Yellow Pine and Front Doors.

Shingles

Extra "Star A" 6 to 2 in., Washington Red Cedar Shingles, Price per thousand \$3.10. Special prices on Bevel Siding or Clap Boards, Red Cedar Siding, White Pine Siding, etc.



Windows and Glass

Check Rail windows, 74c. up. Plain rail, glazed, 66c. up. Transoms, 40c. each. 8x10 window glass, 34c. per light. Any size, large or small, at equally low prices. Safe Delivery Guaranteed. See Grand Catalog. Dealers charge from five to ten times our prices on glass.

Builder's Hardware

Everything in Builder's Hardware direct to you at wholesale—hinges, locks, doorsets, window sets, etc.

Storm Sash and Doors

Anticipate for winter NOW. All sizes. All styles for every window or door, house or any building. Also builder's hardware, hinges, knobs, locks, catches, buttons, etc. Serviceable Storm Doors and Windows of "A" Quality and Painted.

All White Pine STORM SASH as low as 72c. STORM DOORS as low as \$1.43.

See Big Catalog Bargains

GORDON-VAN TINE COMPANY, 716 FEDERAL ST., DAVENPORT, IOWA
Business Originally Established 1863—49 Years

Experience in Service and Square Dealing

Everything always sold at wholesale prices direct to you

the points to bear in mind are to avoid unloading the flooring in damp weather; not to store it in open sheds or in newly plastered buildings; nor to lay it until the building is thoroughly dried out. When an under-floor is used, as is advisable with the thinner sizes, the flooring should be laid diagonally across the sub-floor, and the latter should be dressed to even thickness. The best practice indicates the use of steel cut nails for hardwood flooring. The nails are manufactured especially for this purpose and should be driven at an angle of 45 degrees.

Wherever a particularly rich effect is desired to harmonize with finish and furnishing, nothing is superior to a selected Red Birch floor. It is as strong as maple, sufficiently hard to stand service, and of unusual beauty of figure and color. Such a floor finished natural is not out of place in the most palatial structure.

Birch flooring is manufactured and graded under the rules of the Maple Flooring Manufacturers Association, and it is a high class standard product in respect to widths, thickness, and quality.

The demand for conveniences and economy of space has resulted in a wide variety of built-in work all the way from kitchen to bed room. Built-in book cases, china closets, side-boards and ward-robos are considered among the necessities of the modern residence. For them no wood is superior to Birch. In addition to its desirable qualities of figure and color, Birch looks well and fulfills every requirement of a high-grade cabinet wood. We have all seen beautiful examples of built-in work that harmonize perfectly with finish and furniture which are also the ultimate of convenience and utility. Large quantities of Birch have for many years gone into furniture factories to emerge as Mahogany. The only fault we have to find with this is that Birch has not received the popular approval it would if the furniture had been generally known to be Birch. Perhaps we are getting to the

time when we consider it more important to purchase useful democratic material under whatever name it comes than to have an imitation of an aristocrat. At least I hope so, for Birch has the qualities required of the best furniture woods. More Birch is used for parlor furniture frames than is any other wood. Every argument in favor of Birch for interior finish applies equally well to Birch for furniture and there is the added one of harmony between finish and furnishing.

Stains

At the risk of being somewhat tedious, I want to go into the subject of stains in some detail. I have seen so many cases in which good wood has been spoiled by poor stains that I feel this is justified. When we have gone to the expense of getting the best wood there is for our interior finish, we should take care to see that it is properly and appropriately stained.

Reliable stains of nearly any shade desired may be purchased in shape for applying. Samples and color schemes are freely supplied by the manufacturers. Care should be exercised, however, to make sure that the stains selected are of tested quality. Care should also be exercised to have the wood thoroughly seasoned, surfaced and cleaned before applying the stain. Since Birch is a close-grained wood, a paste filler is not necessary. Birch is just the right density and texture to form a superior base for white enamel, and it is largely used for this purpose.

Stains are designated as spirit, oil, or water stains, according as the medium in which the color is held in solution is alcohol, oil, or acid. Spirit stains are not recommended for Birch since the alcohol evaporates so rapidly that it is difficult to apply uniformly. Oil stains give splendid effects, but not as clear and transparent colors as are produced with water stains. Water or acid stains are evenly and quickly applied and permit any method of finishing over them. The



A. P. Gassmann & Co., Architects
(Construction Photograph)

For a Good Looking Building

use

a dark texture brick

and

MIDLAND STOCK
TERRA COTTA

"Write for a Portfolio"

MIDLAND TERRA COTTA COMPANY

1120 CHAMBER OF COMMERCE :: CHICAGO, ILLINOIS

UNIVERNISH

The Universal Varnish *A Personal Statement*

For a full generation, we devoted our energies to the development of Specialty Varnishes. We have dozens of them which are practically ideal—each perfectly adapted to *one* purpose.

Several years ago, we began experimenting toward the production of **ONE VARNISH FOR ALL PURPOSES.**

We soon made it universally adaptable. Then we perfected its various qualities.

It avoids the bother and waste incident to the use of two or three varnishes on the same job. It is an especial boon to house painters and boat finishers and furniture manufacturers.

We made it *proof* against turning white, either by wetting or scratching.

We made it *proof* against hot water and steam and hot dishes and salt water.

We made it *proof* against alkali soap, and against alcohol and ammonia.

Then, we gave it the easy-working quality and we gave it the weather-resisting power, and we gave it the property by which it would not clog brushes nor thicken in the can.



UNIVERNISH

A Trade Name for
Universal Varnish
Pale-Hard-Durable
Waterproof
for Use Outdoors or In

Prepared only by
Murphy Varnish Company
Newark U.S.A. Chicago

Quality Is Economy



*The Biltmore, New York.
Architect, Warren Whitmore.
Painting Contractors, Robert E. Mackey Co*

The beautiful woodwork in the fine new Biltmore Hotel, New York, was finished with Bridgeport Standard Wood Finishing Products,

And the Use of



did not stop there.

They were used on all the furniture that went into this hotel by The Berkey & Gay Furniture Co., Grand Rapids, Mich., whose name is standard in the furniture world and always associated with high class furniture. The same practical materials which were used for this work can be obtained from dealers handling our goods.

Ask for our "Modern Wood Finishing"—a beautifully illustrated book showing all of the popular finishes in their actual colors, and giving a complete treatise on the art of modern wood finishing. Simply write your name and address on the margin of this ad. and mail it to us.

SOLE MANUFACTURERS
THE BRIDGEPORT CO.
WOOD FINISHING CO.
Box 108, NEW MILFORD, CONN., U.S.A.
NEW YORK CHICAGO BOSTON

objection that water stains sometimes raise the grain of the wood is averted by sponging the wood with clear water and sanding it smooth before applying the stain.

Varnish magnifies the natural appearance of the wood, hence defects as well as natural beauty are also magnified. This makes it especially important to have the surface smooth and free from defect, dirt, and dust before the varnish is put on. Varnish works best at a temperature of about 70 degrees and in a dry atmosphere.

Rubbed, or rubbed and polished finishes give the best results with Birch. I recently saw an excellent silver gray produced on Birch by one coat of acid stain followed by sand papering, finished with one coat each of white shellac and wax and then rubbed. There are also some flat finishes that are satisfactory for certain purposes. The user of Birch should always remember, however, that he is handling a high-class, hard wood whose peculiar richness of tone and figure is worthy of his most painstaking efforts.

Where to Use Birch

Having thus outlined the qualities of Birch, the next question is, where shall we use it? My natural inclination is to reply, everywhere in the interior of your building. It is of proven worth for such hard service as store counters, show cases, and fixtures, while its merits make it just as appropriate for the trim of the finest of residences, apartments, offices and hotels. Moreover, the reasonable cost of Birch places it easily within the reach of the builder of the modest cottage or bungalow. The colonial hall and stairway in white enamel, the living room in silver gray, the dining room in one of the many shades of brown, the bed-room in white enamel or natural, the den to suit the owner's particular fancy—all offer suitable opportunities for the use of Birch. Among the stains which I like best on Birch are silver gray, walnut, fumed oak, natural and mission brown. These are colors which harmonize well with general schemes of decoration, and are not likely to get on anybody's nerves. However, I have no quarrel with the user of Birch who prefers an entirely different selection. The wood will take and hold permanently any stain of the right kind that is properly applied. So good an authority as Keith says that: "Birch is the ideal high light for a scheme of coloring in browns with notes of blue and orange" also that silver gray is beautiful in a room with walls of dull old hue and a ceiling of silver gray on which are frescoed pink old roses—but not being a professional decorator I shall have to go carefully here.

One of the best features of Birch is that it combines so well with other woods. I have seen excellent combinations of maple or oak floors with Birch trim, and of Birch veneered doors with a trim of other woods or white enamel. Your own observation will furnish a multitude of instances of this sort.

(Delivered before the National Association of Building Owners and Managers, Duluth, Minn., July 14, 1914.)



New Edition "The Door Beautiful"

The Morgan Company, Oshkosh, Wis., have just issued the seventh revised edition of their beautiful book of Morgan doors entitled, "The Door Beautiful." This edition is more attractive and will prove more useful than any of the former editions, attractive and valuable as they invariably were. A feature of special note in this new book is a large double page insert, in colors, showing exactly twenty-four of the Morgan styles of finish. An explanatory key tells what the wood and finish are in each case; also the specification used by the company in producing the finish. The woods used in Morgan doors are plain, rotary cut, and quarter-sawed oak; birch; ash; and mahogany. The grain and coloring of these



"Take My Advice And Install An Underfeed" Says The Architect Who Knows

FOR fourteen years and in 25,000 buildings, Williamson Underfeed furnaces and boilers have been saving one-half to two-thirds of the usual coal bills, besides delivering **more** even, sanitary heat than any other heating system in existence. The United States Government **specifies** Williamson Underfeed furnaces wherever possible. It **knows** that such statements as, "Coal bill \$16.22 for 7 rooms;" "\$5.40 to heat 4 rooms;" "Reduced coal bills from \$109 to \$53;" "Underfeed reduces coal bill 60 per cent;" "A great fuel saver;" "Have cut coal bill \$70 each winter for 9 years;" "Saved \$122 a season;" "I have divided my coal bill by five;" "Even temperature with no smoke or dirt;" **are absolutely true.**

Get Our Latest Improvements


by installing a Williamson **New-Feed** Underfeed for either warm air, steam or hot water heating. The Williamson **New-Feed** Underfeed now requires **less** coal, less attention and less effort than ever. The attention of a 12-year-old boy **once** every 24 hours for firing and **once** every week for removal of ashes is all that is required.

An Underfeed in the basement means **clean, even, economical** heat in the home.

With the Underfeed, coal is fed from **below**. All the fire is on top. Smoke and gases, are burned up, making more heat with **on** smoke, soot, clinkers, smell and dirt, and but few ashes. No other furnace or boiler does this. Soon pays for itself in any home, store, church, hall and other buildings. Adds to renting and selling value of building. If you are contemplating building a home see that an Underfeed is installed. When an Underfeed goes in real heating comfort stays in.



Cut Coal Bills $\frac{1}{2}$ to $\frac{2}{3}$



Cut-Out View of Underfeed Furnace

A Startling Saving Guarantee

With every Williamson **New-Feed** Underfeed furnace or boiler, when properly installed and operated, we guarantee a saving of at least 50% in your coal bills. No other manufacturer dares to make such a guarantee. We have saved millions of dollars in coal bills for others. Why not save your share? The coupon to the right brings our great book. "From Overfed to Underfeed". This book is for every individual who wants to reduce his coal bills. Do you? Address

The Williamson Heater Company

(Formerly The Peck-Williamson Company)

293 Fifth Street

CINCINNATI, OHIO

For The Full Facts, Mail This

THE WILLIAMSON HEATER COMPANY

293 Fifth Avenue, Cincinnati Ohio.

(29)

I would like to know how to cut my coal bills from $\frac{1}{2}$ to $\frac{2}{3}$ with a Williamson **New-Feed** Underfeed.

Warm Air..... Steam or Hot Water.....
(Mark an X after system interested in)

Name.....

Address.....

My dealer's Name is.....

My Business is.....

woods are exactly reproduced in these color plates. In all, it is a feature that adds immensely to the sales strength of the book.

As in former editions of "The Door Beautiful," all of the doors are illustrated just as they appear in the modern home. The architectural details have been carefully considered in every case, and we hazard a guess that builders, architects, and home owners will find quite as many worth while suggestions in these full page illustrations aside from the doors, as they do in the doors themselves. The character of the illustrations serves to show the importance of harmony between the doors and the balance of the woodwork in a modern home.

Copies of this book will be sent free of charge to any of our readers who will write the Morgan Company, Oshkosh, Wis., requesting same.



Self-Setting Planes

In offering their self-setting plane the Gage Tool Company, Vineland, N. J., bring out the fact that considerable time is wasted in setting planes that could easily be saved. They say that the self-setting plane saves this time and also the temper of the workmen trying to set their planes right. The Gage plane has an adjustable iron throat extending through the stock. The cutting iron moves up and down without moving the cap. They say that the cutting iron and cap can be removed and reset in five seconds. The plane is equipped with two screws to change the thickness of shavings, one for a heavy cut and one for a light.

The Gage Tool Company are so confident of the special merits of their plane that they are offering it on a 30 days' trial plan, guaranteeing that the plane can be returned after 30 days' trial and purchase price refunded if it is not in every way satisfactory.

All Steel Pry Chisel

One of the most recent additions to the Diamond Edge line of tools by the Shapleigh Hardware Co. of Saint Louis is, their all steel prying chisel made in widths from ½ to 1½ inches, and lengths from 9½ to 11½ inches.

The round knurled handle gives a positive grip so necessary in a tool of this kind.

Forged from the highest grade crucible tool steel, oil tempered, highly polished blade especially adapted for prying or ripping.



"Diamond Edge" Steel Pry Chisel.

Carpenters and plumbers will find the Diamond Edge a very good and useful tool.

The quality of this tool is as high as the best obtainable. This item will be found quick selling and profitable.




Stopping the Water Waste

"It is astonishing," said an engineer who had been investigating water consumption statistics, "that there is such a remarkable difference between the gallons per capita used in various cities. What do you think the maximum and minimum gallons per head per day are?"

The man questioned admitted that his ideas were rather vague.

"The maximum," continued the engineer, "is 398 gallons, the average 121, the minimum 26. This illustrates the tremendous wastage, especially in locations where meters are not used. It has been found that by far the greatest per cent of loss is due to leaky faucets."

Safeguards Health--Increases Comfort in Every Rural Building



Never again the unsanitary outdoor closet with its contaminated disease-promoting odor—its germ-carrying flies and other insects. Never again the inconvenience, the horror in the night and in bad weather. All these disadvantages are removed in the

Kaustine Sewage Disposal System

Kaustine chemically and quickly destroys all disease germs—all odor. It's installed easily and inexpensively inside or outside the home—just as convenient as the sanitary city water closet, but with its disturbing noise and temporary odor eliminated.

Think! Every Rural Home, Factory, Church, Hotel or School in your locality is a prospect—a good prospect. And Kaustine meets approval of the Boards of Health. It requires

No Water—No Sewer—No Plumbing

Now don't put it off—you'll forget. Send us a postal or a note—use a pencil if you wish—but get our proposition.


Unusual Opportunity for Carpenters—Exclusive Territory

Kaustine is not a "season" product. You can sell a Kaustine closet every day in the year. And every one sold will multiply your sales—will build your bank account surprisingly fast. Write today.

Kaustine Co.

Dept. B.


Buffalo, N. Y.



A New Casement Operator

The bronze metal handle is all that is seen. Turning it opens or closes the casement window with ease and holds it firmly locked at any point. There is no interference with curtains or shades, or with window screens placed on the inside.

This device makes casements easy to govern and eliminates many objections to this very desirable form of window. Any dealer in Corbin hardware can tell you all about it. Or we will send you descriptive matter upon request. Let us hear from you.



P. & F. CORBIN

The American Hardware Corporation Successor

NEW BRITAIN, CONNECTICUT

CHICAGO

NEW YORK

PHILADELPHIA



*Dowling Ave. Highway Bridge, Grand Trunk Ry., Toronto, Canada.
Waterproofed with J-M Waterproofing Materials*

Some of the Largest and most difficult waterproofing jobs ever attempted

have been planned by our Engineering Department and executed under their supervision by our trained corps of workmen.

This can mean but one thing—that we have the proper facilities and materials for undertakings of this character.

You can be absolutely sure of results on your next waterproofing job if the work is done by us, with

JM

Waterproofing Materials

These materials are made of non-organic substances, therefore are practically proof against deterioration. They give lasting protection under all conditions of weather and climate. Will not crack, run, shove or disintegrate. And are not affected by expansion or contraction caused by settling walls.

No matter what your waterproofing problem may be—bridge, abutment, reservoir, residence, business structure or church—we will gladly co-operate with you.

Write our nearest Branch for Booklet.

H. W. JOHNS-MANVILLE CO.

Albany
Baltimore
Boston
Buffalo
Chicago
Cincinnati

Cleveland
Dallas
Detroit
Indianapolis
Kansas City
Los Angeles



Louisville
Milwaukee
Minneapolis
New Orleans
New York
Omaha

Philadelphia
Pittsburgh
San Francisco
Seattle
St. Louis
Syracuse

THE CANADIAN H. W. JOHNS-MANVILLE CO., Limited
Toronto, Montreal, Winnipeg, Vancouver 2221

In this connection, it is interesting to note the appearance on the market of a new washerless faucet which puts an end to leakage. This device is fitted with a conical valve bearing directly on a spherical seat. This gives a line of contact which makes a tight joint, so it is not necessary to jam the handle in an endeavor to stop leakage. This new faucet should be of decided interest to owners of hotels, factories or large establishments where the water bill is a considerable item.

Householders also will find it a boon, as a leaky faucet not only means plumbers' bills, but also the disfigurement of bowls and tubs with an unsightly yellow stain.

This washerless faucet is in extensive use abroad and has been authorized by the London Water Board. The manufacturers, the H. W. Johns-Manville Company, New York, state that the American sales are mounting fast and making new records each month.



"Simonds Guide for Carpenters"

The 1914 issue of "Simonds Guide for Carpenters" is now being distributed. It is a vest pocket size booklet containing 64 pages. The first 38 pages are devoted to valuable information for carpenters. This is in condensed form and just the way carpenters like to have it.

Some of the points covered are rafter framing, stair building, safe loads for common size timbers, painters' department, first aid to the injured, etc. That part regarding the setting and filing of hand saws is especially good for the young carpenter who wants to learn this necessary part of the work.

The latter part of the booklet features a view of the most popular styles of Simonds hand saws.

Our readers will find this a valuable booklet to own. A copy will be sent free to any carpenter writing the Simonds Manufacturing Co., Fitchburg, Mass. In writing, please mention this offer in the AMERICAN CARPENTER AND BUILDER.



Gypsum Industry Prosperous

VALUE OF OUTPUT IN 1913 REPORTED BY GEOLOGICAL SURVEY AT SIX AND THREE-FOURTHS MILLION DOLLARS

Gypsum, the rock that makes plaster of Paris, was mined in the United States in 1913 to the extent of 2,599,508 short tons, an increase of 98,751 tons over the production of 1912, according to R. W. Stone, of the United States Geological Survey. The total value of gypsum and gypsum products produced in 1913 was \$6,774,822, compared with \$6,563,908 in 1912, an increase of \$210,914. Gypsum sold crude without calcining and used principally as an ingredient in Portland cement and paint and as land plaster amounted to 463,136 short tons, valued at \$697,066, which is a good increase over the business of 1912. About 85 per cent of the gypsum sold crude in 1913 was used for Portland cement at an average value of \$1.49 a ton. The quantity sold for this purpose is steadily increasing. The quantity of gypsum sold crude for land plaster has remained nearly stationary for four years, but the average price dropped in 1913 from \$2.02 to \$1.75 a ton.

There was an increase of 42,175 tons in the amount of calcined gypsum sold in 1913, yet the average price per ton was \$3.43—the same as in 1912. A total of 1,680,157 short tons was calcined for wall plaster, Keenes cement, plaster of Paris, etc. About 1,250,000 tons of this amount was used for mixed wall plaster, the so-called cement plaster and hard wall plasters of the building trade.

It is interesting to note that only 10 years ago (in 1903) did the output of the gypsum industry first pass the million-ton mark. The present production of over 2,500,000 tons, as shown by the figures, goes very largely into the manufacture of Portland cement and of hard wall plasters.



Fall in line—NOW for doubled profits on Fall building

Since August a year ago, hundreds of wide awake contractors have joined the doubled profits company, by buying lumber of Hewitt-Lea-Funk

**Start now—write for price list—
Send the lists you now are figuring—
Don't lose out on the big money any longer**

Begin making a doubled profit on the jobs you are working on **now**. Send us a copy of your lists of materials and **find out** just what we can do for you in the way of price. You'll be surprised when you get our freight-paid quotation. It will open your eyes to the profit you've been *missing*. You'll be surprised again when you *see* the lumber that we ship.

Our yellow fir is beautiful in grain, straight and clear. Our red cedar is the kind that has made the Puget Sound Region famous for lumber. Our lumber comes from forests and mills which we control and our officers own. We absolutely guarantee grades, and count—also *guarantee satisfaction* or your money refunded.

Do something NOW toward DOUBLING YOUR PROFITS.
Make a doubled profit on your next job. Send us the list today for hurry-up quotation. Freight-paid to you
Fill out the coupon, too.

Many practical plan ideas in our Prize Plan Book

In the planning of your fall jobs you'll get great help from our Prize Plan Book. Over 100 plans—worked out by our own architects—and pronounced by many leading contractors the most practical book of plans ever published. It is worth a thousand dimes to you but costs you only one dime.

**HEWITT-LEA-FUNK
COMPANY**
408 Crary Building
Seattle, Wash.

Still time for good big Silo Orders

Many silos are erected during August and September. Get the orders for the ones to be erected in your neighborhood. Write quick, for our proposition.

Special plan service

Our architects are always at your service for the working out of special plans following your own ideas. These plans, together with our *guaranteed estimates*, have resulted in the greatest satisfaction for contractors using our service, and enabled them to add many dollars to their profits.

Quick delivery service

Our delivery service is immensely satisfactory to contractors. Seven railroads compete for our business. They know they've got to give us service to get the business. Shipments leave our mill within 24 to 48 hours after order is received—reach points as far as Mississippi River in two weeks. You always figure ahead lots farther than that.

Hewitt-Lea-Funk Company

408 Crary Bldg., Seattle, Wash. (Write your name plainly, please)

Please send the following:

- ☐ () I. J.ivered, freight-paid price on enclosed list of lumber, millwork and other materials (no charge for quotation).
- ☐ () Lumber Price List and Millwork Catalog (free).
- ☐ () Prize Plan Book (ten cents enclosed).
- ☐ () Barn Builder's Guide (four cents enclosed).
- ☐ () Silo Folder (free) and special Silo Proposition.

Name _____

Street No. or R. F. D. _____

Post Office _____

State _____ Business _____

Keystone Folding Saw Clamp

A very handy folding saw clamp is the Keystone, made and sold by the Keystone Grinder & Mfg. Co., 106 Wood Street, Pittsburgh, Pa. The accompanying illustration shows a cross section view through the operating mechanism. Eccentric lever automatically centers the jaws exactly opposite



Section Through Saw Clamp.

each other with one closing motion, giving the tightest possible grip, all working quickly and with slight effort. The jaws are provided with screws that take up lost motion as the faces wear away.

This Keystone clamp takes up little space in the tool box; it can be fastened instantly to a work bench, tool box, window sill, or to the edge of a board, plank, pile of lumber, fence rail, or any other suitable place without the use of nails or screws. The clamp weighs three pounds. It is made of malleable iron and is warranted not to break. The Keystone Grinder and Mfg.

Co. have such confidence in this saw clamp that they guarantee it absolutely. The clamp costs very little and the manufacturers say "money back if not satisfactory." Write them for full particulars.

Easter manufacturers are looking to the Northwest for hardwoods for the manufacture of clothes-pins.

Bishopric System Book

A nicely illustrated thirty-two page booklet containing a good deal of valuable information is being distributed by the Mastic Wall Board & Roofing Co., 530 Este Ave., Cincinnati, Ohio. It is entitled "Durable Homes by the Bishopric System." It tells all about Bishopric stucco or plaster board and shows how it is being used for both interior and exterior plastering. The use of this material has increased enormously in recent years and all builders should be thoroughly familiar with it.

The company will gladly send a copy of this book, together with a sample of Bishopric stucco board, to each one of our readers who will write them.



Annual Meeting Cement Products Exhibition Co.

The stockholders of the Cement Products Exhibition Co., held their annual meeting at the office of the company, 208 South La Salle St., Chicago, Tuesday, June 9.

The annual report of the directors showed the company to be in prosperous condition. The operations for the year, including the management of the Seventh Annual Cement Show and the National Conference on Concrete Road Building, resulted in a net loss of \$2,469.39. The total expenses of the Cement Show and the Conference aggregated \$26,987.79. The total income was \$24,518.40. The cost of the National Conference on Concrete Road Building, which was initiated by the Cement Products Exhibition Co., was \$3,054.69—the principal items of expense being printing and postage. The loss incurred during the year, however, was more than offset by the surpluses which have accumulated. The directors of the Cement Products Exhibition Co. are committed to

We Save a Builder Money

- 1st—By price.
- 2nd—By quality.
- 3rd—By assortment.
- 4th—By *quick service on odd and special work.*

We specialize on promptness. Have a large mill, with a million feet of shop lumber always on hand, much of it worked into sash and door material, half or three-fourths made up, ready to complete at short notice.

To show you our exceptional advantages we make this offer:

A TRIP TO CLEVELAND

If you have not yet visited us and will come to Cleveland and look over our stock, our mill and our warehouse and will place an order amounting to \$100.00 net or more we will pay your Railroad fare from any point East of Illinois and North of North Carolina.

Come to Cleveland now at this vacation time when country and city are at their best—When you can, besides business, enjoy baseball, lake rides, bathing, summer resorts and theatres. Take a day or two off and learn by actually seeing how much we can save you, both in price, and in time of delivery. It will help you the rest of the year to get more business and larger profits on what you already are doing. **Our facilities are yours** and you should know them thoroughly.




The Cleveland Window Glass & Door Co.
CLEVELAND, OHIO

Catalog B—Sash and Door. Catalog C—Paint. Catalog D—Mantels. Catalog E—Art Glass.



"The
Engine
for
Every
Purpose"




NO TANK
NO FAN
NO FREEZING
TROUBLE

Novo Portable Saw Rigs can now be furnished in two sizes—

Novo No. 3 Saw Rig (3 H. P.)

Novo No. 4 Saw Rig (4 H. P., Illustrated)

Two perfect answers for a Convenient, Economical, Reliable Saw Rig



NOVO
Engines
and OUTFITS

Reg. U. S. Pat.
Off.

The Power an Engine Delivers

Rated horse-power means nothing.

Power delivered under favorable conditions and in factory tests is misleading.

This is the question—

What will the engine do when you get it on **any** job? What power can it deliver?

That's the power that does the work—it's the **only** power you can **use**. How near does rated horse-power come to **usable** horse-power?

Novo power is usable power—power you can count on under whatever conditions the Novo Engine must run.

It is just that quality of reliability, proven under the most adverse conditions, that has won the endorsement of the contracting public.

The reason—

Simplicity in construction cutting out the many small parts which are always getting out of order.

Big factor of safety on each part—born of experience—that makes the Novo proof against the **unusual** strains that it may meet at any time.

Care in machining and fitting of "hidden parts," and in the selection and testing of material that enters into them.

The Novo does not require skilled help for its operation. Its vertical form and reduced weight make it easily portable. It is four-cycle, hopper-cooled and free from outside tanks and circulating pipes. Its cooling system can freeze solid without damage to any part.

Novo Engines can be furnished for operating on gasoline, kerosene, alcohol or distillate.

Novo Engines are made in thirteen sizes—1 to 15 H. P.

Let us send you "**RELIABLE POWER**," the Novo book—valued by every man who wants cheaper and better power. Free if requested on your business letterhead.

NOVO ENGINE COMPANY, CLARENCE E. BEMENT,
Sec'y and Mgr. 440 Willow St. Lansing, Mich.

WHEN WRITING ADVERTISERS PLEASE MENTION THE AMERICAN CARPENTER AND BUILDER



Use the Scientific Shingles On Every Job

The house-owner whose home has a Rex-tile roof will always be grateful to the carpenter and builder who recommended the scientific shingles and laid them.

They are weather and time proof. Nailed at the bottom through a turned-under fold, they can't flap, warp or curl. Rain-water can't seep under the edges.

Rex-tile
TRADE MARK

"The Scientific Shingle"

makes a handsomer roof than wooden shingles, slate or tile, and are more economical.

The color is a part of the shingle—will not fade. No painting necessary. Easy to handle. Light weight and smooth.

Rex-tile is an exclusive material sold at one price. Therefore you are not subjected to price-cutting, because the turn-under fold for nailing—at bottom—no flapping or warping—nails perfectly covered—is patented and exclusive.

Write today for free samples, prices, and full information.

Flintkote Manufacturing Co.

90 Pearl St., Boston, Mass.

659 Peoples' Gas Bldg., Chicago, Ill.

Also manufacturers of Paradux—a waterproof canvas covering for all surfaces on which walking will be done—such as sleeping porches, piazza roofs, roof gardens, balcony roofs, boat decks, etc. Easier to lay than tin or metal—far more durable—requires no special preparation of the surface to be covered. Can be painted any color desired.

the policy of paying no dividends, consequently such surpluses as occasionally remain are devoted to the promotion of future exhibitions. The following directors were unanimously elected:

Edward M. Hagar, President, Universal Portland Cement Co.

Norman D. Fraser, President, Chicago Portland Cement Co.

D. McCool, President, Newaygo Portland Cement Co.

A. Y. Gowen, Vice-President, Lehigh Portland Cement Co.

George S. Bartlett, Vice-President, Edison Portland Cement Co.

B. F. Affleck, General Sales Agent, Universal Portland Cement Co.

W. E. Cobean, Sales Manager, Wolverine Portland Cement Co.

J. U. C. McDaniel, Sales Manager, Chicago Portland Cement Co.

J. P. Beck, Manager Publicity Bureau, Universal Portland Cement Co.


It was announced that the Chicago Coliseum has been leased for the Eighth Annual Cement Show, to be held February 10-17, 1915.



Prevention of Poor Acoustics Better Than Acoustical Correction

Members of the architectural profession are manifesting considerable interest in the recently completed First Church of Christ, Scientist, Los Angeles, Cal. Their acknowledgment of the exceptional acoustical qualities of this church is a demonstration of the fact that it is better to prevent bad acoustics at the outset than to have recourse to corrective methods afterwards.

The acoustical work in this church was handled throughout by the H. W. Johns-Manville Company. This concern cooperated with the architect from the time the preliminary sketches were made until the building was completed. As the




























First Church of Christ, Scientist, Los Angeles Cal. Elmer Grey, Architect. Made acoustically correct by the J-M Acoustical Method.

result of this precaution, the church is said to be entirely free from excessive reverberation, as well as from the other acoustical defects which cause so much annoyance in most churches, theaters and other auditoriums.

The methods employed by this company are based on the scientific application of natural laws. No stringing of wires or other obsolete methods are used, but proper principles of design and construction are employed. It is noteworthy that they have solved successfully some of the largest and most difficult acoustical problems on record.

The home office of the H. W. Johns-Manville Company, New York City, will be glad to send to anyone interested, a list of buildings treated by the J-M Acoustical Method.



The use of **WALTER'S AND COOPER'S SHEET METAL SHINGLES** would have surely prevented this



What Inflammable Roofs did for Salem!!

June 25th, 1914—Salem, Mass.—conflagration—burned 16 hours—over 295 acres—destroyed 20 big factory plants and over 1,000 homes and other buildings—9,000 out of work—10,000 homeless out of a population of 40,000—loss \$14,000,000.00—an insurance loss of \$3,000,000.00—a net loss of \$10,000,000.00 on an assessed valuation of \$40,000,000.00—inflammable roofs and flimsy construction the cause.

Your duty as owner, builder or contractor is to correct this condition. It is your duty to the community to prevent these immense fire losses. There never would have been a five billion fire loss in the U. S. in the last 20 years if fireproof roofs had been used. Make your roofs fireproof; make the start now; use fireproof roofing material; use only that which has proven itself in service; to be quite sure, to have no after regrets, to make assurance doubly sure, use nothing but the time tested

Walter's and Cooper's Metal Shingles

The view shows their fireproof value. Houses are ten feet apart, the roof of the central house was burned entirely off, no damage to the other houses which were covered with the W. & C. shingles.

National Sheet Metal Roofing Co.
339-78 Grand Street, Jersey City, N. J.

The old old story

The story of Chelsea, Paterson, Houston and 150 other cities in the last 20 years and as long as such roofs are used just so long will these things happen. Inflammable roofs cause over 60% of the fires. Safeguard the homes by fireproof roofing and do it now.




Prominent Slate Man Dies

Mr. Jas. L. Foote, manager of Slatington Bangor Slate Syndicate, Slatington, Pa., died July 23rd. He was one of the best informed men on slate in the United States and one of the best known. He was engaged in the business for over twenty-five years, practically all his business life, and his death is regarded as a distinct loss to the industry.



A Weather Strip for Doors

The necessity often arises for placing weather strips on doors in order to prevent the entrance of cold air, dust, etc., through the spaces caused by the wearing away of the threshold in the center, also around the frame of the door due to shrinkage. A weather strip to satisfactorily serve the purpose must be inexpensive, durable and easily installed. Further, it must not have any moving parts which are likely to soon wear out with use. A strip which embodies features that practical experience has demonstrated meets the requirements of the case is the "Pullman," made by the Pullman Weather Strip Co., 22 York St., York, Pa. The details presented show how the strip is installed around a door in order to exclude the elements as well as dust and noise. A heavy brass sill is attached to the threshold and a brass hook which is fastened to the bottom of the door interlocks with the sill when the door is closed, thus making it weather-proof. On the lock, hinge and top sides there is a special spring bronze which is attached to the casing and spring against the door when closed, thus preventing the entrance of rain or dust at these points. A regular beaded strip is sometimes used on the back of the door, but this necessitates cutting a groove in the edge of the door as shown in one of the details. The spring bronze used on the lock side



Details of Pullman Weather Strips.

must be cut out to permit the lock to work properly, therefore a special strip, known as a "lock strip," is installed which prevents the entrance of air around the keeper of the lock. This strip is sold direct to builders and carpenters with full instructions as to the method of installation and any mechanic capable of using ordinary tools can install a door complete in about two hours. The weather strip equipment consists of a brass sill, drilled and countersunk for screws; a brass hook for the bottom of the door; spring bronze; brass rider; bronze lock strip; brass screws and coppered nails. The company in question also makes a full line of weather strips for double-hung windows, casement windows and transoms.

"I am satisfied that it will effectually prevent seepage of moisture."



The Dependable Waterproofer for Cement

(Read the letter on the right. It's interesting)



Y. M. C. A., Norfolk, Neb.

Norfolk, Neb., Feb. 10th, 1914.

CERESIT WATERPROOFING CO.

Dear Sir: Your letter of recent date, asking that I give you my opinion of your "CERESIT WATERPROOFING" which we used in the construction of the Y. M. C. A. swimming pool at this place, has been received.

Our pool is of reinforced concrete construction with a plaster coat of cement mortar about one and one-fourth inches thick, in which we used between 15 and 18 lbs. of the waterproofing for each 100 square feet of plastered surface.

With the exception of a little moisture around the intake and outlet pipes, which could not be attributed to any failure of the waterproofing, the other walls of the pool are perfectly dry at the end of a ten day test, during all of which time the pool was full of water.

I am satisfied from our experience with this material, that if the proper amount is used in accordance with instructions it will effectually prevent seepage of moisture.

Respectfully yours,

E. H. HUNTINGTON,

Member of Building Committee, Young Men's Christian Association.

Use Ceresit wherever conditions of dampness or water pressure obtain. Its method of use is simple—its results sure and permanent. Write for the new 1914 "Book of Evidence," which tells all about Ceresit.

Ceresit Waterproofing Co.
910 Westminster Bldg., Chicago, Ill.

FACTORIES

Chicago Unna, Germany Paris London Vienna Warsaw

Something Dependable

*Something you know will hold paint,
Something you know will take stain,
Something that is easy to work,
Something that may be nailed without damage.*

That **Something** will appeal to every contractor, to every carpenter in the land, and that **Something** is

ARKANSAS SOFT PINE

It is within the reach of every builder; it can be secured in quantities, grades and sizes required;

It will meet the expectations of the most exacting;

It will lower the labor cost of building;


It will live up to every representation made for it.

**Get a Copy of "HOW TO BUILD"
Increase Your Lumber Library by Adding Our
Trim Book.
Sent FREE on Request**

ARKANSAS SOFT PINE BUREAU

1728 Transportation Bldg.

CHICAGO, ILLINOIS



A Wisconsin Contractor Said:

"My Harley-Davidson permits me to do twelve hours work in eight hours. It saves three-quarters of the time formerly consumed in going to and from my meals, from job to job, besides performing many errands."

THE HARLEY-DAVIDSON

is the only motorcycle built with a Step-Starter, a starting device which starts the motor every time.

Two-Speed

The Harley-Davidson Two-Speed is the most simple, compact and effective two-speed on the market. The rider can shift from low to high or high to low or to neutral, at any time, whether the machine is standing still or in motion.

Double Clutch Control

The clutch can be controlled either by the customary hand lever or by a convenient foot pedal. This does away with the necessity of taking either hand off the handlebars.

These and many other features of the Harley-Davidson will be demonstrated by any Harley-Davidson dealer.


Call on our local dealer or write for illustrated catalog

HARLEY-DAVIDSON MOTOR CO.

Producers of High-Grade Motorcycles for More Than Twelve Years
752 C Street Milwaukee, Wis.

Campbell Auto Trailers

\$35.00 to \$65.00



Cut Your Cartage Costs Without Abusing Your Car

Get the Full Value out of your automobile investment. Hundreds of car users are increasing the efficiency of their automobile equipment by the use of trailers.

Short, Quick Hauls are mighty important at times in the busy seasons. The time lost by your workmen in waiting for tools and materials on contract jobs costs you a lot of money. Save that money by hitching a Campbell Trailer to your automobile—and

Get There in a Jiffy with the needed supplies. Don't wait for the return of your delivery wagon, nor spend more money for outside cartage. Use an inexpensive Campbell Trailer on that machine of yours—and do

General Hauling of All Kinds quicker and cheaper than with a horse or motor truck. The Campbell Trailer is built for hard knocks and rapid service. It is strong, compact, safe and durable—and

Mighty Soon Pays for Itself in time saving and convenience. It's a small fraction of the money invested in your car and it increases beyond measure the service you can get out of it.

You Can't Afford to Overlook the money saver that others are profiting by. Better investigate at once.

Photographs and Detailed Specifications are yours for the asking. Write today.

Campbell Manufacturing Co.
210 Dwight Bldg. JACKSON, MICH.

A Valuable Saw Book

Henry Disston and Sons have just issued a hand book of eighty-six pages that every user of saws should have. It contains a treatise on the construction of saws, illustrating and describing exactly how they are made in the Disston plant. It also tells how to keep saws in order. The point is made that saws must be specially toothed and filed for different kinds of work; and all of the different styles and sizes of toothings are clearly illustrated. For the younger man this Disston Hand Book will prove a gold mine of valuable information; and it is safe to predict that even the most wise and experienced of the old-timers will find something new to them in this book.

In addition to saws of various kinds some other well known Disston tools are discussed, including try square and bevel, trowels, files, rasps, etc. Address Henry Disston and Sons, Inc., Philadelphia, Penna., for free copy of this new Hand Book.



Low Cost Concrete Walls

A very interesting booklet entitled "Concerning Costs" has been prepared by the Van Guilder Hollow Wall Co., 720 Chamber of Commerce Building, Rochester, N. Y. It takes up in detail the labor and material costs on a typical two-story residence, 25 by 27 feet, 26 feet high from cellar floor to eaves. It shows that with Van Guilder Hollow Wall system—the double cellar walls being six inches thick outside and four inches thick inside and superstructure of four inch walls—the total cost is \$356.60. This is the cost of the outside walls complete from footing to plate.


Interesting figures are also given in this little book for estimating cost of hollow concrete cellar walls for a frame house. Also for cost of double wall silos.

Copies of the booklet will be mailed to those writing the Van Guilder Hollow Wall Company.



Heavy Reinforced Asphalt Shingles

Neponset roofing is now on the market in shingle form. These Neponset shingles are having a great sale and their use is certain to spread, as they are quality-built, like all of the Neponset products.



Neponset Shingles Come in Pairs; the Shingle Butts are Triple Thickness.


These shingles are not simply shingle sizes cut from rolls of prepared roofing; the Neponset shingle is built up and strongly reinforced. The butt end consists of three layers of Neponset roofing laid so that the grain or weave of the inside layer runs at right angles to that of the other two. This heavy butt end with rounded edge presents a weathering surface that will not warp or curl up at the edges. When laid there are not less than seven layers of roofing over every part of the roof.

In appearance the Neponset shingles are unusually attractive. Their original color is a rich gray, which weathers to a darker shade, resembling weathered red wood.

Neponset shingles are shipped in bundles and are laid like ordinary wooden shingles. Any carpenter, roofer, or handy man can lay them. They come in double widths, two shingles together like Siamese twins, each shingle being 8 by 12¾ inches in size; the double shingle measuring 16 by 12¾ inches. Two hundred and twenty-six double shingles weighing 176



Introducing—
America's Greatest "Light Six"
\$1485



HAYNES

America's First Car

Since Elwood Haynes built America's First Car twenty-two years ago, the public has looked to him to set the standard in motor car values.

The Haynes latest production is this beautiful, powerful "Light Six," with graceful streamline body, unit power plant, 3-point suspension, 55 brake horsepower en bloc motor having a flexibility that enables you to throttle down to one mile per hour and sufficiently powerful to make a mile a minute.

—With 121 inch wheelbase, left hand drive, center control; weight completely equipped, 2950 lbs., giving one horsepower for every 55lbs.; Leece-Neville starting and lighting separate unit system, the economical Rayfield carburetor.

—With exclusive arch frame construction over rear axle, Vacuum gasoline system with gas tank at rear of chassis, force feed and gravity lubrication, centrifugal water pump and fan for cooling, Haynes full floating rear axle, Firestone demountable rims, motor driven tire pump, Stewart-Warner speedometer, improved One-man top, Collins quick adjusting curtains—these and other exclusive Haynes features make this car truly America's Greatest "Light Six."

Some manufacturers have abandoned the water pump, some the oil pump and others the full floating axle. In fact, it is very difficult to find a "Light Six" at a popular price that has not been slighted in some way.

You will find this a complete car in every respect. It was designed with the most scrupulous care, with a view of eliminating all complications without sacrificing any of the fundamental features that make for increased power, endurance and general reliability.

In addition we build Model 31, "Big Six" with 65 brake horsepower and 130 inch wheelbase—\$2250; Model 32 Haynes "Four" with 48 brake horsepower and 118 inch wheelbase—\$1660.

THE HAYNES AUTOMOBILE COMPANY

14 Main Street
KOKOMO, INDIANA

Builders of America's First Car

The Haynes car is handled by Direct Factory Branches at 1715 Broadway, New York City, N. Y.; 1702 Michigan Ave., Chicago, Ill., corner Polk and Turk Sts., San Francisco, Cal., and by dealers in every state in the Union.

Catalog upon request.

**Coupon for your
convenience**

herewith

Write

today

THE HAYNES

AUTOMOBILE CO.,

14 South Main Street,
Kokomo, Ind.

Please send me your 1915
catalog with full particulars in
regard to America's Greatest "Light
Six."

Name.....

Address.....

I expect to buy a car about.....



A Residence at Canton, Mass., roofed with Neponset Shingles.

lbs. are required to cover one hundred square feet of roof. This is with shingles laid 4 inches to the weather as recommended by the manufacturers.

These shingles are said to cost approximately \$5.00 per hundred square feet, less than slate, asbestos or tile. It is claimed that the reinforced butt prevents the annoyance of flapping in the wind, the danger of catching fire from flying sparks along raw edges and the fraying out of exposed edges and curling up at the corners.

The Neponset shingles are manufactured by Bird & Son, East Walpole, Mass. They will gladly send descriptive matter and a sample to any one of our readers who will write them. The high quality of Neponset products is well known among carpenters and builders; and this improved Neponset shingle should receive the attention it deserves.

Unique Invitation

Quite a novelty reached us a short time ago—a shingle post card; a white pine slab, bearing the printed announcement on one side that the Ives-Hartley Lumber Company of Baldwin City, Kansas, invite all their friends to the opening of their new lumber yard, Saturday, June 27, 1914, from 2:30 to 10 p. m., and on the other side was the customary one cent stamp and the address. We don't know what Uncle Sam thinks of wooden postcards $\frac{1}{8}$ of an inch thick, but it struck us as O. K.



A Saw with a Record if Not Much Shape

After twelve years' sawing and filing, sawing and re-filing, the one-time hand-saw shown below has assumed the shape of a compass-saw, with a nose like an ant-eater and teeth like a squirrel.

The story of this old Keen Kutter saw is best told in a letter received by the Simmons Hardware Co., of St. Louis, Mo., from E. T. Lindsay & Co., hardware dealers of Senatobia, Miss.

The letter reads, in part, as follows:

"The man who used the saw, Nelson Smith, requested us to say that he used it continuously for 12 years, and that it is the best saw he ever worked with in his 30 years' experience as a carpenter.

"Yours very truly,

E. T. LINDSAY & Co."



Keen Kutter Hand-Saw after Twelve Years' Active Use.

Your problems are being met by KisselKar Trucks

KisselKar Trucks are not only good trucks in a general mechanical sense, but are the right trucks for **you—in your business.** This can be proven by asking us who **in your line** are owners, and following the information by asking these owners. They will tell you that they not only received a well built, serviceable vehicle, but one which particularly suited their individual requirements.

KISSELKAR TRUCKS

It is the KisselKar policy to sell only trucks that will pay—trucks adaptable in size to the needs of the buyer. We study **your** haulage problems and give you just the truck you should have to keep your trucking on an economical as well as a highly efficient basis—hence the range of sizes.

Standard sizes—1500 lbs., 1, 1½, 2½, 3½ and 6 tons.
Bodies to order.

The KisselKar Truck portfolio with 350 illustrations is indispensable to you if you are considering the truck question. Write for it.

KISSEL MOTOR CAR CO.

546 Kissel Ave., Hartford, Wis.

New York Chicago Philadelphia Boston St. Louis Kansas City
Milwaukee Minneapolis St. Paul San Francisco Los Angeles Dallas
and 300 other leading American and Canadian points



KisselKar Truck in Service of Sheboygan Lime Works


You Can Make More Money

Building Silos

Than In Any Other Line—Get Our Plans Free!

Carpenters—Builders—Contractors! Farmers all around you are waiting for the man who will build wood silos for them. Now is the time to get busy. Patents on door systems make the prices of ready-made silos prohibitive. We have solved the door problem. The Drico Expansion Silo Door is the simplest, most convenient, most durable door ever devised. Now in operation on silos in all parts of the country.

You build the silo. We furnish you all the plans down to smallest detail **FREE!** The Drico Expansion Silo Door opens a business for you that is now making thousands of dollars for carpenters, contractors and builders. Write today for information about the



Drico

Expansion Silo Doors


(Sold through Lumber Dealers)

Just send us the name of your lumber dealer and we will send you a **full set of plans for building a silo of any size** with flooring and flat bats that you can get at any lumber yard. You do not pay us anything for plans. You do not put yourself under any obligations whatever.

The Drico Expansion Door is wholly independent of the Harder patents—a different door entirely. Instead of building a silo to sell this door we have decided to put the whole business in the hands of local carpenters, contractors, builders and lumbermen.

Our handbook gives complete plans and specifications for 66 different sizes of silos. Any man who can drive a nail can build them. Write for the plans today, and be

the first man in your territory to get the silo business. Be sure to send your lumber dealer's name.



Deal-Rice Lumber Company
606 Clapp Block Des Moines, Iowa



HERCULES CONCRETE BLOCK MACHINES


Are the **ONLY** machines that meet every requirement of the architect and builder

They are simple in construction, easy to operate and do not require skilled labor. You can install them with small equipment and add to it from time to time, according to your needs. The output from **One Hercules** exceeds the combined production of from **Two to Four** machines of other makes.

Hercules machines make stronger and more durable blocks Because they use a Coarse Wet mixture—other machines do not.

For the man who wants to make 16-inch blocks, there is nothing to equal our new **Hercules Junior** machine with complete equipment, for it is the best block-machine value ever offered. Investigate—send for illustrated catalogue. **It's Free.**

CENTURY CEMENT MACHINE COMPANY, 220 MILL STREET, ROCHESTER, N. Y., U. S. A.



WHEN WRITING ADVERTISERS PLEASE MENTION THE AMERICAN CARPENTER AND BUILDER

This double hung window is equipped with

PULLMAN ALL METAL WEATHER STRIP

It is one of several hundred. The man who had the contract to install the complete order made a profit of a dollar and a quarter on each window. Here is an opportunity for YOU to get into a profitable business.

We protect you by giving exclusive territory.

The demand has been created. We want live men to sell and install

PULLMAN STRIP

You buy the strip direct from us at

FACTORY PRICE

and make the

BIG PROFITS

Write today for information.

Pullman Metal Weather Strip Co.
22 York St., York, Pa.



Be the First Man in Your Town

to get into the vault business and increase your income. Here is a wide-open opportunity to step into a profitable business without investing a lot of money. Takes little time;—no experience and payment is generous and sure.

MAKE THE BIG PROFIT

Automatic Sealing Vaults are made from cement in steel molds. Takes little material. The adult size costs about \$6.00, and sells for \$30. Nets you \$24 solid profit.

Easy Work—Good Money

All you do is make the vaults. They sell themselves. Demanded in every locality because they are water-tight, moisture-proof, neat and strong. People buy Automatic Sealing Vaults because they protect the remains of a loved one from every element of the earth.

We sell the molds for making these vaults. You make the vaults and keep all the profits. No blue sky for sale. The molds are sold outright. A legitimate business for any man. Write us for particulars and let us show you how much money you can make.

AUTOMATIC SEALING VAULT CO.
36 East River Street - - - PERU, IND.



"Vandor" Hammers Now in Four Sizes

We have been advised by the Van Doren Manufacturing Company, Chicago Heights, Ill., that they are now making their "Vandor" Vanadium Hammers in four sizes as follows: 16 oz. standard size, 13 oz. general purpose, 10 oz. finishing size, and 16 oz. ripping style. All of these hammers are warranted absolutely against defective material or workmanship.



New Sasgen Derrick

A portable one-ton stiff legged derrick has just been placed on the market by the Sasgen Derrick Co., 2053-57 No. Racine Ave., Chicago, Ill. The construction of this derrick



New Model Sasgen Derrick.

is well shown in the accompanying illustration. The derrick is equipped with all steel fittings, including the double drum geared winch, making it strong and light and easy to put up or take apart. It is arranged so that it can be used by man, horse or power.

The legs and sills can be swung in or out to rest at any angle desired. It is claimed

that with one setting of this derrick using an 18-foot boom every stone on a 30-foot one-story front can be placed.

Two extra fittings are provided so that the boom can be used separate as a tower boom when desired.

The Sasgen Derrick Company have been putting out a great many popular and practical derricks of different types and it is expected that this new portable, one-ton, stiff-legged derrick will find many users.



Carpenters Wanted

The Gem City Acetylene Company, Dayton, Ohio, inform us that they would like to get in touch with a number of ambitious carpenters to take orders for their acetylene lighting systems. They say that their convincing sales literature and follow-up system really make the sales. What they want is a reliable builder in every community to look after the business locally for them. They say that no money is needed and previous experience is not necessary.

These people make the "Faultless Pit Generator," a well-known acetylene lighting system. All those interested should write at once, addressing Dept. B, Gem City Acetylene Generator Co., Dayton, Ohio.



"Faultless Pit Generator".

LOOK and READ Carefully

We Want Live Carpenters to Handle the GOLDEN METAL WEATHER STRIP

The season is now on for taking up the agency of the Weather Strip business. By the time you get the minor details straightened out and get nicely lined up you will find the Weather Strip season on you in full force and people clamoring on all sides for better protection from the cold blasts of the fall winds, and the Carpenter is the man invariably selected for this work.


There are millions of feet of Golden Metal Weather Strip now in use in some of the largest and finest office buildings, schools, hospitals, residences, etc., in the country.

The standard metal for sliding windows excepting the meeting rails is made from zinc. The Meeting Rail strip, Casement Window strip and all strips used for Doors are made from tempered Spring Bronze. These two metals are indestructible and will last a lifetime.


Golden Metal Weather Strips are easily applied, are weather, wind, soot and dust proof. They allow for shrinkage, swelling and warping of sash without binding, are invisible and prevent windows from rattling. They save from 25 to 40% annually on fuel bills.

Only one agency will be established in any one section, so write at once or your competitor may get in ahead of you and secure the agency for one of the oldest and most reliable Metal Weather Strips on the market, one that has stood the test of time for over 12 years. This is one of the best money getters and money savers in the field today and we feel you cannot afford to let this opportunity get away from you.

Write for samples or further information.




Section
Through
Window
Jamb



Golden's Sill Strip



Meeting Rail Strip



Door Bottom

MICHIGAN ENGINE VALVE CO., 115-117 W. Columbia, DETROIT, MICH.



We have some mighty interesting facts for you about the

EUREKA SELF MEASURING MIXER "WHERE GUESS WORK ENDS"

May we show you these things in a clean cut way—one business man to another—no extravagant claims, no glittering generalities, JUST PROOFS AND FACTS THAT HAVE AN IMPORTANT BEARING ON YOUR WORK.

GASOLINE, STEAM OR ELECTRIC POWER

It costs you less than half as much to buy it!

It costs you less than a third as much to run it!

It costs you less than a fifth as much to move it!

The Eureka Mixer, capacity for capacity, with any standard batch mixer, weighs less than half as much.

Powerful, Simple, Easy to Operate. Its Cost is Surprisingly Low. Send for the Facts Now.

EUREKA MACHINE CO., 12 Case Street, Lansing, Michigan


JUST RIGHT in Price, Capacity and Construction

That's the beauty of buying a Northwestern machine. You can get a mixer that will suit you in capacity, construction, and price. All our machines are built to satisfy and they do it. By ordering a Northwestern Mixer you avoid a big initial investment and all future worry and expense.

Northwestern Special Batch Mixer

Capacity 5 cu. ft. per batch. 40 to 50 cu. yards a day. This is a

speedy and durable mixer that will soon pay for itself. Has the sturdiness, simplicity, and mechanical perfection that makes it a winner. Low Charging. High Closed Discharge. Combined cone and cylindrical drum. Strongly braced truck. Wide face truck wheels. 2 1/2 H. P. Engine. Let us send you a complete description of this mixer which can be bought at about half the price asked for other machines of the same quality.



Carpenter's Hand Batch Mixer

An especially strong, well-made little machine for handling small batches of concrete quickly and with a small amount of labor. 3 cu. ft. of loose material per batch. Perfect mixing guaranteed. Best iron and steel construction. Weight 220 pounds. PRICE....\$23.00

Get Our Complete Catalog of Mixers, Hoists, Moulds, Brick and Block Machines, Crushers, and all Concrete Machines and Supplies.

Northwestern Steel & Iron Works
625 Ball Street - - - Eau Claire, Wis.

New 1914 Model "Standard" Double-Acting Checking Floor Hinge


An improved model of the popular "Standard" floor hinge has just been announced. It embodies a number of notable features that make it even more desirable than former models put out by the Standard Manufacturing Co. that have already met with such a demand. The business of the Standard Manufacturing Co. has, in fact, grown to such proportions that they have been obliged to purchase a new site and erect a new factory devoted exclusively to the manufacture of "Standard" double-acting checking floor hinges. As this new factory is equipped with the most up-to-date economical machinery, they are able to give their customers the double advantage of low price and high quality.

The new 1914 model hinge is a ball-bearing hinge. The entire weight of the door rests on hardened steel ball-bearings operating in a steel ball cup and cone placed in the top of the hinge and so far away from slop and grit. In the old hinge the weight of the door simply rested on the iron post in the bottom of the bowl. The new bearing makes a joint that will never wear out.

The new model hinge is made considerably heavier and more strongly ribbed than the old; also the back part of the form bends at an angle of 45 degrees, so that the wood screws go into the wood diagonally, making a much stronger attachment than heretofore. The cam and plunger are of malleable iron and have large wearing surfaces. They are nearly double the size of the rollers and cast plunger which answered the purpose in the old style hinge.

In the new hinge the manufacturers have produced an appliance that is very much easier for the carpenter to install. Only a small hole has to be cut for the simple rectangular oil chamber.

The checking mechanism has also been perfected. When the Standard Manufacturing Co. first put out a double-acting hinge with checking attachment it was hailed as the greatest improvement ever offered. The closing spring and checking mechanism automatically close the door without a slam, bringing it to a stand-still at the center line without passing through and flopping back and forth. An unchecked, double-acting door is dangerous and a menace to the household. The door check feature means absolute safety. No matter how hard or fast the door is opened it comes back slowly and quietly and stops without flapping back and forth. And now this checking mechanism also has been improved.



1914 Model "Standard" Hinge.

Architects, contractors and builders are recommending and using these hinges enthusiastically. The Covell Construction Co., Architects and General Contractors, Ionia, Mich., after placing a trial order for six of them, write that this new hinge fills a long felt need, and that they will use it and specify it in all their work. Our readers will all do well to write at once to the Standard Manufacturing Co., Shelby, Ohio, and ask for complete description.

Don't Just *Line* Walls with Sheathing Paper— *Insulate* Them

THE insulating effect of ordinary sheathing papers is practically nil, because, being thin and porous, they confine practically no dead air.

To efficiently **insulate** (not merely **line**) walls, partitions, floors, etc., to prevent the transmission of heat, cold and sound, a lining must contain a vast quantity of dead air. Keystone, because of its cushion-like construction, contains millions of "dead air" cells to the square foot, which makes it the most efficient insulating material on the market.

Keystone Hair Insulator

is made of a thick layer of thoroughly cleansed and sterilized cattle hair, securely fastened between two sheets of strong, non-porous insulating paper.

We have proof in the form of actual tests and testimonial letters that it has reduced fuel bills from 25 to 35%.

Keystone will not settle, pack down, dry out, rot or attract moisture. It is inodorous, vermin-proof, and will last as long as the building. Is an effective fire retardant.

Write our nearest Branch for catalog and samples.


H. W. JOHNS-MANVILLE CO.

MANUFACTURERS OF ASBESTOS SHINGLES ROOFINGS; STUCCO; PIPE COVERINGS;
COLD STORAGE INSULATION; WATERPROOFING; SANITARY SPECIALTIES;
ACCOUSTICAL CORRECTION; CORK TILING; ETC.



Albany	Cincinnati	Kansas City	New Orleans	San Francisco
Baltimore	Cleveland	Los Angeles	New York	Seattle
Boston	Dallas	Louisville	Omaha	St. Louis
Buffalo	Detroit	Milwaukee	Philadelphia	Syracuse
Chicago	Indianapolis	Minneapolis	Pittsburgh	1757

THE CANADIAN H. W. JOHNS-MANVILLE CO., LIMITED.
Toronto, Ont. Montreal, Que. Winnipeg, Man. Vancouver, B. C.



WHEN WRITING ADVERTISERS PLEASE MENTION THE AMERICAN CARPENTER AND BUILDER

More Business for Carpenters

The ALADDIN Read-Cut system offers every carpenter a rare opportunity to increase his business. The vast popularity of ALADDIN Read-Cut houses and the large Aladdin advertising campaign have convinced home builders everywhere of the many ALADDIN features. Carpenters are taking advantage of this great demand and are building ALADDIN houses for their customers. The ALADDIN catalog enables you to give your customer an actual photograph of the finished house.

5-Room House Complete, \$298



Price includes all material necessary for completion. ALADDIN Read-Cut system saves builders a third—all material cut-to-fit saving time in erection—no middleman's profits. *Get the Aladdin Catalog today.*

ALADDIN

READI-CUT HOUSES

This House Complete \$797

Aladdin Price Includes Everything

The quality of all material is far superior to the average—clear siding, clear flooring, clear interior finish, clear shingles. "Clear" means free from knots or any defects—the best that grows. The price includes all framing lumber, siding, flooring, cut to fit, all inside finish, windows, frames, casings, stairways glass, hardware, locks, nails, paint and varnish for the outside and inside, shingles, plaster board for all rooms or lath and plaster. ALADDIN construction passes successfully the strictest regulations of the big cities. *Send today for catalog 790.*

North American Construction Company,



793 Aladdin Avenue
BAY CITY, MICH.

Can. Branch:

Sovereign Const. Co., C.P.R. Building, Tor., Ont.



Ask other manufacturers if their board is

**TREATED WOOD FIBRE
MOISTURE PROOF GUARANTEED**



The pure wood fibre of Plastergon is treated with a moisture proofing chemical to protect it against the dampness in the air and it is guaranteed by us to assure EVERY ONE it can be used satisfactorily to replace lath and plaster.

PLASTERGON

TREATED WOOD FIBRE

WALL-BOARD

"THE STANDARD BY WHICH OTHERS ARE JUDGED"

To the best of our knowledge, Plastergon is the only treated wood fibre, moisture proof and guaranteed wall board on the market.

Unless you use Plastergon, you are apt to have trouble with wall boards and set your customer against this class of material.

IT COSTS NO MORE THAN OTHERS

Samples and complete information upon request. These all belong in your "kit."

The Plastergon Wall Board Co., Dept. A, Tonawanda, N. Y.

There's Just One "Wood-Core" Wall Board

Its construction is shown by the border of this advertisement. Selected kiln-dried wood slats are laid edge to edge for the core. Heavy, specially prepared paper is cemented onto both sides, under enormous pressure.

This patented construction makes



Trade Mark Registered U. S. Patent Office, No. 94745

the strongest wall lining in use. It will materially strengthen and stiffen a frame house, as compared with lath and plaster or other wall covering.

Other wall boards are often wrongly called Compo-Board, and sold as such. Be sure you buy and use *real* Compo-Board—our trademark, as shown above, is on every piece. It's sold almost everywhere.

Northwestern Compo-Board Company
5777 Lyndale Ave. N.
Minneapolis, Minn.

Because Its Surfaces Have Been Waterproofed

A carpenter who furnishes a room with **NEPONSET** Wall Board is doing the right thing by his customer because the surfaces of **NEPONSET** Wall Board have been thoroughly **waterproofed**. This **extra** treatment which is given to the surfaces of **NEPONSET** Wall Board is done to prevent the board from absorbing moisture.

Another point—**NEPONSET** Wall Board is beautifully finished and requires no further decoration.

To get an **attractive** as well as a **practical** job with Wall Board be sure to get

NEPONSET
WALL BOARD

Write for samples and information to

BIRD & SON

ESTABLISHED 1795

25 River Street

EAST WALPOLE, MASSACHUSETTS

NEW YORK, CHICAGO, WASHINGTON, SAN FRANCISCO

Canadian Office and Plant:
HAMILTON, ONT.

Make Money Building Silos

SET OF WORKING PLANS FREE

"Are the carpenters and builders who read your paper going to be interested in a type of silo which they can erect out of material which they can buy in their local lumberman's yard? In other words, a type of Home-Made silo built of flat batts and 4-inch flooring?"

We were asked this question the other day by a prominent Iowa lumberman who is a keen student of the silo situation and also a great booster for the country carpenters and builders. We replied that it certainly seems reasonable that the carpenters and builders will take a personal interest in a farm silo that requires their services to erect.

"The policy of most of the stave silo concerns has been to cut out the carpenter and we believe he has resented it," we said. "The stave silo people have told the farmer that he and his hired man can easily put in the foundation and erect the stave silo, and the result has been that many silos have not been properly put together and have fallen down. While the farmer is naturally an all around handy man, silo building is really builders' work and the farmer should call in outside skilled assistance."

"Well then, this Home-Made silo is just the ticket for builders, and they can work up some nice business with it. For a great many years this type of silos has been built back in New York state. Some of the New Yorkers moved out to Kansas and then they began building these silos in Kansas. We first learned of them in Kansas. The silo is not patented and can be erected by any one, and when completed it makes a better silo than any of the stave silos; it gives the farmer more advantages, and costs the farmer from \$100 to \$150 less than any other good silo would cost him. The farmer can buy the material for a Home-Made silo and hire regular builders to put it up all at a lower cost than a stave silo which he would try to erect himself.

"My people, the Deal-Rice Lumber Co., Des Moines, Iowa, are advocating the Home-Made silo for the reason that it is the best silo for the farmer, for the lumber dealer and for the carpenters and builders, and also because it makes use of our 'Draco' Expansion Silo Doors. Here you see a large set of working plans we are giving away—they show exactly how a silo should be built.

Best Construction of Silo

"You will notice that the hoops are made of flat batts curved around a form to get the proper circle and eleven of these flat batts are nailed together to make a strong, durable hoop. These hoops are then set, around a scaffolding, two feet apart on centers and four inch flooring is nailed inside and outside of the hoops.

"The wooden lining gives the fermentation benefits claimed by the stave people. The hollow-wall with its dead-air space gives the freezing protection claimed by the hollow-tile people and when the outside sheeting is omitted and metal lath is used and covered with cement the farmer secures the fire protection claimed by the cement people.

"The silo cannot blow down as it is well anchored, it cannot drop to pieces as each board is securely nailed in place, there are no hoops to tighten and none to loosen.

"The doors which the farmer will admit are about the most important part of the silo are the 'Draco' Expansion doors, each two feet high. They have an expansion feature at the right hand side of the door termed the sealing strip. When the door is locked by pulling down the crank arm, this sealing strip is moved outward against the door jamb and makes the opening absolutely tight. When the crank arm is raised this strip is drawn in and the door can be removed with one



Residence of Mili Bunnell,
Duluth, Minn., roofed with
Asbestos "Century" Shingles

Architect, John Wangenstein;
General Contractor, Hugh
Fawcett; Roofing Contractor,
A. H. Kreiger, Duluth, Minn.

Asbestos "Century" Shingles

Featured by Architects, Contractors and Builders in Response
to the Growing Demand for Artificial Roofing Slate

EVERY architect, contractor and builder knows that Civic authorities and individual property owners are more and more strongly favoring the use of Artificial Roofing Slate for roofing all classes of buildings.

It is plain that those contractors and builders who feature Asbestos "Century" Shingles to their clients will benefit most.

Property owners are becoming more critical about the length of service and fire protection qualities of their roof. That is what has doubled the sales of Asbestos "Century" Shingles in four years—the only Artificial Roofing Slates made by the Patented "Century" Process.

Can you supply Asbestos "Century" Shingles? And do your customers know it?

Write for prices and full particulars—and samples if you want them.

KEASBEY & MATTISON CO. Factors, Dept. B, AMBLER, PA.

Branch Offices in Principal Cities of the United States



Residence of John Miller, Shaker Heights,
Cleveland, Ohio.

Our free book shows many other "Creo-Dipt" shingle houses in all parts of the country.

Buy Shingles Already Stained

You save money, time and worry and muss of staining on the job. You get the most artistic effects in fast, even colors. Best of all, you get selected Red Cedar shingles of exceptional quality.

"CREO-DIPT" STAINED SHINGLES

14 Grades, 16,-18,-24-inch. 25 Different Colors

They come in bundles, ready-to-lay—one even stain, perfectly dry, ready for the job. We preserve them in Creosote against wet or dry rot or worms. We use only selected Red Cedar Shingles. You pay for no waste in either shingles or stains.

Most pleasing effects obtained by using one color on side walls and a darker tone on roof. They are being used by architects, builders and owners all over the country.

Write us for catalog of CREO-DIPT Houses and Pad of Colors on Wood.

Special information on request for Architects and Lumber Dealers.

STANDARD STAINED SHINGLE CO., 1028 Oliver St., N. Tonawanda, N. Y.



Least Expensive—Most Durable

HUDSON ASPHALT SHINGLES


Rich and beautiful for roofing or siding.
Provide fire protection at the least cost.

Surfaced with Red and Green Crushed Slate. Fast colors. Require no painting or staining. Rust-proof. Easy to lay.


Send for Samples.

ASPHALT READY ROOFING CO.
9 Church Street New York, N. Y.





Hoops in Place with Scaffolding on Inside.




Home-made Silo Almost Completed.

hand without binding or sticking. No swelling or shrinking of the lumber can affect the doors. The crank arms form a very convenient ladder, for climbing to the top of the silo. These doors are cheap and can be purchased from any lumber dealer.

"To your carpenter and builder readers I want to say to send the name of your lumber dealer to the Deal-Rice Lumber Company, 606 Clapp Block, Des Moines, Iowa, and they will send you a full set of plans for building a silo of any size with flooring and flat batts that you can get at any lumber yard. You do not pay anything for plans.

"This handbook gives complete plans and specifications for 66 different sizes of silos. Any man who can drive a nail can build them. Write for the plans today, and be the first man in your territory to get the silo business. Be sure to send your lumber dealer's name."



The Permanent Roof

In the Cortright roof there are no exposed nails to rust off, no chance for wind to get under the shingles and blow them away. They overlap and interlock so that no rain, snow or sparks can penetrate. Thus a Cortright Roof remains unchanged through the passage of years, and requires no attention beyond an occasional coat of paint.


The first cost is little if any more than a good wood shingle roof, but it is then perfect, permanent protection without maintenance expense which make

Cortright Metal Shingles

so much cheaper in the end.

Cortright Metal Shingles are economical enough in first cost to enable you to meet the keenest competition, and their superior quality with nearly 30 years of success ensure satisfaction to your client, and future business for you. Your ordinary workmen can lay them, no soldering or tinner's work to do, no skilled roofers necessary. Your share of this season's profits in Cortright Shingles is waiting for you. Write for Contractors' and Builders' propositions today.

CORTRIGHT METAL ROOFING CO.
PHILADELPHIA & CHICAGO.



WHEN WRITING ADVERTISERS PLEASE MENTION THE AMERICAN CARPENTER AND BUILDER



Kno-Burn EXPANDED METAL LATH

Is most Adaptable as a Plaster Base for Theatre Interiors—

because its simple mesh construction is so easily worked into the exact form of the architectural details. This applies equally well to cornice, frieze and all forms of construction where ornamental plaster work is specified.

"Kno-Burn", in addition to being adaptable, is rigid on wide spacing; easy to apply to the wall and easy for the plasterer to work over. Undoubtedly you are thoroughly familiar with Kno-Burn Expanded Metal Lath, but if you are not—

Send for Booklet 33. It will give you the details.

North Western Expanded Metal Company, 903 Old Colony Bldg., CHICAGO

Spanish Tile



Write for Prices on

Catalogue "S" showing a complete line of Ornamental Roofings mailed free to Architects, Contractors and Carpenters.

Ceiling Marquise
Columns Roofing
Cornice Shingles
Cresting Siding
Culverts Skylights
Finials Spouting
Garages Tanks
Gutter Ventilators

Address The Moeschl-Edwards Corrugating Co.

Covington, Kentucky

REYNOLDS ASPHALT SHINGLES

Guaranteed for 10 Years

will last many years longer—Natural colors of garnet, red, gray and green, which never fade

We are the ORIGINAL MAKERS of Flexible Asphalt Slate Shingles and tested our product for ten years before putting it on the market Let us send you a booklet.

H. M. Reynolds Asphalt Shingle Co.

Established 1868

West Grant St. GRAND RAPIDS, MICH.



Promptly!

Contrary to reports from our competitors, all orders for Flex-A-Tile Asphalt Shingles—both the "Giant" and standard—are being filled promptly. We have even gone to the expense of setting up shingle machinery in the open in order to take care of our obligations to our customers.

With the completion of our new shingle manufacturing building—now a mere matter of hours—our former capacity will be doubled.

Never has Heppes service received so severe a test and "delivered the goods" so splendidly as at the present time and in the weeks following our fire.

Heppes promises will always be filled, regardless of what it costs.

THE HEPPESS CO.

Manufacturers also of Asphalt Paint,
Asphalt Roofing in Any Finish and
Utility—the only 5-ply Wall Board.

1010 Kilbourne Ave.

Chicago, Illinois

A New Door Trolley Track

The Wagner Mfg. Co. of Cedar Falls, Iowa, have recently placed on the market two new tracks that will meet a need that has long been felt by architects and builders.

One of these new tracks is called the Wagner Ever-Tight; the other is the Wagner Rain-Shed Track.

The illustrations show at a glance the great advantage of this improved type of track. Instead of being formed entirely of one strip of sheet steel, as the Wagner Tubular Trolley Tracks are, this new track is made of two pieces of steel securely riveted together at the top with one part overlapping the other. This forms a continuous bracket that serves to hold the track securely at every point and at the same time keeps rain from driving in between track and building. To still more completely shed rain and prevent snow and sleet from driving in under track, the Wagner Ever-Tight and Rain-Shed Tracks are made with a downward and outward curve on the outside of the hanger groove (A, Fig. 1), at the bottom, this piece being extended out over the door. This deflects the rain completely and makes the track absolutely weathertight, giving complete protection to the hanger and underside of track as well as the top of the door. This track is bird-proof, being tightly closed at both ends, and the construction is such that it is practically impossible for any dust or dirt to get into the track and impede the trolley. If any dust or trash should be blown into the track it is naturally forced out by the wheels. The shape of the track is such that dust or dirt cannot lodge in it.

The two parts are securely riveted together with $\frac{1}{4}$ inch rivets every 6 inches, the outside pieces overlapping the inside piece at the top with the edge of metal (B), so that it will be forced into the wood, making an absolutely tight connection. To fasten track to building, a bolt hole is provided every 12 inches for a $\frac{3}{8}$ -inch lag screw or machine bolt. The lengths of track are fastened together and the joints made weather-proof by a special bracket which conforms to the shape of the track.

Both tracks are furnished in 4, 6, 8 and 10 ft. lengths; $\frac{3}{8}$ by $2\frac{1}{2}$ -inch lag screws for putting up the track and brackets for joining the sections are included.


The Wagner Rain-Shed Track (Fig. 2) is the same as the Ever-Tight, except that it does not have the piece of metal (A) extending out over the door.

These two new weatherproof tracks, as well as several new models of door hangers especially designed to go with them, are shown in new literature which is just off the press. A copy will be mailed free to contractors, architects or dealers. Address Wagner Mfg. Co., Dept. F, Cedar Falls, Iowa.



J. H. Baldwin Retires

J. H. Baldwin, Secretary and Treasurer of the Southington Hardware Company, retires from active business about August 1. Mr. Baldwin has been identified with this company for the past twenty-eight years, twenty-five years as an officer. His associates in the hardware and tool manufacturing business and his many friends in the trade will miss him sadly.



View of Hanger.




Fig 1



Fig 2



For Service **For Price**

G **GENUINE FRANKLIN TUNNEL** **G**
ROOFING SLATE

During its life, you will probably roof a building four or five times. The expense is great. Use G. F. T. Slate and only one roof is necessary. The cost? Practically the same as any good shingle. Cleaner and more artistic, too; also fire-proof.

Send for the **FREE BOOK** that gives real facts about G. F. T. Roofing Slate. Samples and Prices, too.


SLATINGTON SLATE CO. **Slatington, Pa.**


THE ONLY ROOF THE ONLY ROOF
 THAT THAT
 STAYS PAYS
 THE ONLY
 ROOF YOU CAN
 AFFORD TO CONSIDER

for pleasing results and endless freedom from roof troubles and costly repair bills is

RCD **SHELDON'S** PURPLE
 GREEN **SLATES** BLACK

The use of any artificial substitute means endless expense and dissatisfaction. Our booklet "The Reason Why," tells every reason why **SHELDON'S SLATES ON YOUR ROOF WILL PUT DOLLARS IN YOUR POCKET.** Post a postal and get posted.

F. C. SHELDON SLATE CO., Granville, N. Y.

HIPPED TURRET SKYLIGHT



with swinging sash. Sides 24" high; all windows on each side made to open at the same time. Operating device securely locks them open or closed.

The Skylight is of guaranteed quality. You can use it on any of your buildings with the assurance that it will stand the wear. Watertight. Can be set up in a moment by an inexperienced man.

Write for our Skylight Catalog and Prices

Galesburg Sheet Metal Works - **Galesburg, Ill.**

FOSTER HIPPED SKYLIGHTS

Here is a neat skylight that is a popular seller. We manufacture many designs suitable for all roofs.

Foster Skylights are waterproof, and have the largest possible glass area. It requires no experience to place them. You need no special tools. Hammer and nails are all that is necessary. Send us the dimensions of the skylights you need and let us give you our prices.



Send for
 our Catalog

FOSTER SHEET METAL WORKS
530 N. Tenth St., - **Springfield, Ill.**

West Bangor
Slate Roofs

Slate has always been recognized as the "only" roof for all buildings erected for durability. The best structures of the past 200 years have been roofed with slate.


Years ago, the method of quarrying made slates somewhat expensive. With modern methods the cost has been reduced until slate is as inexpensive as shingles or any of the composition roofings.

There is a West Bangor Slate suitable for all uses. The selection offered is one of the widest you can find. Prices and quality of West Bangor Slate will please you.

Samples of West Bangor Slate and price list will be mailed to you promptly. Send your name and address. We can show you that this "most durable of all roofs" is the most economical in first and last cost.

Bangor Slate Mining Co.
Trust Bldg. **Bangor Penna.**

The Big Man in the building business



is the man who delivers the most satisfactory house to the owner. No chain is stronger than its weakest link. No house is better than its roof—generally the weakest link in any building, because most roof makers acknowledge that the roofs they put on need repainting, recoating and replacing. Naturally the man who builds a house whose roof lasts as long as the foundation, and that without constant paint or repairs, is building for himself a substantial business and reputation that enables him to get better prices. You can build such a house by covering it with


Genuine Bangor Slate

"Why" and "how" we shall be glad to tell you without obligation. Let us also explain to you our system of co-operation which picks out for you the substantial trade of your town, able and willing to pay good prices for good material and good workmanship. We have done this for many carpenters, builders and roofers. We can also do it for you. Will you let us? Write us today. Send the appended coupon.

August, 1914
 Genuine Bangor Slate Co.
 Easton, Pa.

Please send information.

Signed
 Address
 Easton, Pa. City State



Cut Geared Dumb Waiter

The Warner Elevator Manufacturing Company are now making a special offer on their cut geared dumb waiter, built expressly for use in hotels, restaurants and private houses. Hundreds of them have been installed in apartment houses of three, four and five stories.

The gearing operating this dumb waiter is cut from the solid blank on a milling machine making every tooth perfect, which enables it to run with very little noise and with little liability of getting out of order. The cars are made of ash with removable shelves. The counterweight is adjustable. The car is suspended by an iron wire tiller cable and the brake is automatic in operation and will hold the dumb waiter when loaded at any point while being loaded or unloaded.


These dumb waiters are set up complete and run before they are shipped from the Warner factory, and it is a very simple matter to install them, as all the gearing is trued up and put in perfect working order and shipped in this condition. Three standard sizes of this dumb waiter are carried in stock and can be shipped on a day's notice. The guides and the carriage are made of maple and any number of shelves or trays will be furnished.

The Warner Elevator Company, Cincinnati, Ohio, have been building this style of dumb waiter for the past twenty-five years; hundreds of them are in operation.



Two-Door Auto Coming Style

The most significant announcement of the year in the automobile industry is the introduction by the Kissel Motor Car Company of a two-door body as a standard construction. This revolutionary style is offered as an optional feature of the new Kissel Kar 48-"Six," known as series B.



New Kissel 5-Passenger Car Has One Wide Door on Each Side.

For some months the Kissels have been building this body type on special order, and with such increasing success that it was decided to manufacture it in quantity.

The two-door body is very handsome, giving the car a notable distinction as well as grace and smartness. It is a perfect, unbroken stream line from the bow of the bonnet to "midships." Both driver and passengers enter the tonneau from 26 inch doors set at the rear on either side of the car.

The front seats are individual and between them is an eight inch aisle permitting free passage from the rear. Both a four and five passenger model is offered, the rear seats in the four passenger being separated by an arm.

By those who recall how completely and quickly the introduction of the four-door type supplanted the old "open front" automobile, a repetition of history is predicted. It is pointed out that while the four door served no purpose except to beautify the lines of the car, the two-door style offers improved comfort and convenience as well as a better appearance.

The new 48 "Six" is an extremely classy car and with the two-door body will unquestionably attract wide attention.



Copper Bearing Sheets, both Black and Galvanized, are designated "C. B. Keystone Grade," added to regular brand, as indicated above.



C. B. OPEN HEARTH
16
32 POUNDS COATING

Copper Bearing Roofing Tin bears the stamp "C. B. Open Hearth" in addition to the brand and weight of coating.

Copper Bearing Sheets and Roofing Tin

Have STEADILY INCREASED in consumption from 5,318 tons in 1911, to 74,975 tons in 1913—another evidence of the recognized ability of this material to satisfactorily meet the most exacting requirements of architects, builders and property owners.

The superiority of Copper Bearing Steel for Roofing and exposed sheet metal work has been proved by careful research and actual service tests. Our booklet, "Copper in Steel—the Influence on Corrosion", contains indisputable evidence of added durability.

American Sheet and Tin Plate Company
General Offices: Frick Building, Pittsburgh, Pa.

DISTRICT SALES OFFICES:

Chicago Cincinnati Denver Detroit New Orleans New York Philadelphia Pittsburgh St. Louis
Export Representatives: UNITED STATES STEEL PRODUCTS COMPANY, New York City.
Pacific Coast Representatives: UNITED STATES STEEL PRODUCTS COMPANY, San Francisco, Los Angeles, Portland, Seattle

IVES PATENT WINDOW STOP ADJUSTER

Prevents Drafts, Dust and Window Rattling



The only stop adjuster made from one piece of metal with solid ribs and heavy bed that will not cup or turn in tightening the screw

Descriptive circular mailed on application

THE H. B. IVES CO.

Manufacturers of Builders' Hardware
NEW HAVEN CONN., U. S. A.

AGENTS \$45 TO \$80 A WEEK



Thousands of dollars paid to agents already in the field. Smith, Ohio, got 18 orders first week; Meyers, Wis., \$250 profit first month; Newton, California, \$60 in three days. You should do as well. 2 SALES A DAY MEANS \$300 A MONTH. The work is very easy, pleasant, permanent, fascinating. It means a business of your own. We want good agents in every

county in the United States, Canada and Mexico.
NEW INVENTION Just out. Nothing like it. **FOLDING BATH TUB.** Gives to every home a complete bath room in any part of the house—without expense. Biggest, quickest, surest money maker of the century for agents. Territory being rapidly assigned. Send your application today. **100% PROFIT** We back you with our capital and experience. We give you complete instructions, assistance and co-operation. No charge for territory. Don't delay. Send your name at once. Write plainly and give name of your county. Complete particulars FREE. Write today.
ROBINSON CABINET MFG. CO., 467 Factory Bldg., Toledo, O.

A METAL TAG LIKE THIS is on Every Bundle of REAL BOSTWICK TRUSS-LOOP METAL LATH.



If you want the best metal lath,
If you want the heaviest metal lath,
If you would save money on your metal lath and plaster work,
If you want the firmest plaster bond,
If you want the most satisfaction and the largest profit,

See That This Tag is on Every Bundle of Metal Lath You Buy.

THE BOSTWICK STEEL LATH CO.
NILES, OHIO

Big Savings For Contractors and Builders— Buy Direct From Us at Wholesale Prices



GET your building material, lumber and millwork at less than wholesale prices! All goods guaranteed to be absolutely as represented, with safe delivery and satisfaction. Send today for our brand new 250-page catalog of Millwork and Building Material. It contains 3,000 superb illustrations and 8,000 bargains for you to save money on. Get our magnificent Book of Modern House Plans also. We ship you lumber, flooring, doors, windows, mouldings, porchwork, building paper, hardware, tinwork and roofing. Note the few bargains listed below.

H. H. Munnings President.

Porch Post
Clear Fir
4x4, 8 Feet
55c

**8000
PRICE SAVING
BARGAINS**

Get Our Two Free
Books Today

**Door and Window
Screens**

We can supply any kind and style. Rustless galvanized, bronze or black wire—clear pine and oak frames. Window screens for 24 x 28 2-light windows, full size, 79c. Catalog shows all sizes and prices.

100 feet of Quarter
Round, Dealer's Price,
\$1.00—our
price, only **30c**

Glazed Windows
of all kinds, ready for
quick shipment.

2-Light, 65c up
4-Light, 77c up
12-Light, 83c up

1-Light
Stall
Sash
34c

4-Light
Barn
Sash
47c

**Porch
Spindles**

Hardware

Wearwell Paint

Perfect guaranteed
house paint—

\$1.20

per gal. in
5-gal. kit.

We have
all kinds of
paint at
wholesale
prices.

All kinds
of building
hardware.
You can't
beat our
goods or
our whole-
sale prices.

Estimates Made Free—We Furnish Everything for Building Your House—We Sell at Wholesale—We Guarantee Everything to be Bright, Brand New Material. We Guarantee Safe Delivery. Don't Plan a Building without Our Aid!

For \$838 We will furnish complete all lumber, millwork, hardware, spouting, paint—everything except

masonry and labor to build 7-room house. Plans free. 113 250-Page Catalog and Book of Plans mailed you FREE. Write today for these books. You need them—whether you build now or not. Both books free. Fill in this coupon right now—mail at once.

CHICAGO
MILLWORK SUPPLY
CO.

CHICAGO MILLWORK SUPPLY CO.
1422 W. 37th Street
CHICAGO

1422 W. 37th Street
CHICAGO, ILL.




Please send your free Catalog. (If Plan Book is wanted also, place check mark in ☐ below)

☐ Plan book.

Name.....

Address.....



Klauer's Steel Ceilings

Are the kind you want for the work you now have coming up.

Unexcelled as to designing and mechanical perfection, they are most economical as well as most desirable.

Get our complete catalog and let us figure on your requirements.

Klauer Manufacturing Co.

Dubuque, Iowa

Highest in Quality and Design

Lowest in Price



METAL CEILINGS
SHINGLES
TILE

Our "Safe-Lock" Shingle is a Wonder of Perfection
Write for Sample



The large number of exclusive and beautiful designs enables you to make a quick and appropriate selection for any of your buildings.

Our Metal Ceilings, Metal Shingles and Metal Roofing Tile are of the very best material. You can make no mistake in selecting from our stock. We guarantee satisfaction.

Prices are very low. We employ no travelling salesmen. We cut down expenses and give you the benefit in lowered prices. When you order from us, you get the very best the market offers at prices lower than you will find elsewhere.

Prove this for yourself. Send for catalog and prices now.

**THE CANTON METAL
CEILING CO.**

1947 Harrison Ave.
CANTON, OHIO



Novo Portable Saw Rig

Every builder or contractor can save money and make money by owning a good portable saw rig or wood worker.


The variety of work that can be done, the accuracy with which it can be done, and the saving of time over hand work are features of the Novo saw rig that make its initial cost an economical investment. This is the portable power rig just brought out by the Novo Engine Company, 444 Willow St., Lansing, Mich.

The cost of operation is so small that it hardly need be mentioned. The Novo saw rig No. 4 will work hard all day at an expense of less than 60 cents for fuel and oil.

Novo saw rigs are adapted to any place where light or medium sawing, boring, planing, etc., is to be done. They are built to stand hard, continuous service.

The real vital part of any saw rig is its power plant. If you are not familiar with the reliable Novo engine, which furnishes the power for Novo saw rigs, it will be worth your while to write for "Reliable Power," the book which describes its various features in detail. The Novo is a well balanced engine with little vibration. It is simple in construction and as near trouble proof as any engine can be built. The special governing system with which every Novo engine is equipped is claimed to bring about a great saving in fuel, for instance, if a 4-horse-power Novo is doing 2-horse-power work it uses practically 2 horse-power fuel.

The frame is made of 3½ by 3½-inch seasoned hard wood,



Novo Portable Saw Rig.

accurately framed and strongly bolted, insuring strength, rigidity and durability.

The top is 54 by 30 inches, made of accurately planed iron. It is strongly hinged to the rear of the frame and is readily raised and lowered by the hand screw, and firmly held in any position by clamps on each side. It is independent of the jointer table, and neither interferes with the other.

The ripping gauge is adjustable and has a tilting fence for bevel sawing.

The cut-off gauge can be set to cut squares, mitres or any angle desired.

The boring table is adjustable. The bits have ½-inch shanks, and are carried in the end of the saw arbor, securely held by a hollow safety set screw.

The jointer or planer is entirely separate from top of machine. It has a steel cutter head fitted with two 6-inch knives and slotted on two sides to receive matcher bits or moulding cutters for working a large variety of shapes.

The regular equipment consists of 4-horse-power engine, with batteries, spark coil and connections, endless driving belt, rip and cut-off gauges, one 14-inch rip saw, one 14-inch cut-off saw, one ½-inch and one ¾-inch dado head; one jointer head with two 6-inch knives; one each ½-inch and 1-inch auger bits; one sander drum and sander disc; one emery wheel with arbor; one throat piece for dado heads; one throat piece for saws, oil can and wrenches.

A smaller 3-horse-power machine is also offered. For further particulars address the Novo Engine Company.

Move the Holes Instead of the Plates



Wiley's Adjustable Lock Striker

will save your door casings from ever having to be CUT, which is worth many times its cost.

If your door sags and the LATCH BOLT is out of line so that it will not catch and keep the door closed, THE REMEDY WITH WILEY'S ADJUSTABLE LOCK STRIKER IS VERY SIMPLE. With A SCREW DRIVER you release the screws and adjust the INNER PLATE to the proper position and set the screws again and your troubles are all over as far as the door is concerned.

They are made in two qualities from cold rolled steel and from solid brass, and finished in all finishes. Each one is adjustable for right or left strike door.

Size: Full length, 6 $\frac{3}{4}$ inches.

Size: Upper opening, $\frac{3}{4}$ x $\frac{9}{16}$.

Size: Lower opening, 1 $\frac{1}{4}$ x $\frac{1}{16}$.

Wiley Hardware Mfg. Co.,
(Not Incorporated)

746 First National Bank Bldg.,
CHICAGO, ILL.

Phone Randolph 5334

WAGNER DOOR HANGERS

are furnished in styles, sizes and weights to meet every requirement of modern building. While there are more than a score of distinct models all have certain Wagner features that make them pre-eminently the best Door Hangers on the market. For instance:

Wagner Ever-Tight Trolley Track

—a specially designed new track that meets a long felt want. Fits up absolutely tight to building and lower part protects hangers and top of door. Impossible for rain or snow to drive in. Self-cleaning the same as all Wagner Tracks. Absolutely bird-proof. Impossible for door to come off.

High grade roller bearing wheels
Improved tandem trolley
with bumper on end which
prevents damage to
trolley wheels.

Patented cam and lateral
adjustments that
insure easy and accurate
adjustment.

Other important features of Wagner Trolleys and Tracks are illustrated and described in our new circular which we will gladly send you, free. Write for a copy today.

Ask Your Dealer

for Wagner Door Hangers and Tracks. If your dealer isn't inclined to supply you with Wagner goods, we'll fill your

order direct.

Wagner Mfg. Co.

Dept. F
Cedar Falls,
Iowa

This Illustration

shows a full-size cross section of Wagner Ever-Tight Track. All Wagner tracks are made of high carbon steel. Insures longer life and better service.

THE Rapid Increase

Two New Features



The bead is made extra long, in shape of half an oval, reinforcing the ceiling plates at joints, fitting snugly over underlapping bead, making a tight and perfect-fitting joint. The top of nailing button is counter-sunk, forming a self-centering, self-guiding, never-slip nailing point. These features permit a considerable saving when erecting.

in building has created an enormous demand for Berger's Classik Steel Ceilings, and no ambitious dealer can afford to overlook this profitable opportunity. Write to our nearest branch today for large illustrated catalog.

The Berger Mfg. Co., Canton, Ohio

For prompt service address nearest branch.

New York
Philadelphia
Boston

St. Louis
Minneapolis
San Francisco

We also manufacture Ferro-Lithic and Multiplex Reinforcing Plates, Metal Lath, Roofing, Eaves Trough and Conductor Pipe, and Sheet Metal Building Products of all kinds.

Export Department—11th Avenue and 22d Street,
New York, N. Y.

D. A. Johnson Now Chicago Mgr. J. Dixon Crucible Co

Mr. Dudley A. Johnson succeeds the late Sam Mayer as Chicago Branch Manager of the Joseph Dixon Crucible Company.

He had for a number of years been an assistant to Mr. Mayer at Chicago, and he now comes to the full branch management of the Chicago office, fully equipped by the experience of many years' acquaintance with the Dixon line and the Dixon customers.

When he came with the Dixon Company in 1898, he brought with him experience in the lead pencil and stationery business from P. F. Pettibone & Company and the Holyoke Envelope Company. During the first few years after coming with the Dixon Company, he had charge of the lead pencil department and the school work. Later on Mr. Johnson assumed charge of the crucible and black lead department of the Dixon Company in the Chicago territory, and is, therefore fully equipped to ably represent the Dixon Company as its branch manager in the Chicago territory.




A No-Slip Shinglers' Chair


A shinglers' chair with which a carpenter can work a third faster, lay shingles easier and entirely without injury to the roof is now being offered by the Foster Sheet Metal Co., Springfield, Ill. The illustrations show how this chair is made and how it is used. Some might think from the looks that this seat would slip, but those who

have used it say it will hold two or three men perfectly safe. In fact, it is almost impossible to place this roofers' seat so that it will slip. It is easily picked up and moved along. The sharp claw points at both bottom and top hold the seat securely in position.

Carpenters find this seat very useful, as do also painters who use it in painting valleys, roof gables, etc. After the first three or four courses of shingles are laid this seat is



Seat on Roof



Seat Closed

all that is needed.

Although it has been on the market only a short time the manufacturers say it is selling rapidly—many repeat orders. In one instance a salesman calling on a job where men were working sold five; one to nearly every carpenter on the job. For further particulars address the Foster Sheet Metal Co., Springfield, Ill.

The IRWIN Bit

is imitated as regards pattern, but Irwin Quality cannot be imitated. Look for the trademark (illustrated below) stamped on the shank of every genuine Irwin Bit.

The IRWIN Bit
Reg. U.S. Pat. Office

**You Men
Who Use
Tools!**

**Make Your
Work
Easy!**

You know that good work demands the best you are capable of. You can't afford to be handicapped by inferior tools that won't stand up to the work. Try out a genuine Irwin Bit. Use it on hard lignum vitae; use it on soft pine—it will turn out as clean a job of boring as you could wish for.


The solid centre means greatest strength—no danger of snapping where the twist joins the shank, where other bits are weak. But be sure you get the genuine Irwin. The word "IRWIN" guarantees a bit well worth your money.

**Demand
the Genuine
IRWIN Bit**

**The
Irwin Auger
Bit Company
Wilmington, Ohio**



The Opening Door



Will swing safely on
STANLEY'S
BALL BEARING HINGES
 with Non-Rising Pins

Write for Booklet "Properly Hung Doors"

To Department "A"
THE STANLEY WORKS
 New Britain, Conn.
 New York Chicago

S.W. S.W.



These Files Cut Deep

Saw dull? No matter, these Keen Kutter files will soon fix its teeth so they'll bite deep and clean into long-seasoned hard wood. These files cut deep, because *they're* cut deep.

KEEN KUTTER

files have the quality in the steel that makes them work long and true, that puts vim in their cut. Try Keen Kutter Flint Paper and you'll be pleased. The dealer is authorized to return your money if you find any Keen Kutter goods not giving satisfaction.

If not at your dealer's write us.



One quarter ream of Emery Cloth No. KCL Price \$1.00

Slip Taper Files No. K0885 Price \$0.10 No. K0887 Price \$0.15

Simmons Hardware Company St. Louis, U. S. A.

\$1.00 BUYS THIS KEYSTONE FOLDING SAW CLAMP



This fine malleable iron saw clamp can be attached instantly to work bench, tool box, window sill or the edge of a board. Guaranteed against breakage. Jaws 14" long with felt faces to protect saw and deaden noise. Have 3" opening, giving sufficient clearance for quick and easy working. Clamp weighs but 3 pounds and when folded takes up no more room in the tool chest than a hammer does.

Try it 60 Days. Money Back if not Satisfactory.

The Keystone Folding Saw Clamp is guaranteed to be exceptionally fine in design and workmanship. The special \$1.00 price is offered for a limited time only. Send a \$1.00 bill and a Keystone Clamp will be delivered to your door without extra charge. If it does not prove entirely satisfactory in 60 days, we'll return your dollar.

Illustrated Circular on Request.

KEYSTONE GRINDER & MFG. CO., 106 Wood St., Pittsburgh, Pa.

Folded for the Tool Chest.



This is the **Standard Take Down Square.**

It makes good with the user.

Send and know more about it.

Southington Hardware Co.
 Southington, Conn.

2 Big Bargains in Mixers

If price talks and quality counts, here's your opportunity to get that concrete mixer you need at bargain prices. They are built right, look right and work right. Investigate if you want a bargain.

The Highway Special

Made especially for county and bridge work. 28 in. rear wheels, 20 in. front, 4 in. tires with standard wagon trucks for big hauls over rough country roads. Has stationary measuring hopper which can be loaded while batch is mixing.



The Steam Steel King

10 cubic ft. size. Compact Portable. Big capacity machine. Built of steel. Can also be equipped with gasoline or electric power.

Write for Catalog and Special Fall Prices on complete line of mixers. Our modern construction and improvements will please you. Our prices will surprise you. Address,

American Cement Machine Co., Inc.
 1006 Johnson St., KEOKUK, IOWA.





Make Your Buildings Fireproof and Weatherproof with

KELLASTONE
IMPERISHABLE STUCCO

The Stucco that contains no lime or Portland cement—that “gives” with the settling of buildings instead of cracking—that adheres to brick, stone or wood—that will not discolor from moisture or climatic changes and that lends itself to scores of beautiful, attractive finishes on both old and new buildings.

Kellastone Imperishable Stucco is a non-conductor of heat, cold and dampness. It never has to be treated with weatherproof solutions. It reduces insurance premiums and makes a satisfied client every time.

As an interior plaster, its elasticity prevents unsightly cracks, and its hardness prevents marring when struck by furniture.

Kellastone Composition Flooring

for public buildings and sun parlors, bath rooms, kitchens, etc. In private homes, is sanitary, waterproof, fireproof and abrasion-proof. Ask for details and specifications. Literature gladly mailed on request.

The National Kellastone Company Room 504 Association Bldg., Chicago, Ill.



SPECIALLY TREATED

The foundation of Bayonne is built upon the best quality cotton duck.

Into this is forced, under pressure, a special preparation that permeates every fibre.

This treatment renders the finished fabric positively waterproof, and almost wearproof.

Bayonne can be laid dry over boards, and is painted after laying, merely to match the trim of the porch—not for protection of the covering.

Easier to lay than tin, tar or prepared roofings—and will last longer, and makes a neater job.

Write for Sample Book “N” with prices and laying instructions.

JOHN BOYLE & COMPANY, Inc.

112-114 Duane St., New York City.
70-72 Reade St., St. Louis.
202-204 Market St., St. Louis.



An Addition to the “Standard Mixer” Line

One of the most recent inventions in the concrete machinery field is the removable discharge hopper which appears in the illustration below.


The efficient engineers of the Standard Scale & Supply Co., Pittsburgh, Pa., are always and ever alert to the most economic assistance to their host of patrons.

When the low-charging feature of their mixers was supplied to the trade, their activities did not cease, but through perseverance and careful study they now offer to the contracting world the Removable Discharge Hopper and thereby add another distinctive, effective feature for contractors to their already popular line of machinery.

Only the most cardinal points of the Removable Discharge Hopper can be covered in this first announcement. It is certain that this new device will continue to meet with the same enthusiasm among contractors.

In operation, the Removable Discharge Hopper is placed so that the entire batch can be discharged from the drum into the hopper. Then the wheelbarrows are loaded from it, while another batch is being mixed. The hopper holds more than one batch of concrete so that the delays in placing concrete in forms by the wheelers will not effect a delay in the mixing process. Therefore work can be rushed to a maximum output by increased speed of the workmen at the charging end and also at the distributing end of the mixer. A door is provided in the hopper end, and by operating it, the concrete flows into the barrows. This enables the barrows to be charged with any quantity desired. The hopper can be folded up against the drum in cartage and removed when discharging into wheelbarrows, or when discharging into forms as well as into hoisting elevators. All the “Standard” low-charging mixing machines can be equipped with the hopper at a slight extra cost. They can be furnished to the present owners of machines by being mounted on four legs, not being necessary to attach it to the truck frame, although it can be done.

The Removable Discharge Hopper, as shown in the illus-



“Standard” Mixer with Discharge Hopper.

tration, is constructed of sheet metal and of the usual sturdy design that is characteristic of “The Standard” mixers.

To attest to the receptive manner in which the trade desires this time-saving device, the F. Johnson Co., of Chicago, Ill., after buying one, ordered all the remainder of their machines equipped. The F. Johnson Co. are one of the largest contractors of foundations of flats in the United States.


In this device, contractors will again appreciate that it is not in the material used, but in the use of economical machinery that the greater profits are made.

The Standard Scale & Supply Co., of 1345-47 Wabash Ave., Chicago, Ill., with offices in Pittsburgh and Philadelphia, Pa., and New York, have considerable data on “The Standard” Removable Discharge Hopper and will be pleased to mail a catalog to anyone interested.



Get My Latest Engine Offer

Let a WITTE earn its cost while you pay for it. Take full 60 days' Free Trial to prove its big value.



WITTE Engines

Kerosene, Gasoline, Gas, Distillate

Five - Year Guaranty

I unqualifiedly guarantee every WITTE engine for five years against defects, and consequent faulty operation. I carry the risk, as I have done for my thousands of customers during 27 years.

Ed. H. Witte.

All styles 2 to 22 H. P. Used and recommended by shop, mill, and factory men all over the earth. All my life I have been a shop man, making my own engines. I sell only what I make. That is why, for 27 years, WITTE engines have always made good and stay good.

Look at These Prices!

4 H. P.,	\$ 69.75
6 H. P.,	99.35
8 H. P.,	139.65
12 H. P.,	219.00

Other sizes proportionately low. WRITE FOR MY FREE BOOK, and all about my New Liberal Offer BEFORE you arrange to try any engine. I save you money, besides giving you the easiest chance to get the best engine service.

Write me to show you.

Ed. H. Witte, Witte Iron Works Co.
1779 OAKLAND AVE., KANSAS CITY, MO.

ELLIS ENGINES

Carpenters, Contractors and Builders are making far bigger profits on their jobs by installing a portable, wood-working plant equipped with an Ellis Engine. It is the most economical, most efficient engine they can buy. More power at half the cost is the Ellis way of doing the work. Ellis Engines are


Portable—Easy to Move

from job to job. Another strong point in favor of Ellis Engines, is their low up-keep cost. They develop more power on Kerosene than some engines on Gasoline. They also operate successfully on distillate, petrol, alcohol or gasoline. Ellis Engines

Save 50% on Fuel

Easy to operate—only three working parts. Ellis Engines have patent throttle, giving three engines in one. Force-feed oiler, automobile muffler, speed-changing governor and many other exclusive features. Run either way—reversible while running—this feature of construction is of particular importance to contractors. Buy direct from factory and save money. **We pay freight, 10-year guarantee, 30 days free trial.** Write for new catalog showing 1914 Models with special prices

ELLIS ENGINE CO.
72 Mullett St., DETROIT, MICH.



For Sale or Wanted

ADVERTISEMENTS IN

AMERICAN CARPENTER and BUILDER

BRING


RESULTS

If you want to buy or sell new or second-hand machinery, contractors' equipment, supplies, etc., advertise in our classified columns and get results.

"BULL DOG" HOIST

a builders special hoist equipped with a Bull Dog Engine

3 Sizes:
5, 6 and 8 H. P.




A specially strong piece of equipment for all single or double platform elevating, direct hoisting and pile driving. This Hoist can be used for the greatest variety of work. Equipped with the Bull Dog Engine which is simple and easy to understand. Every engine guaranteed to develop ample power at all times. The Bull Dog Engine assures complete freedom from engine trouble.

Progressive Builders should write for Catalog 21 of up-to-date machinery and equipment. It is sent FREE. **BATES & EDMONDS MOTOR CO.**
Lansing - Michigan

PARTITIONS

Suitable for constructing offices or small rooms. Made portable so that they can be readily set up or taken down again. Oak or mahogany. Pack like doors for shipping. Convenient, durable and low in price. Send for circular and prices.

WALTER F. BARNES CO. MANUFACTURERS NEW YORK 372 Broadway



Use Webster's Elastic Cement

For Bedding Slate, Pointing Wood, Stone, Brick and Iron for Waterproofing and for Setting Glass.

Write for Prices

W. F. Webster Cement Co., Cambridge, Mass.
Established 1848

8 Grape Vines, 6 Currant Bushes \$1

All best 3 year old stock. If planted now or early spring will fruit next summer. Should ground be frozen we tell you how to protect and keep them dormant ready for early spring planting. Orders accepted now and forwarded at any future time if preferred. Grapes are Worden, Niagara, Iona, Concord, the best early, medium and late varieties. Large cherry currants. Write for list of our \$1 Friend Makers, consisting of all kinds of Fruit Trees, Berries and Roses.

The Landscape Garden Co., Newburgh, N. Y.

New Rotary Sand Screen

The Grand sand sifting machine is a light screen that can be easily moved from one job to another, as one man can handle it easily. It is very strongly and rigidly built to stand up under hard service. There is nothing complicated about the screen to get out of order, and is ready for service as soon as placed on the work.



The Grand Sand-Sifting Machine.

One great advantage of this screen over old methods is that it is equipped with an automatic patent tapping device which keeps the screen clean when sifting wet material. This tapping device is controlled by an adjustable spring which can be set so that tapping device will strike the screen either light or hard, just depending upon the condition of your material. It can also be thrown out of gear entirely where the material is dry.

With this screen, it is only necessary to handle the mate-

rial once, as the coarse material rolls out of the discharge end of the screen in one pile and the screened material is thrown off to the side. The screen is very easily turned by a small boy, and will screen all the material two men can shovel into it. It can be equipped with pulley to attach to power if desired. The wire screen is quickly removed by simply taking out two small bolts, and any different size mesh can be quickly put on to suit the requirements of the contractor's work.

In this machine there is no cheap iron to rust away, no gearing to wear out, and no complicated mechanism to get out of order.

The machines are complete, set up and ready for work. All machines are guaranteed to be as represented.

Weight, 100 pounds.

For further particulars, address the Hall-Holmes Manufacturing Company, 420-424 Oak Street, Jackson, Mich.

WATERLOO CAST IRON Coal Chutes



Protect the house from careless coal men. They are burglar proof—unlock only from the inside.

Being made of cast iron, are not affected by the weather.

Wire glass in door furnishes light to cellar. When door is open, the glass is protected by heavy steel, which operates automatically.

The watertable at the top of chute protects the inside of foundation from moisture. Doors are extra heavy, with three hinges at top, and are made with a beaded edge which extends over the border opening, making a tight joint. Are made to fit any depth wall.

Send for catalog, which quotes special prices to contractors.

The Waterloo Register Co.

114 Rath Street

Waterloo, Iowa

Discerning Architects Realize the Practicability of This GENERATOR

Position of Mercury and Water when Generator is Producing No Pressure

Note that when water in the plant is cold, that the mercury (13) is all at the bottom of mercury pot (7).

This bed of mercury is about 1 inch in depth. As fire is made and water begins to expand, it flows into Generator at (6) and pressing down on the mercury at (11) forces the mercury down and then up through circulating tubes (4). When mercury has been pressed down below top of inlet (14) the water passes over the mercury and into circulating tube (4). (See opposite illustration.)

The Honeywell Heat Generator is one feature that has won thousands of friends for the Honeywell System. Architects, in particular, quickly perceive its practical advantages—its safety—its complete dependability.

More and more are the leading architects of not only America, but also Europe, specifying the

Honeywell System of Hot Water Heating

The explanation for this great popularity is simple—upon expert investigation and exhaustive test the Honeywell System has time and time again demonstrated its marked superiority in adjusting itself to changeable weather conditions—in economy of fuel—in ease of control and operation—in low cost of installation in either old or new structures.

The peculiar advantage of the Honeywell Generator lies in the fact that it induces faster circulation throughout the hot water heating system. This inevitably causes the water to change over the heated boiler plates oftener—thus utilizing thousands of more heat units from the fire. It also makes it possible to heat to a higher temperature—240° without boiling—should temperature above normal ever be needed for extreme cold weather.

You will find in the Honeywell System the solution of your most vexing heating problems.



We will gladly send any Architect a Complimentary Copy of our Heating Manual upon request.

This handy desk book of 160 pages is a pocket book of heating system facts—5000 architects now number it among the most helpful books they possess.

HONEYWELL HEATING SPECIALTY CO.
140 Main Street Wabash, Indiana


Position and Action of Mercury and Water when Generator is in Complete Operation

—producing 10 pounds pressure. The ascending water carries with it quantities of mercury. When the mercury and water reach the top of circulating tube (4), the water swiftly passes up and around the deflector, and the mercury will descend through space (8) into space (15), where it operates to raise the mercury level and maintaining constant, speedy circulation.



WHEN WRITING ADVERTISERS PLEASE MENTION THE AMERICAN CARPENTER AND BUILDER

WE HAVE ELIMINATED —THE LAST— OBJECTIONABLE FEATURE



of the
Warm Air Heater
by making a
**Gas and Smoke
PROOF JOINT**

Note the
**Majestic
Covered Joints**

Cement cannot
work out

No Leakage Possible


OTHER FEATURES are: Slotted fire bowl, drop grates, large double feed door, extra large ash pit and door, easily cleaned radiator, heavy castings; all of which tend to make it the last word in cast iron furnace construction. Economical and easy to operate. Write for our free Heating Booklet. Submit your plans and let our Engineering Department make a heating plan and estimate free.

Dealers write for open territory

THE MAJESTIC CO., HUNTINGTON, IND.
1001 Erie Street

The Window Chute

**For
Your
Coal
Bin**



Ready for the Coal Man

The Window Chute is a selling feature for any Residence or Building.

**THOUSANDS IN USE—
THE VERY BEST**

**If You Build,
Buy, Own**

**Be up to date and
Have the World's
Best**

**Write for
Booklet C**



A Light Basement

HOLLAND FURNACE CO. :: Holland, Mich.

World's Largest Direct Installers of Furnaces.



2270 NAMES

of satisfied customers, who have bought their furnace equipments direct from our factory, are listed in a little booklet we send out with our hand book on furnace heating. A good many of these people are **contractors** who have bought from us again and again, and they buy because they find it **profitable**. **One hundred and one letters**, from these customers, are also shown in the booklet, and they are such as to convince any sane man that he can save money and provide a satisfactory heating equipment, and make his house comfortable, with a minimum cost of fuel and labor, by using our furnace and following our method.


We cater particularly to the trade of **contractors**, selling direct to them at better rates than we would make to dealers, for we do not offer our furnaces to dealers. We plan the complete heating equipment, free of charge; we ship the whole outfit, made to measure, with blue

prints and an illustrated book of instruction, and we loan tools, if desired, so that any contractor can put up his own heating equipment with success. We sell these equipments **on trial** and **we guarantee complete satisfaction**. The next house you have, requiring heat, just send us a sketch and let us tell you what we can do.

Hess Warming & Ventilating Co.
1220 TACOMA BLDG., CHICAGO.

**Makers, Also, of White Enameled Steel Medicine Cabinets and Electric
Family Dish Washers**

Separate Booklets on these Subjects Free



Build For Permanent Profit

When you have a job of interior finishing, whether in an office building, a factory or a private home, don't forget that every dollar you save for your client will be appreciated and that his continued patronage depends on the value you put into the first job. You will please your patron and make a satisfactory profit for yourself when you use


Roberds Ideal Wall Board

Unlike many substitutes for lath and plaster, Roberds Ideal Wall Board is not a make-shift but is a substantial, time-tried and thoroughly practical interior finish that does not shrink or bulge, does not pull off or warp. It goes on in a truly workman-like manner and stays where you put it. Properly applied, it makes the most handsome, durable and permanent form of interior finish. Our proposition to contractors makes this a most profitable line to handle. Write for territory, booklet, samples and prices.

Roberds Manufacturing Company, 100 Railroad St., Marion, Ind.

How to Make More Money Building Barns

Every man in the building business can have the benefit of W. D. James' barn knowledge and use it to his own advantage and profit. There's more money in building up-to-date, properly equipped barns on scientific principles than in putting up the old type. The right kind of a barn means an enthusiastic owner, and that means more jobs in the same neighborhood.



Get Our Special Blue Print and Building Service Offer

Mr. James is the foremost authority on dairy barn building, and he wants to make you a special offer of complete working blue prints of several practical dairy barns of different sizes and types. In addition to Mr. James' personal co-operation, you can have help from our architectural department, conducted by experts. Write today for all the facts regarding this service.

James Manufacturing Co.

A H. 75 Cane Street

Ft. Atkinson, Wis.




This Valuable Book Free

—tells about new and better construction—lighting—size—site—drainage—general equipment—King system of ventilation; gives floor plans of successful barns. Your copy—**Free**—if you answer these questions: For whom do you expect to build or remodel dairy barns? (Give names and addresses). When? For how many cows? Send your application now for book and complete information.

Metallic Battens Popular

In the six months that metallic battens have been on the market they have made such a hit with barn builders that the Metallic Batten Company have had to increase their output every month; in fact, it has kept them hustling to keep up with their orders and not disappoint their customers. While the first metallic battens were formed by hand, the manu-




Metallic Batts over Painted Barn Boards.

facturers have now perfected and installed complete machinery equipment for turning out battens in large quantities. The machine product is an improvement, since it is absolutely uniform and has a refinement of contour that the first hand-made batts did not have.

These metallic battens are heavy galvanized metal. They come in 8 and 10-foot lengths and can be joined together with interlocking joints. When nailed on between vertical barn boards they present a perfectly smooth wind and weather tight wall. Sliding doors roll flush against the barn where these batts are used, as they do not stick out and interfere as wood batts do.

The metallic battens are labor savers besides making a better job. Write today to the Metallic Batten Co., Owensville, Ind., for full particulars.

How Big Is Your \$ Dollar?



How much does it buy? How many profits does it pay? How many middlemen get a share of it? Think it over. Figure it out. Compare it with my direct from factory to farm one-profit plan and you will know why your dollar spent with Galloway is larger and brings you more and how I can save the farmers of America over a million dollars every year.

Galloway Makes \$\$\$ Grow

Even if you have no ready cash, you don't want to borrow. You can buy from me on credit at direct from factory to farm prices and get the biggest dollar's worth you ever had.

5 New Selling Plans—Cash or Credit

Here they are. Take your choice. 1—Cash with order. 2—Bank deposit. 3—Part cash, part notes. 4—All notes. 5—Monthly payments. One of these will please you and suit your pocket book.

5 H. P. Engine \$99.50. Write for Catalog

It's the best engine for the money on the market. Sold on 30, 60 or 90 days' trial. Send for catalog and find out all about this great Galloway bargain.

Wm. Galloway, Pres.
Wm. Galloway Co.
945 Galloway Station
Waterloo Iowa

You Take No Chances When You Put on Guaranteed Queen Cupolas

They are made right from heavy galvanized steel. Put together by experts. They look right because they are thoroughly finished. They give service and satisfaction. Last a lifetime without painting or repairs.

Don't Experiment—Get the Cupola That Has a Reputation Back of It

On the market 15 years. Thousands now in use. That's the kind for you to use. To prove that the Queen is the best we will ship you one for examination and 30 days' trial.

WRITE FOR CATALOG AND PRICES
Find out what we have and you will not be satisfied with ordinary kind. Address

QUEEN CUPOLA CO., 405 Peck St., Cresco, Ia.



FREE

DRAFTSMAN'S WORKING OUTFIT


Complete Draftsman's Working Outfit—just like I use myself, that you couldn't duplicate for less than \$15.00, given to you absolutely FREE as soon as you enroll. Handsome set of imported instruments, T-square, French curve, triangle, etc., all given away absolutely Free to my students. This offer is limited. Write today.

\$125 TO \$175 A MONTH TO START

That's the ordinary salary for a draftsman. Thousands of positions open. Be the man who gets the fat pay envelope. I will teach you drafting in your own home—during your spare time. I will give you practical instruction—the kind that the men must have who make the big money. I am Chief Draftsman of a large and well known company. Let me help you. Write to me today.

WRITE FOR FREE BOOK. Your name and address on a postal is enough. I will send you free and prepaid my big new book "Successful Draftsmanship." No obligation. Find out about your opportunity in the drafting profession. Send me your name and address—today—now.

CHIEF DRAFTSMAN DOBE, Div. 266Z, Engineer's Equip. Co., Inc., Chicago.



\$25.00

with your order, will bring this magnificent Book Case Colonnade Complete with Art Glass (no hardware) to your station, all charges prepaid.

This offer is good during the month of JUNE. This is the greatest offer ever made.

Do not fail to take advantage of it.

Pedestals 2 feet wide and 3 feet 6 inches high, 6 inch veneered columns. Workmanship perfect in every detail.


22 years in our present location; this should be sufficient guarantee.

CHICAGO GRILLE WORKS

828-838 Wells Street

CHICAGO, ILL.

Bookcase Colonnade



Bookcase Colonnade,
Only \$25.00

In Yellow Pine

Oak.....\$27.00

The pedestals are 4 feet high, 10-inch face and 18 inches extension from jambs, adjustable shelves, panel back and beveled glass doors, 6-inch square columns, beveled edge taper. Castings and cap trim not included.

This is positively the best bookcase colonnade for the price in the market today. Take advantage of this special offer. Quality, satisfaction and safe delivery guaranteed. Order today. State height of opening and what kind of wood.

Catalog No. 35 contains many new designs in Grilles and Colonnades. The book is free. Write for it.

BERTELSEN ADJUSTABLE GRILLE CO.

611-613 So. Clinton St.

Chicago, Illinois


Rain, hail, sleet and snow can't get near a house painted with

Dutch Boy White Lead

and Dutch Boy linseed oil. This paint is waterproof and the wood can't get water-soaked and take the rotting road to ruin. Ask for Folder "A" showing 39 interior and exterior color combinations.

National Lead Company

New York, Boston, Buffalo
Chicago, Cincinnati, Cleveland, St. Louis, San Francisco. (John T. Lewis & Bros. Co., Philadelphia.) (National Lead & Oil Co., Pittsburgh.)



BIRCH PANELS } Free BIRCH BOOK }

Panels of Birch beautifully stained in silver gray, brown, mahogany and other colors.—Also our helpful Birch Book "C" sent post paid.

The interior finish that will satisfy your customers.

**The Northern Hemlock & Hardwood
Manufacturers Association,**

Dept. C. :: :: Wausau, Wisconsin.

Make \$1000 this Summer

Add this extra money to your season's profits. Before winter sets in you can make \$1000 extra by our Co-operative Plan. We don't ask you to take time from your regular work. Our carefully thought-out plan makes that unnecessary and yet gives you a big chance to make extra money.

BUILDERS

become well-paid representatives, without a cent of cost or a moment's wasted time. Look after our interests in your locality. When a man needs a private lighting plant, hand him our catalog and he'll give you the order. Let us send you a full description of the Faultless Pit Generator. Let us make you an offer. Send your name and address quickly.

GEM CITY ACETYLENE GENERATOR CO.

Dept. A

DAYTON, OHIO



The Lightning Estimator
7th. Edition
PUBLISHED BY
BRADT PUBLISHING CO.
JACKSON, MICH.

CHOOSE

IT'S up to you to be the man at the top instead of the man with the dinner pail.

Don't hesitate to grasp this opportunity to win success, for there's always room at the top for the man who knows how.

The LIGHTNING ESTIMATOR

stops worry, lying awake nights, over or under estimating and guessing—in fact, by showing you how to estimate the cost correctly, it spells the word \$uccc\$\$ for you. Don't do yourself an injustice by passing up the greatest opportunity ever offered to Carpenter, Contractor or Builder.

The New Seventh Edition of the LIGHTNING ESTIMATOR

will teach you: How much time and material involved in each part of your work; how to figure on unfamiliar work; how to estimate quickly and correctly on a large job; how to estimate on time, material and prices in all parts of the country.

This Book is written by a man who has made good in this profession, and is based on hard, solid facts, secured by the knocks of experience, making it an invaluable guide to any one engaged in or those about to enter the building business.

If you are just starting out, here is your chance to get a firm foothold. If you are an old timer and getting a little behind the times, here's your chance to brighten up and get some new ideas.

This Edition is bound in cloth, profusely illustrated—a feature not found in other books of this kind. The price, \$1.00. Don't delay. Send for it today.

BRADT PUBLISHING CO.

1260 Michigan Avenue

JACKSON, MICH.

Get Your Material at Cost - - -

It's never too late to buy your material from us. Never too late to take advantage of our rock bottom prices. All you need is our big millwork catalog. You can order direct from it and we will fill your orders promptly (that means *at once*). We guarantee you just as much satisfaction with our selection as if you personally picked out the material at your local dealer's.


Colonnades	\$12.50 to \$40.85
Outside Blinds	.96 " 2.33
Stair Rails, per foot	.05 " .12
Newals (Starting and Landing)	1.50 " 2.95
White Lead, per lb.	.05 " .08
Custom Stairs (all designs)	35.00 " 40.00
Cove Mould, per foot	.33 " .43
Gable Ornaments	.80 " 1.60
Porch Columns (Solid)	1.34 " 5.12
Wall Board (all sizes) per M sq. ft.	
Guileint Papers, per roll	.35 " 1.50
Deadening Felt, per lb.	.31

Shingles, Beaded Ceiling, Partition, Flooring, Drop Siding, Shiplap, Bevel Siding, etc., at bargain prices.

You can still save a lot of money this year by sending now, for our new catalog. Guaranteed goods at guaranteed prices. Write us today, without fail.

THE HUBER BUILDERS' MATERIAL CO.

45-49 Vine St., Cincinnati, Ohio




Roll Roofing.
2-Ply, 65c
3-Ply, 85c



Cap Mould.
Per 100 Feet,
\$2.20



Plate Rail at Low
Prices.
See Catalog for
Complete List



Porch Newels,
31c to 72c.
Spindles, 1 1/4c.

Put These Windows In the Next Hog House You Build

They are made to use on any hog house, old or new. Easy to install. They will please the man you are building for. They will make a profit for you.

New Idea CHIEF SUNSHINE WINDOWS

Let the sunlight into the hog house where it's needed. Keep hogs healthy and strong.


Windows are made so you can shingle over flashing top and sides. Lower flashing comes over shingles. Perforated trough lets water run off, prevents leaking. Galvanized screen protects glass. Copper clips hold glass. No putty needed. The only modern scientific-



ally correct hog house windows on the market. Investigate. One hog house in a community with these windows brings more business for you. Write for prices.

CHIEF CUPOLAS




The best cupolas made. Rain, snow and bird proof. We have complete stock of cupolas of every size for every purpose. Strong, well made. The kind that please you because they are easy to handle and give satisfaction at low cost. They please your customers. Write today. Get descriptive circular and prices. Also full particulars of our silo roofs, silo chute and other galvanized products.



Address

SHRAUGER & JOHNSON
430 Johnson St., Atlantic, Iowa





Furniture Making Made Easy—

A FINE RECREATION FOR ALL HOME LOVERS

You know enough about tools and how they are used, to make some pretty nice things. You have the ability; these books give you the working drawings, designs, mill bills and instructions. Why not fit up a little shop for yourself and the boys where you can make some handcraft furniture and have real pleasure in doing it?

HAVE THE FUN OF FURNISHING YOUR OWN HOME

Your home can be made more comfortable and beautiful. Hand-made furniture is all the rage. It's so substantial; and your pride in it will be doubled because you made it yourself. There's no end to the work you can do if you follow our instructions. You simply can't make mistakes. You can make beautiful, sturdy pieces of furniture at a trifling cost.

READ THE TABLE OF CONTENTS OF THESE USEFUL BOOKS

VOLUME I

EQUIPMENT OF THE HOME SHOP

Value of Good Tools—The Bench—Rapid-Acting Vise—Outfit of Tools (Planes, Chisels, Saws, Gauge, Screwdriver, Try-Square, Bevel, Hammer, Brace, Bits, etc.)—Grindstone—Miter Box, etc.

USE AND CARE OF TOOLS

Uses of Try-Square—Working Face—Joint-Edge—Testing for Squareness, Uniform Width or Thickness, etc.—Marking Gauge—How to Gauge Lines—Saws (Crosscut, Rip)—Position in Sawing—How to Hold Saw—How to Hold Work—Accurate Sawing—Ripping—Good and Bad Sawing—Modern Plane and Its Parts—Smooth Plane—Jack Plane—Setting the Blade—Adjusting Cap and Plane Irons—Planing and Finishing Surfaces, Edges and Ends—Free End Planing—Chamfers—Chisels and Chiseling—Grinding Beveled-Edge Tools—Use of Grindstone—How to Sharpen Chisel on Whetstone—Grinding and Whetting—Sharpening Plane-Irons—How to Tell Whether a Tool is Sharp or Not—Use of Scraper.

MODELS FOR HOME WORKSHOP CONSTRUCTION

Furniture Designs—Itemized Stock Bills—Working Drawings—Simple Bookcase or Magazine Stand—Convenient Book-shelves—Six-Sided Tabouret—Eight-Sided Tabouret—A Book Rack—Three-Part Screen—Footstool—Library Table of Mission Design—Heavy Six-Sided Table—Drawing Board and T-Square—Folding Porch Chair—Porch Swing—Set of Porch Furniture—Arm Chair—How to Make a Steam Box—Settee—Slide Chair—Piano Bench—Mission Chair—Settle of Mission Design—Pierced Ornamentation—Tabouret and Settee of Pierced Ornamentation—Morris Chair—Simple Morris Chair Design—Leather Upholstered Arm Chair and Rocking Chair—Large Mission Rocker—Writing Desk—Bookcase with Paneled Glass Door—Linen Chest—India Stool—Weaving Stool—Seat of Rush Fiber—Hanging Clock of Mission Design—Hall Clock—Hall Clock of Mission Design—Hall Tree—Umbrella Stand for Hall—Plant Stand for Pedestal—Use of "Winding Stick"—Electric Light Pendant Fixture—Carpenter's Workbench—Workbench Vise—Cabinet-Maker's Bench.

VOLUME II

MANUAL TRAINING IN EDUCATION

HANDCRAFT FURNITURE MAKING

Ornamental Plant Stand—Hat Rack and Key Rack—How to Make a Necktie Rack—A Tea Pot Mat—Decorated Foot Stool—Foot Stool with Keyed Tenons—Leg Rest—Tabourets with Pierced Ornamentation—Stools with Pierced Ornamentation—Tabouret with Straight Legs—Telephone Table or Stand—Plant Stand—Simple Umbrella Stand—Enclosed Umbrella Stand, Ornamental—Coat and Hat Rack—Mirror Shelf—Hall Rack with Mirror—Umbrella Rack for Hall—How to Make a Fireless Cooker—Sewing Cabinet and Folding Table—A Strong Utility Chair—Dutch Chair with Rush Seat—A Sewing Room Rocker—Mission Rocker with Cobbler's Seat—Leather Upholstered Rocker—Big Morris Chair—Library Easy Chair—Mission Settle with Diagonal Back Pieces—Heavy Mission Settle—Straight Line Mission Settle—Davenport, Leather Upholstered—Piano Bench with Hinged Top—Piano Bench with Keyed Tenons—Kitchen or Side Table—General Utility Table—A Large Library Table—Library Table with Leather Top—Flat-Top Desk or Desk-Table—A Square Dining Table—A Serving Table—A Plate Rack—Magazine Stand with Cabinet Top—A Writing Desk—Craftsman Bed of Wood—How to Make a Chiffonier—Writing Desk of Plain Design—A Table Book Rack—A Porch Swing—Electric Table Light—Electric Chandelier—To Make a Book Trough—A Dictionary Stand—A Picture Frame with Shelf—Round Top Table—Mission Candlestick—Massive Arm Chair—Side Chair of Straight Line Design—Morris Chair—How to Make the Mission Rocker—Carved Book Rack for Table—Library Table with Book Shelves—Big Easy Rocker—Electric Drop Lights—Heavy Mission Library Table—Art Craft Bedstead—Wood Screen for Bedroom.

SUGGESTIONS FOR FURNITURE DESIGNING

Kitchen Furniture—Kitchen Table—Wood-Box—Cottage Chair—Cottage Serving Table—Chain Cabinet—Extension Table—Dressing Table—Round-Top Table—Table—Twin Beds—Mirror—Library or Den Furniture—Morris Chair—Foot or Leg Rest—Light Stand—Bookcase—Library Table—Settle—Chair—Sewing Table—Well-Furnished Hall—Settle—Umbrella Stand.

OTHER POPULAR HANDCRAFT WORK

Hammered Metal Work for the Home Shop—Stencilling—Stencilling with Flat Oil Paints—Single-Color Stencilling—Two-Color Stencilla—Modeled or Art Leather Work—How to Build a Canoe—Retrospective.

Complete Designs, Clear Drawings and Full Instructions

These books describe the article to be made and tell you how to do it in a simple, understandable way. They tell you how to lay out the work; how to work it; how to put it together; and how to finish it. Everything is complete and made still plainer by very clear drawings and illustrations.

Art Work, Tooled Leather, Hammered Brass and Copper


In addition to the largest assortment of beautifully-designed handcraft furniture ever put into book form, RADFORD'S MANUAL TRAINING books contain special departments devoted to the home arts, working with leather, brass and copper. The designs of the furniture and other articles shown throughout these books are original, serviceable and pleasing. The value of this guide for the home-craftsman is worth many, many times its price.


RADFORD'S MANUAL TRAINING in 2 Volumes (622 pages, size 8 by 9 inches), thoroughly indexed, Cloth Bound, printed on good heavy paper and thoroughly illustrated with drawings and full-page half-tone engravings, will be sent, prepaid, on receipt of check, money-order or currency.

Price, \$3.00 Per Set, Postpaid

Radford Architectural Co.

1827 Prairie Avenue :: CHICAGO, ILL.






Note Heavy Scratch Coat, Due Entirely to Stiffness of RIB LATH.

Better Stucco and Plaster

are assured by the use of RIB LATH. Plaster cannot streak or crack, as with wood lath. Improved method of manufacture provides a perfect clinch for the plaster. RIB LATH provides a most rigid surface so that plaster can be compacted against it without loosening surrounding plaster.



RIB LATH

Saves Labor and Material

The exceptional rigidity of RIB LATH permits wider spacing of studs, and in plastering effects a great saving in labor and material. Two coat work is ample with RIB LATH, where other laths require three. RIB LATH covers about 10% more area than other metal laths because of interlocking ribs along sides of sheets. Self-furring RIB LATH eliminates all furring strips in stucco work.

RIB LATH is furnished in four types and twelve weights. Also Detroit Diamond Lath, Steel Studs for Hollow Partitions and Steel Corner Beads.

VALUABLE RIB LATH HAND BOOK

Containing Details, Specifications, Tables, Illustrations, etc., FREE to those interested in building.



TRUSSED CONCRETE STEEL CO.

Dept. H. 44

YOUNGSTOWN, O.

Reinforcing, Hy-Rib and Lath, Steel Sash, Etc.




Residence of C. A. Mangold, Oak Cliff, Dallas, Tex.
Stucco on RIB LATH.

SYKES

Expanded Cup Lath

The Self-Furring Kind
with Anti-Rust (Oil)
Coating, Painted Black
or Galvanized




Inexpensive and perfect for remodeling and for all interior and exterior plastering.

For All Stucco Work

The cup feature of this lath allows it to be fastened direct to the sheathing without the use of furring strips. Both sides alike. Perfect keying principle. The use of this lath in stucco work reinforces the plaster, or over-coating better than any other lath made. Cannot buckle, sag or warp. Made in sheets 18 in. x 96 in. Twenty square yards to the bundle. Price extremely reasonable. Send for FREE SAMPLE, particulars and price.

SYKES METAL LATH & ROOFING CO.
506 Walnut Street NILES, OHIO



WE have issued Very Interesting Catalogues containing valuable information for the Architect, Carpenter and Builder regarding wood columns for exterior and interior use.

Catalogue "U. 40" for Exterior and Interior Columns.
Catalogue "U. 50" for Interior Columned Openings.
(Above will be sent FREE on request)

HARTMANN-SANDERS CO.

Exclusive Manufacturers of

Kolls
Lock
Joint



Patent
Stave
Column

Suitable for Pergolas, Porches or Interior Use.

Main Office and Factory
Elston and Webster Aves., Chicago, Ill.
Eastern Office: 1123 Broadway, New York City, N. Y.
Pacific Coast Branch, A. J. Koll Planing Mill Co.,
Los Angeles, Calif.


WHY TAKE A CHANCE

of having a defective wall from using a scrap wall tie in varying thickness as light as tin.

Ask your dealer the weight of a box containing 1000 ties and if the weight is below 50 pounds you are buying an inferior tie and entitled to rebate.


To be safe, specify the

WHALE BONE WALL TIE



and if your dealer cannot supply same, order direct from us and we will ship the same day as received, at price of \$2.50 per 1000, Pittsburgh, Pa.

ALLEGHENY STEEL BAND COMPANY
BELL PHONE: 718 Cedar North Side, PITTSBURGH, PA.



ROSS Iron Studding SOCKETS

The "100-Year" Post Supports for **Cement Floors and Cement Foundations**


**No Sills to Rot!
No Toenailing to Rust!**

For Corncribs, Granaries, Barns, Hoghouses, Sheds, Garages, etc. Simply tap Sockets into soft cement. Easy and convenient to use. More than save their cost in labor. Ross Sockets last. Good profits for you. We pay the Freight.

Write for
Free Booklet

G. M. ROSS & CO.

1844 Broad Street
GRINNELL, IOWA



OAK FLOORING

"AMERICA'S BEST FLOORING"

Builders and owners will find it a clinching argument to say "It's floored with OAK FLOORING." It is the biggest single feature to look for in any house or apartment building. It imparts an air of refinement and elegance. It is the modern flooring.

OAK FLOORING $\frac{1}{2}$ inch thickness by $1\frac{1}{4}$ inch or 2 inch faces can be laid over old floors in old homes or over cheap sub-floors at a very low cost. It is cheaper than carpets or pine flooring. When laid it has all the appearance of heavy flooring.

There is a solid satisfaction and lasting pleasure in the substantial and dignified appearance of OAK FLOORING.

Contractors and carpenters find it very profitable to lay $\frac{1}{2}$ inch stock over old floors in old homes during dull periods. A little canvassing is all that is necessary to secure jobs. A carpenter or handy man can lay OAK FLOORING successfully.

For durability, OAK is the best. OAK FLOORING laid thirty years ago, after very hard use, is still in good condition.

Write for Booklet

THE OAK FLOORING BUREAU, 890 Hammond Bldg., DETROIT, MICH.


METAL CEILING



See that Joint?

The Acme of perfect construction.
Don't nail or slip the joints. Lock them.
Full information in catalogue E.

S. KEIGHLEY METAL CEILING & MFG. CO.
PITTSBURGH, PA.




BOWER'S BARN VENTILATOR and CUPOLA

The exhaust capacity of the Bowers is far greater than that of any other cupola ventilator. The arrangement of storm lands, cones, etc., gives a direct escape for foul air without drafts. A steady upward "pull" means constant ventilation. Storm-proof and easily set in place on the roof.

The Bowers is made of 20 and 22 gauge Galvanized steel with steel braced corners and top. The weather vane is gold-leaved. Combines the best in good looks and utility at a very reasonable cost. Our catalog explains why Bowers' Ventilator and Cupolas really ventilate. Consult it before you buy. We can save you money on skylights, Cornices, Finials and all sheet metal goods. Write us.

F. M. Bowers & Sons 927 W. Wash. St. Indianapolis, Ind.



Double Hung Metal Window

WILLIS Fireproof Metal WINDOWS

Frames and sash of hollow metal, glazed with wired glass. In all the standard types. Tested and approved by the Underwriters' Laboratories, Inc.

Architects and Contractors

Get our Special Catalog on "Fireproof Windows and Doors." It has 48 pages of information on this subject. No Builder should be without it. Costs you only a postage stamp.

WILLIS MFG. CO.

Galesburg, Illinois

Mfgs. Skylights, Ventilators, etc.

DIAMOND HARD

MAPLE FLOORING

Thoroughly kiln-dried, side and end matched, hollow backed, bored for blind nailing, and STEEL POLISHED. Guaranteed to give best results under hard continuous wear.


Do not be satisfied with ordinary flooring. You can get **DIAMOND HARD MAPLE FLOORING**.

You'll receive full value in wearing service and permanent finish.

Write us. We'll Tell You More.

J. W. WELLS LUMBER CO.

Menominee, Michigan



ASHBY'S
Designs of Schools and Libraries

display a composition of utility, durability and good, pure architecture without any "gingerbread."

No buildings are too large or too small for our personal and prompt attention. We develop your own ideas into a practical set of plans and specifications which can be executed to the smallest details into a building that can be built within your means and to your entire satisfaction.

Ashby's "Designs of Schools and Libraries" will be sent to parties interested in the erection of a school building or library for which plans have not yet been procured.


G. W. ASHBY—ARCHITECT
512 Medinah Building
CHICAGO, ILL.



Ordinary cellar windows leave any building at the mercy of thieves and burglars. The Canton Coal Chute is positively burglar-proof



Canton Coal Chutes



prevent battered foundations, broken windows and sash, blackened walls and dirty lawns.

Always specify a **Canton** for your buildings. If you want to use the **best**—the most solidly built coal chute at a very fair price.

Booklet B-1 will give details. It also shows our complete line of Builders' Iron Work. All we need is your name and address.
Canton Foundry & Machine Co.
Canton, Ohio



In specifying varnish take this tip from the paint man

There's one varnish that beats them all, because it works easily, has a good body, covers well, dries in a hard, firm coat, gives a brilliant surface of deep lustre, is unaffected by moisture and water, does not wear or scratch white and is long wearing. You get it when you specify

Lowe Brothers
"Little Blue Flag"
VARNISHES

The offices of the Lowe Brothers Company were not refinished, but merely cleaned, after they were submerged with slime and water during the Dayton flood. The old varnish still looks fine.

Write for "Varnish and Varnishing." It's full of valuable varnish information.

The Lowe Brothers Co.

457 E. Third St., Dayton, Ohio

Boston Jersey City Chicago Kansas City Minneapolis
Lowe Brothers, Ltd., Toronto, Can.

See Sweet's Catalog
1914 edition
pages 1916-1917

Look for this
"Little Blue Flag"
—your guarantee of quality



HESS MEDICINE SANITARY LOCKER



The Recession Steel Medicine Cabinet

The Only Modern, Sanitary STEEL Medicine Cabinet

or locker, finished in snow-white, baked everlasting enamel, inside and out. Beautiful beveled mirror door. Nickel plate brass trimmings. Steel or glass shelves.

Costs Less Than Wood

Never warps, shrinks nor swells. Dust and vermin proof, easily cleaned. Should be in Every Bath Room. Four styles—four sizes. To recess in wall or to hang outside. Send for illustrated circular.

HESS, 920L Tacoma Bldg., CHICAGO

Makers of Steel Furnaces

Free Booklet

\$50 Bovee Economy Furnace \$50

SAVED BY BUYING A



At Manufacturers' Prices.

Has large combustion chamber.

Saves one-third of the fuel.

Has perfect Ventilating System.

Most perfect hot air plant sold.


Send pencil sketch of floor plan for our manufacturers' price and illustrated catalog. Address

BOVEE FURNACE WORKS

50 8th Street,

WATERLOO - IOWA

PLUMBING AND HEATING SUPPLIES AT WHOLESALE



When in the market for Plumbing and Heating Supplies and you wish to

SAVE 20 to 40 Per Cent

on every article, write for my free illustrated Catalog. The only house that sells first-class guaranteed goods at wholesale prices direct. Shipments are promptly made from a very complete stock.

Small orders are as carefully handled as large ones.

B. B. KAROL, 768-772 W. Harrison St., Chicago, Ill.

Start to Succeed NOW

Mail the Coupon



Forget the past. Better times are ahead. Start up out of the old ruts NOW. Mail the coupon. We want to tell you how you can learn Plan Reading, Estimating, Contracting, etc., IN YOUR OWN HOME. We furnish plans of buildings now being built. Never mind the cost—it's small. We want ambitious men now in the building line. Write today.

\$15.00 Outfit and All Blue Print Plans Free

CHICAGO TECHNICAL COLLEGE

1017 Lake View Building, Chicago, Ill.

CHICAGO TECHNICAL COLLEGE, 1017 Lake View Bldg., Chicago, Ill. Gentlemen: I have marked with a cross (X) the branch or branches interesting me.


☐ Architectural Draft'g ☐ Bldg. Superintendence
☐ Builders' Course ☐ Structural Drafting
☐ Estimating ☐ Structural Design
☐ Plan Reading ☐ Mechanical Drawing
☐ House Planning ☐ Machine Drafting
☐ General Contracting ☐ Machine Design

Name.....

Address.....

Town..... State.....

College or Home-Study Course.....



\$22.50 \$25.00

FOR THESE ELEGANT, MASSIVE, SELECTED OAK OR BIRCH, MAHOGANY FINISHED MANTELS. BEVELED MIRRORS, 18 X 36

Prices include our "Queen" Coal Grate with best quality enameled tile for facing and hearth. Mantels 82 inches high, 5 feet wide. Furnished with round or square columns, as shown in cuts.

Catalogue Free—Will send our 100 page catalogue, the finest ever issued, free, to carpenters, builders and those building a home.

HORNET MANTEL CO., 1147 Market St., St. Louis, Mo.




Hot Water Heating From the Fireplace

Illustration shows section of our Heating Coil which if placed in the old style fireplace will easily heat six times the amount of space without additional cost of fuel and affords the same healthful ventilation. Will suit any fireplace or mantel.

Write for descriptive circular.

Heitland Grate & Mantel Co.
No. 126½ N. Fifth St., Quincy, Ill.

YOU SAVE MONEY WHEN YOU BUY FROM US

No. 1240. In Plain Oak. Quartered Oak and Maple Mahogany. Price in Q. O., \$19.06



Every home you build should have one of these handsome mantels and fireplaces. These beautiful designs are rare bargains. If you bought them elsewhere you'd pay twice as much for them.

The wood in all our mantels is guaranteed to be thoroughly seasoned, free from blemishes and of a beautiful grain.

Fireplaces and mantels are in style. They are popular for every house. You can get high grade mantels from us at the wholesale price. Think of it. Every mantle warranted to be perfect in material, workmanship and finish.


Write now—today—for our big, handsome Mantel Catalog. It shows 82 styles of modern mantels—all at the lowest prices. Write for this free book immediately.

The Huber Builders Material Company

45-49 Vine Street
CINCINNATI, OHIO

Get Our **FREE** Catalog


No. 1295. White Enamel. Three Coats of White and Birch Mahogany. Price, T.C. of W., \$6.87



No. 1241. In Quartered Oak and Real Mahogany. High grade. Price in Q. O., \$23.12



No. 1198. In Quartered Oak and Real Mahogany. Price in Q. O., \$18.12



THE BEST COLUMNS

for Porch, Interior and Pergola use the **NICKERSON Patent DOUBLE LOCK JOINT** THEY CANNOT COME APART

We Specialize on Detail-work. "Vignola" is our Standard for proportions when Architect's details are not furnished.




Clinch your Trade by giving them the very best Columns. Ours have the best Construction and correct shape.

All kinds of interior trim to detail.

Write for Catalogue No. 4.

NICKERSON MFG. CO.
KNOXVILLE . . . TENNESSEE



IF You Want the Best Wood or Tile Mantels at the LOWEST PRICES

write for our 50-page illustrated catalogue, mailed free on application.

Special prices to contractors and builders.

MOORMANN & OTTEN, 615-617 Main Street CINCINNATI, OHIO

Building Material Exhibit

TO THE ARCHITECT:— TO THE BUILDER:—

The leading manufacturers in every line have spaces at this Building Material and Equipment Exhibit. Their catalogs and booklets are on file, and you can help yourself. Practical builders and estimators are on hand to give you information. The actual materials are on view, including practically everything required to complete a modern building from the foundation to the finial, inside and outside—from the cottage or bungalow to the five-million-dollar skyscraper.

We have spacious Committee Rooms for your use when in Chicago. These are equipped with telephones and you can have meetings here with contractors and others. The entire service of our organization is at your command, without expense to you.

Send us your Plans and Specifications at our expense, we will gladly get bids for you on any lines that you wish.

TO THE BUILDING MATERIAL MEN:—

\$89,150,200 in 1913

This huge sum of money was spent for the erection of buildings in the city of Chicago in the year 1913.

Would you not like to have had the individual attention of each man who paid the bills before the material for his building was finally selected?

Would you not like to have had the opportunity of telling him the advantages of your particular product?

Instead of rushing to the architect or owner at the last moment, when the plans are public property and all your competitors are doing the same thing at the same time, wouldn't you like to have had your product determined upon in the mind of the owner before the plans were even drawn?

Constant, sincere effort toward a logical result has made our reputation.


For information about building materials of all kinds or about exhibit space, write to

Building Material Exhibit (Inc.)

Jackson Blvd., Fifth Ave. and Sherman St., Chicago, Ill.

J. P. FORAKER, President
A. FRIEDMANN, Vice-President

Telephones:—Wabash 2020, 2021, 2022,
2023, 2024, 2025, 2026



Copyrighted by the L. Wolff Mfg. Co.

Silentflow

A Noiseless
Water
Closet

IN THE TOILET
adjoining the sick room
one of the distressing noises
can be eliminated by installing the
"Silentflow."

This closet was not put on the market
until it was proven perfect in construction,
design and workmanship.

**SPECIFY WOLFF H-7005
FOR RESIDENTIAL USE**

L. WOLFF MANUFACTURING COMPANY


Manufacturers of

Everything in the Plumbing Line

The only complete line made by any one firm.

General Offices, 601-627 W. Lake St. Showrooms: 111 No. Dearborn St., CHICAGO
Pottery: Trenton, N. J.

BRANCHES: Denver, Colo.; Omaha, Neb.; Minneapolis, Minn.; Dallas, Tex.; Rochester, N. Y.;
St. Louis, Mo.; Washington, D. C.; Cleveland, O.; Cincinnati, O.; Kansas City, Mo.;
San Francisco, Cal.



"Standard" Floor Hinge Improved Again


Our 1914 Model is Double-Acting on Ball-Bearings—Oil Checking Mechanism Perfect—Hinge Frame Stronger—Hinge Easier to Apply

We announce our New Model Double-Acting Checking Floor Hinge. It automatically closes the door without a slam, bringing the door to a stand-still at the center. Swings door slowly and checks at the center. In the New Model the entire weight of the door rests on hardened steel ball-bearings placed up in the top of the hinge away from slop and grit. There is no wear-out to this bearing. Checking mechanism has especially sealed cylinder filled with non-freezing glycerine and alcohol. Checking plunger cannot get out of adjustment. All working parts submerged in oil and cannot wear out. New 1914 Model has simple rectangular oil chamber making it easy for carpenters to fit doors for this Hinge.

New Hinge Frame is $\frac{1}{4}$ -inch heavier than former model. It is also extra ribbed. New design of frame gives much stronger bearing for wood screws, making a more solid attachment to the door.

Guarantee

We guarantee all "Standard" hinges to be made of first-class material by skilled workmen and to give good service and satisfaction. We conscientiously believe that this New Model Floor Hinge will last at least 10 years in ordinary usage without giving any trouble whatsoever.



GIVE THIS HINGE A TRIAL. Nearly all up-to-date architects, contractors and builders are recommending and using "Standard" Double-Acting Checking Floor Hinges for all double-acting doors in Residences, Churches, Hospitals, Schools, Banks, Theaters, Apartments, etc.

Write us today for complete detail specifications of this new 1914 Model Checking Floor Hinge

STANDARD MANUFACTURING CO.
SHELBY, OHIO

WHEN WRITING ADVERTISERS PLEASE MENTION THE AMERICAN CARPENTER AND BUILDER



Brick Houses AND HOW TO BUILD THEM

Containing 219 (8 x 11 inch) pages illustrated by over 300 designs and details of brick house construction, beside perspective views and floor plans of 82 brick houses with estimates of cost construction and miscellaneous data about the use of brick from its manufacture to its placing in the building, including ornamental brick and tile work, sewer construction, fireplaces, brick veneer construction, arches, cements and mortars, how to estimate the cost of brick construction, etc., etc. A valuable book for the home-builder as well as to the builder and brick-layer.

Your Copy is Ready to Mail

Simply send us your subscription at the regular rates and this book will be sent by return mail, **Free**, postage paid. Regular subscription \$2.00 per year.

American Carpenter and Builder
1827 Prairie Ave. CHICAGO, ILLINOIS



Don't eliminate ornate effects

—from your designs on account of weight and expense.

If you cannot use heavy stone or cast ornaments or statues in your designs, consider light weight, substantial, enduring and economical sheet metal work. You can secure the maximum of artistic merit, all the elegance and refinement of the best sculpture, with a minimum of cost.

Mullins Sheet Metal Ornaments

We have the skilled workmen and the modern equipment to satisfy your needs in this kind of work. We have, too, the essential experience, gained from a quarter of a century of notable achievement.

Write us for information concerning the particular kind of work which you require. We shall be pleased to give your needs our prompt attention.

THE W. H. MULLINS CO.
214 Franklin Street Salem, Ohio, U. S. A.



The Parrot says—

"Contractors! Equip your houses with the

**PARROTT
(Hot Water)
HEATER**

10 Gallons of water heated for one cent


Put a Parrott Heater in the basement, light the pilot light and all inconvenience is past. Opening any hot water faucet in the house automatically turns on the gas in the heater. The water is heated "on the run". In a few seconds it is rushing from the faucet.

Supply the Demand


for Hot Water Heaters. The Parrott gives the best service at the lowest price. Clean and convenient. All home owners now want a Parrott Heater. Take up practically no room. Capacity unlimited. Easy to install. Requires no attention. Positively supplies hot water for any purpose at any time.

Your Clients will want a Parrott. Learn more about the Parrott Heater from our literature. Money for you. Write for FREE CATALOG.

MICHIGAN GAS APPLIANCE CO.
JACKSON, MICHIGAN



WHEN WRITING ADVERTISERS PLEASE MENTION THE AMERICAN CARPENTER AND BUILDER



These Handbooks Will Help YOU

When a puzzling formula, an elusive table, or some other equally necessary piece of information slips out of your memory—then it is that one of these little encyclopedias demonstrates its worth. They are written by the well-known textbook writers of the International Correspondence Schools and are so thoroughly indexed that you can turn instantly to any rule, formula, or other information you need. Here is a brief table of the contents of one of them:

BUILDING TRADES: Arithmetic; Weights and Measures; Formulas; Mensuration; Geometrical Drawing; Structural Design; Loads on Structures; Strength of Materials; Masonry; Carpentry and Joinery; Roofing; Plastering; Plumbing; Plumbers' Tables; Heating and Ventilation; Gas and Gas Fitting; Estimating; Elements of Architectural Design; Proportions of the Greek and Roman Orders; Moldings, etc. The others are equally complete.

Special Offer: For a limited time we are selling the Handbooks shown here in the titles listed below, durably bound in silk cloth, containing an average of 375 pages and 175 illustrations, and regularly sold at \$1.25, **50c** at a special price for each handbook of only

International Textbook Company Box 910, SCRANTON, PA.

I enclose \$_____ for which please send me the books BEFORE which I have marked X.

- | | | |
|--|---|---|
| <input type="checkbox"/> Building Trades | <input type="checkbox"/> Bookkeeper's | <input type="checkbox"/> Poultryman's |
| <input type="checkbox"/> Concrete Engineer's | <input type="checkbox"/> Tel. & Tel. Engineer's | <input type="checkbox"/> Salesman's |
| <input type="checkbox"/> Plumbers & Fitters' | <input type="checkbox"/> Mariners' | <input type="checkbox"/> Farmer's |
| <input type="checkbox"/> Mechanics' | <input type="checkbox"/> Business Man's | <input type="checkbox"/> Window Trimmer's |
| <input type="checkbox"/> Electrical Engineer's | <input type="checkbox"/> Steam Engineer's | <input type="checkbox"/> Chemist's |
| <input type="checkbox"/> Advertiser's | <input type="checkbox"/> Automobile | <input type="checkbox"/> Civil Engineer's |
| <input type="checkbox"/> Steno. and Corr. | <input type="checkbox"/> Coal Miner's | <input type="checkbox"/> Cot'n Text. Worker's |
| | | <input type="checkbox"/> West. Air-Brake |

Name _____

Street and No. _____

City _____ State _____



Don't Miss This Opportunity

We Want One Carpenter or Builder in Every Community to Demonstrate, Take Orders for and Apply Our EDWARDS METAL SPANISH TILE ROOFING on a Liberal Commission.

Here is a chance to build up an independent, profitable business for yourself right at home. Many carpenters are now devoting their entire time to selling our metal roofing. Others have made big profits simply devoting part of their time to selling and laying our Metal Spanish Tile.

Edwards Metal Spanish Tile

Is being advertised in the leading magazines and is now known to thousands of home builders and owners everywhere. Wherever it has been used it has made a decided "hit" because it shows off to good advantage on the roof and has numerous points of superiority over any other style of roofing.

Architects are specifying Edwards Metal Spanish Tile, for they know it will do away with roofing "troubles." Builders like it because of the finished appearance it gives any house on which it is used.

Our Metal Tile are stamped out of the highest quality Worcester terne plate in exact imitation of the most expensive Terra Cotta Spanish Tile. They come either "dip" painted or heavily galvanized size 10 x 14 inches. Our patented interlocking side lock makes it possible to make a perfectly moisture-proof roof without soldering. Edwards Metal Spanish Tile afford the fireproof advantages of Terra Cotta Tile, but are much lighter in weight, cost but a trifle more than ordinary roofing and will last a lifetime.

WRITE US TO-DAY ABOUT YOUR TERRITORY. Our business is growing so rapidly that it is necessary to have an agent in every community. The territory is going fast. One day's delay may mean that some one else will be given your territory. DON'T DELAY. WRITE TO-DAY FOR OUR SPECIAL AGENTS' PROPOSITION.

The Edwards Manufacturing Co.

"THE SHEET METAL FOLKS"

401-417 Eggleston Ave.

CINCINNATI, OHIO


THE WORLD'S LARGEST METAL ROOFING, METAL SHINGLES AND METAL CEILING MANUFACTURERS

NEW YORK OFFICE, 81-83 Fulton St.

BRANCH OFFICE and Warehouse, 1625-27 Pacific Ave. Dallas, Texas



Note the construction of patented interlocking device, protecting nail heads from weather and providing perfectly for expansion and contraction of the metal.



Style "B"—Showing Method of Laying

PLACE YOURSELF ABOVE YOUR COMPETITOR

AND SELL "TITELOCK" THE BEST

METAL SHINGLES made. They are business-getters and money makers. FIRE, WATER AND LIGHTNING PROOF.

Write for Samples and Prices

MILWAUKEE CORRUGATING COMPANY

MILWAUKEE, WIS.

KANSAS CITY, MO.



THE GALE

BARN AND GRANARY VENTILATOR

For all your buildings

INEXPENSIVE, BEAUTIFUL, STRONG

Made of heavy galvanized iron. Screened inside. Storm-proof and bird-proof. Perfect ventilation guaranteed. All you have to do is to place ventilator on roof and nail fast.

Write for Illustrated Circular with Complete Prices.

Galesburg Sheet Metal Works, Galesburg, Illinois



A HOT AIR FURNACE

For Less Than \$50 Complete

For 5 and 8 Room Dwellings

An Unheard of Price and a most Remarkable and Indestructible Furnace.


No Pipes No Lost Heat

AMERICAN BELL AND FOUNDRY CO.

NORTHVILLE

MICH.

EASY and SURE Steps to Higher Wages and Larger Contracts



The man who climbs to success is the man who knows how to do things in the best modern way. A bigger share in the

BUILDING OPPORTUNITIES OF TODAY

is surely yours to claim! You can do it without technical training or hard study. To master every detail of your trade or business will be a pleasure instead of a labor. Your task if you will let us send you for five days' free examination absolutely at our own expense and risk, a set of

RADFORD'S CYCLOPEDIA OF CONSTRUCTION

Carpentry, Building and Architecture

* Practical Uplift to Complete Mastery of Modern Building Methods and Materials

Twelve Massive Vols.—5,000 pages, 3,000 illustrations. Up-to-date, practical, thorough. All in simple English, without higher mathematics. Latest materials and methods. The cream of practical experience of the world's best known builders and contractors. Every detail covered—Carpentry; Framing; Concrete Work; Masonry; Steel Construction; Fire and Waterproofing; Drafting and Design; Heating; Ventilating; Plumbing; Decorating; Contracting; Estimating Cost, etc., etc.

Sent Anywhere on Approval

ORDER ABSOLUTELY AT OUR RISK

No Obligation or Expense to You Unless You Keep the Books
No Follow-Up Agents to Bother You

WHAT OUR FREE TRIAL OFFER INCLUDES:

12 Massive Vols.—Bound in ½ Morocco leather, with full Persian library covers. A brand new work, costing over \$100,000 to compile and publish, built along new lines especially for the practical builder or contractor. Without magazine, \$1.00 less.

FREE Radford's Portfolio of \$30,000 Prize Building Plans—Over 300 designs of houses, bungalows, outbuildings, apartments, churches, etc. Ranging in cost to suit any purse.

FREE Complete Set of Guaranteed Working Blue-Prints and Specifications for any house design selected from Portfolio—Ordinarily costing \$75 to \$100. We will also include One Full Year's Subscription to the "American Carpenter and Builder," the world's greatest building paper, without extra cost to you.

If you are a Carpenter or Builder, you can do all the ordinary work of the Construction Engineer or Designer without any deep mathematical calculations, thus insuring your title to better recognition, wider responsibilities and higher wages.

If you are a Contractor, your clients will appreciate dealing with a man who is able to give them the latest practical suggestions, and who has back of him the experience and resources of one of the largest architectural firms in the world.

12 MASSIVE VOLUMES

**SENT ON APPROVAL
FOR FIVE DAYS' FREE EXAMINATION**

No Obligation. No Expense. No Risk to You
We Take all the Risk

READ THE COUPON

ON NEXT PAGE

RADFORD ARCHITECTURAL COMPANY,

1827 Prairie Ave., Chicago, Ill.

SIGN AND MAIL COUPON TO-DAY

WHEN WRITING ADVERTISERS PLEASE MENTION THE AMERICAN CARPENTER AND BUILDER

He Waited Too Long



"If I only had this set of books twenty or thirty years ago, they might have changed my whole life. The knowledge in the big CYCLOPEDIA would have enabled me to increase my earning power, to take on big work, paying big money, and possibly have helped me to make a fortune in the building business."

Hundreds of letters like the above have come to us, breathing between the lines the same pathetic story of regret—showing how hard it is for the untrained man to really get ahead in life. **The opportunity is yours NOW**, and the way is easy. **Don't wait too long. Don't wait at all.** Read the terms of our **NO-RISK, Guarantee Offer** over again, and **sign and mail coupon today.** You risk absolutely nothing, and you will reap the benefit ever afterward.

VERY BRIEF LIST OF CONTENTS

To realize their tremendous scope, you must see the books—you can get the books for five days' examination without cost to you.

A.C.B.
8-14.

**Radford
Architectural
Company**
1827 Prairie Ave.,
Chicago

Please send me, express prepaid, your 12-volume Cyclopaedia of Construction, for five days' free examination, with privilege of return at your expense. I enclose \$1.00 deposit, which you agree to return if I decide not to keep the books after examination. If I keep the books, I will pay \$2.00 a month until the special price, \$23.80 is paid, otherwise I will notify you within five days after receipt of books. Your offer also includes Radford's Portfolio of Plans (over 300 designs), and one full year's subscription to the American Carpenter and Builder. You also agree to furnish set of Blue Prints and Specifications, if ordered within 2 months after acceptance of books.

Name.....

Town.....State.....

Street.....

Carpentry.
House Framing
Uses of Steel Square
Rafter Cuts
Strength of Timber
Roof Trusses
Stair Building
Drafting and Design
Working Drawings
How to Read Plans
Blue-Printing
Architectural Forms
Architectural Lettering
Construction Contracts
Forms of Contract
Architect and Owner

Specification Writing
Inspection of Work
Cost Estimating
How to Bid with Safety
Timekeeping, Superintendence
Cement Construction
Origin of Portland Cement
Advantages of Concrete
Common and Hydraulic Lime
Cements (Portland, Natural, etc.)
Proportions for Mixing
Aggregates (Sand Gravel, Crushed Stone, etc.)
Mixing by Hand and Machine
Depositing Concrete
Concrete Troubles
Waterproofing Concrete
Concrete Blocks and Brick
Cement Mortar
Stucco and Plaster
Concreting Machinery and Tools
Concrete Mixers

Block Machines
Number of Blocks Required
Brick and Tile Machines
Forms (Wood, Metal)
Cement Houses
Foundations
Floors and Walls
Roofs and Chimneys
Fireproof Construction
Concrete Sidewalks
Ornamental Use of Concrete
Surface Finishes
Art Tile and Mosaics
Terrazzo Floors
Concrete on the Farm
Fence-Posts and Gate-Posts
Sewer and Drain Pipe
Concrete Silos
Reinforced Concrete
Principles of Design
Reinforcing Materials and Systems
Industrial Buildings
Concrete Piles
Sewer and Tunnel Work
Bridges and Viaducts
Culverts, Reservoirs


Estimating Concrete Work
Standard Specifications
Masonry Construction
Building Stone
Brick and Brickwork
Mortar for Masonry
Bonds and Joints
Steel Construction
Steel Shapes
Use of Handbook Tables
Allowable Stresses
Rivets, Tie-Rods
Columns, Beams and Girders
Floor and Roof Arches
Roof Trusses and Coverings
Mill Building Construction
Steel Bridges
Heating, Ventilation
Furnaces and Pipes
Plumbing
Sewers and Drains
Electric Wiring
Painting
Paperhanging
Furniture Making
Useful Tables, Rules, etc.

**12 Big Volumes—Free Premiums—No Risk
SENT FOR ONLY \$1.00**

RADFORD ARCHITECTURAL CO.
1827 Prairie Ave., CHICAGO, ILL.

PIN A DOLLAR BILL TO THIS COUPON AND MAIL IT AT OUR RISK TODAY

Don't Waste Time and Labor with Hand Pumps



The Fairbanks-Morse Eclipse Engine and Trench Pump will raise 3,000 gallons of water an hour 18 to 20 feet on about a pint of gasoline.

Cheaper than hand labor—and quicker. A little gasoline in the fuel tank—some water in the cooling-hopper and the engine is ready to do the work of several good men.


Let us tell you more about it.

Ask for Catalog 1409-55A.

Fairbanks, Morse & Co.

NEW YORK CHICAGO SAN FRANCISCO

THE FOOS



Direct Connected Contractor's Pump
Described in Bulletin 47

ENGINES for construction work, contractors' service and industrial purposes $1\frac{1}{2}$ to 325 H. P. Portable electric plants, pumping rigs and other special outfits for all kinds of work. This factory builds high-grade equipment for any purpose requiring an engine, and carries a stock of contractors' outfits for quick shipment. Its sales engineers co-operate with contractors on municipal work (waterworks or electrical service) and are capable of handling the specifications on any job up to 325 H. P.

THE FOOS GAS ENGINE CO.

704 Monroe St.

Springfield, Ohio

A Moderate-Priced Steel Structural Material for Every Kind and Size of Building.

For the bungalow or the skyscraper, for the garage or the apartment building—for the residence or the hospital. Build with Berger's Metal Lumber joists and make your Buildings strong and fireproof at moderate cost.

Berger's Metal Lumber

Pressed steel members are so constructed that they will withstand great loads under high temperature when the same sizes of rolled steel members will collapse of their own weight. They economize material, time, money and space.

Our New Metal Lumber Catalogue tells all about it. Write for it today.

The Berger Mfg. Co., Canton, O.

For the best service address nearest branch

Chicago, New York, Boston, Philadelphia, St. Louis, Minneapolis, San Francisco, Cincinnati.

"Opportunities"

Have you anything to Sell, Barter or Exchange,
Want Help, Agents, or a Situation? Use our

Classified Department

RATES 5 CENTS A WORD. CASH WITH ORDER

No Display Type Allowed in Classified Advertisements

Patents

O. L. PARKER, PATENT ATTORNEY. Formerly member Examining Corps, U. S. Patent Office. 920 G. St., Washington, D. C. Pamphlet of instructions sent upon request.

PATENTS THAT PROTECT AND PAY—Books free. Highest references; best results. Send sketch or model for free search. Watson E. Coleman, Patent Lawyer, 622 F St., Washington, D. C.

Instruction

DRAFTSMEN'S, BUILDERS' AND FOREMEN'S COURSES—Day, evenings or by mail. MAACK'S ACADEMY OF ARCHITECTURE, 1742 Chouteau Ave., St. Louis, Mo.

YOU CAN BUILD ANYTHING IN ARTIFICIAL MARBLE, concrete or plaster from my instructions, simplified method of FLEXIBLE MOULD MAKING for ornamental casting of garden furniture, statuary, etc. Sanitary flooring material furnished at wholesale price. Joseph Roth, Office, 45 Frost St., Brooklyn, N. Y.

Wanted

AGENTS WANTED for house lighting machines, supplying gas for small country homes as well as large. Simple and economical. Guaranteed. A live proposition. Write for terms. THE ALEXANDER F. MILBURN CO., Baltimore, Md.

For Sale

FOR SALE—Well equipped contracting business and old stand. Write for prices and terms. Must sell in 30 days. D. L. Hamilton, Colfax, Ill.

Miscellaneous


CABINET MANTELS direct to builder, \$3.00 to \$40.00. AMERICAN MANTEL TILE & GRATE CO., Hamilton, Ohio.

FREE—\$1.00 Certificate and 4-inch rule. See Ad Page 143. GAGE TOOL CO., Vineland, N. J.

AGENTS—500 per cent profit; free sample. Our new gold and silver sign letters for store fronts and office windows. Easily applied. Big demand everywhere. Write today for liberal offer to agents. METALLIC LETTER CO., 447 N. Clark, Chicago.

THE UNIVERSAL PITCH GAUGE is the simplest and most complete tool ever devised for roof-framing. With this Gauge a beginner—even a boy—can mark more framing in less time than the best expert can WITHOUT it. Gives 22 lengths, bevels, etc., for 100 pitches. Any pitch in five minutes. Hundreds of irregular hip rafters. Octagon hips and jacks, etc. Two Gauges, making a perfect Stair and Brace Gauge. Prepaid for \$1.00. Money back, if returned. JOHN PARKHILL, Rochester, Minn.

Over 1,000,000



In Daily Use

Here's What People Want **The Axtell**

A perfectly tight All-Metal Weather Strip for bottom of doors and swinging windows. Saves sill from wearing and can be put on any door in 5 minutes at 200% profit. Sells at sight wherever shown. Our prices will interest you. Write us.

E. I. Church & Co.
West Hanover, Massachusetts

WHEN WRITING ADVERTISERS PLEASE MENTION THE AMERICAN CARPENTER AND BUILDER



Pullman Roof Ventilators

are the best exhaust medium on the market. Provide for removing the foul air by using Pullman Ventilators on the roof. Write for booklet. Ask us to solve your Ventilating problems. The Pullman System means Natural Ventilation.

Special System for Moving Picture Theatres.

Pullman Automatic Ventilator
Mfg. Co., 21 York St., York, Pa.

THE IDEAL WAY TO BUILD

Use a Van Guilder Hollow Wall Concrete Machine

It builds double monolithic walls tied together and steel reinforced. Continuous air space, dry, warm, sanitary, fire proof, age proof, repair proof. Better than brick, cheaper than wood.

Large illustrated Catalogue and Book "How to Build" free.

VAN GUILDER HOLLOW WALL CO.

720 Chamber of Commerce Building ROCHESTER, N. Y.

Triumph Light

EVERYBODY WANTS BETTER LIGHT. HERE IT IS

This new 100 to 700 candle power light turns up and down like gas. One-third cost of electricity, gas or kerosene. For home, church or store. Anyone can operate. Perfection guaranteed or money back. Write for catalog. (A. C. B.) Dept. 20. Agents Wanted. **BRILLIANT GAS LAMP COMPANY** 1009 S. Wabash Av., Chicago, Illinois

BYERS

HOISTING ENGINES

Specially Designed for Builders

Write for Catalogue No. 20

The John F. Byers Machine Co. Ravenna, O.

"As Near Rust Proof as Metal Can Be Made—"

GILBERT & BENNETT

PEARL

WIRE CLOTH

Insist upon the genuine. Look for the 2 Copper Wires in the Selvage.

THE GILBERT & BENNETT MFG. CO.

Chicago; New York; Georgetown, Conn.; Kansas City



2 Dollars a Month


Buys a Standard Typewriter. Your choice of late style Visibles, etc. Prices lower than other cash prices. Perfect machines only. Guaranteed for one year. 5 days Free Trial. Do not buy a machine until you have my bargain prices and terms. Write Today

Harry A. Smith

702 R.—231 N. Fifth Ave., Chicago, Ill.



DON'T ORDER
Lignine (Wood) Carvings
UNBREAKABLE—INVESTIGATE
 Send postal for free sample and catalog
 One cent investment, saves dollars.
 Let us prove this.
ORNAMENTAL PRODUCTS COMPANY
 Fourteenth Avenue, Detroit, Mich.



BUY YOUR CANVAS WORKING GLOVES
DIRECT AND SAVE MONEY

One dozen pairs like illustration only \$2.60. Post paid anywhere in U. S. Sample pair 25 cents silver. Every pair guaranteed to wear or your money back if you want it.

— Agents Wanted —

GEISINGER THE GLOVE MAN
 Dept. B. :: :: LEBANON, PA.


THE ZIMMERMAN IRON BASE

Is the ONLY BASE having a CENTER BEARING.

It carries the required weight without allowing the corner supports to sink into the floor and prevents the base of column and floor from rotting.

See "SWEET'S" page 958.

S. CHENEY & SON, MANLIUS, N. Y.



Bottom View Showing Center Bearing



The Eau Claire Chalk Line Reel

Always ready; holds chalk and line together; uses solid chalk, no powder. We furnish no line. Sent to any address prepaid, 75c. We handle Eau Claire chalk. Agents wanted.

THE MILLER-LAUT CO., 916 Monomonic St., Eau Claire, Wis.



\$4 Per Month!
FREE TRIAL!

Genuine Oliver Visible Typewriter. We sell direct; save you agents' commissions and expenses. Ship on approval. \$4 per month if you keep it. Send for free booklet. See how you save \$41.50 on high-grade machine.

TYPEWRITERS DISTRIBUTING SYNDICATE
 166-T-75 N. Michigan Boulevard, Chicago


ONLY SELF-SETTING PLANE

Sent on trial as per circular

Our \$1.00 certificate if you mention this paper.

GAGE TOOL CO.

Vineland, N. J.



A UNIQUE TIME SAVER.

The Jackson Aluminum Line Level is a mighty small device; it brings about a tremendous saving of both time and labor. It takes the place of the old-fashioned sixteen foot straight edge, yet it can be carried in your vest pocket.

No contractor, builder, carpenter, mason, bricklayer, architect or plasterer, etc. can afford to be without one. Just stretch your line and hang the level on it—it's positively accurate. The complete outfit is put up in a neat leatherette case and consists of the level with a 40-ft. line also a spring clamp for attaching the level to a steel square or pocket rule, thereby serving as a plumb rule or bench level.

Ask your hardware dealer or send \$1.00 for the Level outfit complete post paid. Send for our Catalogue of Tools.

JOS. WOODWELL CO., Sole Agents
 201-203 Wood St., Pittsburgh, Pa.

A SHINGLING HATCHET
WITH POSITIVE GAUGE
CARPENTERS and BUILDERS
 Here is a hatchet you can do some fast shingling with—No. 144 (oval head, 169 points.) Gauge is positive—it cannot slip. Clamps on with screw, gauge is readily changed. This hatchet is also made with flat head No. 44, 81 points, milled. Price of either is \$1.75 prepaid. We make a complete line—and the best—of Lathing Hatchets, from 64 to 225 points. Prices \$1.40 to \$1.75. You get your full money value in a Sayre Shingling or Lathing Hatchet. You can be positive of that. Find them at your dealers or send direct.

L. A. SAYRE & SON
 8 Oliver St. -1- Newark, N. J.

CYPRESS
 (OF COURSE)
BECAUSE IT'S "THE WOOD ETERNAL"
& LASTS & LASTS & LASTS & LASTS

EVERYTHING in Guaranteed Plumbing and Heating Supplies at wholesale. Our \$200,000 establishment behind our Guarantee. Send for complete CATALOG 41.

J. HARDIN CO., 30 years at 4543-53 Cottage Grove Ave., CHICAGO


ROOFING SLATE
OF QUALITY
MINERS The AULD & CONGER CO. MANUFACTURERS
ESTABLISHED DEPT. B. 1870
CLEVELAND, OHIO.

SLATE WE HAVE WHAT YOU WANT
In Roofing Slate. Slate Blackboards
Structural and Plumbers' Slate
SATISFACTION GUARANTEED IN QUALITY AND PRICE
ASK FOR DELIVERED PRICES
J. K. HOWER, Station, C., Slatington, Pa.
R. J. KICHLIN, Sales Agent



Send us two or more names of persons who are interested in or want to buy Hot Water Heating Plants and we will send you this scale. Back inches are divided into 6, 10, 12, 20, and 40 parts. Also free catalog on request. Mention this paper.

Andrews Heating Co., 1431 Heating Bldg. Minneapolis, Minn.



Think what 5-ply really means!

Think of a wall board with strength that is more than ordinary; that is more than ordinarily moisture-proof and weather-proof; whose quality, durability and satisfactory service have been convincingly proved in hundreds of different ways by thousands of actual users. There's only one such wall board that you could possibly

think of—

UTILITY

the only 5-ply wall board

Five, high-grade, fibre-board layers are solidly welded together with four layers of asphalt, coated on the outside with a special moisture-proofing. In ware-

houses and factories, offices and hotels, garages and display rooms, **UTILITY** meets every requirement perfectly. Its limitless possibilities for home decoration form only one phase of its usefulness.

Samples and Book Sent to You

Your name and address on a post card will bring tangible proof to you—specimen sheets and the **UTILITY** Book. Be sure you write today—**NOW**—before you forget.

THE HEPPE'S CO.

*Manufacturers also of Flex-A-Tile Asphalt Shingles,
Asphalt Paint and Asphalt Roofing in Any Finish.*

4503 Fillmore Street

CHICAGO, ILLINOIS

INDEX TO ADVERTISEMENTS, AUGUST, 1914

	Page		Page		Page
Allegheny Steel Band Co.	30	Foster Sheet Metal Works	115	Northwestern Expanded Metal Co.	113
Aloe Co., A. S.	25	Fox Machine Co.	16	Northwestern Steel & Iron Co.	107
Alpha Portland Cement Co.	147	Fox Supply Co.	4	Novo Engine Co.	97
American Bell & Foundry Co.	138	Gage Tool Co.	142-143	Oak Flooring Bureau	131
American Cement Machine Co.	121	Galesburg Sheet Metal Works	115-138	Ohio Tool Co.	20
American Elevator Co.	8	Galloway Co., Wm.	126	Ornamental Products Co.	143
American Floor Surfacing Machine Co.	4	Geier & Blum	24	Orr & Lockett Co.	2
American Level & Grade Finder Co.	22	Geisinger & Gloveman	143	Oshkosh Mfg. Co.	3
American Mantel Tile & Grate Co.	142	Gem City Acetylene Generator Co.	127		
American Pulley Co.	31	Genuine Bangor Slate Co.	115	Parker, C. L.	142
American Saw Mill Machinery Co.	18	Gilbert & Bennett Mfg. Co.	142	Parkhill, John	142
American Sheet & Tin Plate Co.	116	Goodell Mfg. Co.	29	Parks Ball Bearing Machine Co.	18
American Steel Scaffold Co.	28	Goodell Pratt Co.	23	Pearson Mfg. Co.	32
Andrews Heating Co.	143	Gordon VanTine Co.	87	Pennsylvania Saw Co.	27
Archer Iron Works	10	Grand Rapids Hardware Co.	18	Phoenix Sliding Blind Co.	8
Arkansas Soft Pine Mfrs. Assn.	101	Hall Holmes Mfg. Co.	13	Plastergon Wallboard Co.	109
Ashby, Geo. W.	132	Hamilton, D. L.	142	Prentiss Vise Co.	20
Asphalt Ready Roofing Co.	111	Hardin Co., John	143	Progressive Mfg. Co.	26
Atlantic Engine Co.	20	Harley Davidson Motor Co.	102	Pullman Automatic Ventilator Mfg. Co.	142
Atlas Engineering Co.	13	Hartmann Sanders Co.	130	Pullman Metal Weather Strip Co.	106
Auld & Conger Co.	143	Haynes Automobile Co.	103		
Automatic Sash Holder Mfg. Co.	8	Hawthorne Sales Corp.	22	Queen Cupola Mfg. Co.	127
Automatic Sealing Vault Co.	106	Heitland Grate & Mantel Co.	134		
		Henderson-Traylor Mfg. Co.	22	Radford Architectural Co.	12-129-139-140
Bangor Slate Mining Co.	115	Heppes Co.	114-144	Rehm Hardware Co.	29
Barnes Co., Walter F.	123	Hess Warming & Ventilating Co.	125-133	Reynolds Asphalt Shingle Co., H. M.	113
Barnes Co., W. F. & Jno.	18	Hewitt-Lea-Funk Co.	95	Richards Shingling Bracket Co.	27
Barnett Co., Jos. A. C.	6	Holland Furnace Co.	125	Richards Wilcox Mfg. Co.	33
Bates & Edmonds Motor Co.	123	Honeywell Heating & Specialty Co.	124	Roberts Mfg. Co.	126
Beckmann Co., The L.	25	Hornet Mantel Co.	134	Robinson Cabinet Mfg. Co.	117
Berger Mfg. Co.	119-141	House Movers Supply Co.	25	Ross & Co., G. M.	131
Bertelsen Adjustable Grille Co.	127	Howar, J. K.	143	Roth, Joseph	142
Bird & Son	110	Huber Builders Material Co.	128-134		
Bishop & Co., Geo. H.	27	Hussey & Co., C. G.	32	Samson Cordage Works	30
Blystone Mfg. Co.	10	Huther Bros. Saw Mfg. Co.	24	Sand & Sons, J.	33
Bommer Bros.	36			Sargent & Co.	34
Bostwick Steel Lath Co.	117	International Correspondence Schools	137	Sasgen Derrick Co.	7
Bovee Furnace Works	133	Irwin Auger Bit Co.	120	Sayre & Son, L. A.	143
Bowers & Sons, F. M.	131	Ives Co., The H. B.	117	Schlueter, M. L.	5
Boyle Co., John	122			Schrauger & Johnson	128
Bradt Publishing Co.	128	Jaeger Machine Co.	10	Sedgwick Machine Works	8
Bragstad Concrete Machinery Co.	13	James Mfg. Co.	126	Shapleigh Hardware Co.	23
Bridgeport Wood Finishing Co.	90	Jennings & Co., C. E.	6	Sharon Hardware Mfg. Co.	30
Brilliant Gas Lamp Co.	142	Johns-Manville Co., H. W.	94-108	Shelby Spring Hinge Co.	22
Buck Bros. Works Co.	15	Johnson, E. J.	26	Sheldon Slate Co., F. C.	115
Buffalo Wire Works Co.	31			Sherman Mfg. Co., H. B.	23
Building Material Exhibit	135	Karol, B. B.	133	Shultz All Steel Corner Post Co.	33
Byers Machine Co., John F.	142	Kaustine Co.	92	Sidney Elevator Mfg. Co.	8
		Keasbey & Mattison Co.	111	Sidney Tool Co.	17
Cabot, Samuel	36	Kees Mfg. Co., F. D.	27	Simmons Hardware Co.	121
Caldwell Mfg. Co.	20	Keighley Metal Ceiling Co., S.	131	Simonds Mfg. Co.	34
Campbell Mfg. Co.	102	Keystone Grinder & Mfg. Co.	121	Sioux City Engine & Machinery Co.	12
Canton Foundry & Machine Co.	133	Kissel Motor Car Co.	104	Slatington Slate Co.	115
Canton Metal Ceiling Co.	118	Klauer Mfg. Co.	118	Smith, Harry A.	142
Carborundum Co.	28	Knickerbocker Co.	14	Smith & Hemenway Co.	23
Cement Tile Machinery Co.	12-13	Kolesch & Co.	25	Southern Cypress Mfrs. Assn.	143
Century Cement Machine Co.	105			Southington Hardware Co.	121
Ceresit Waterproofing Co.	100	Landscape Garden Co.	123	Sneidel, J. G.	8
C. H. & E. Mfg. Co.	21	Lowie Bros. Co.	133	Standard Mfg. Co.	136
Champion Safety Lock Co.	5	Lufkin Rule Co.	20	Standard Paint Co.	5
Chappell Co., Wayvell.	4			Standard Scale & Supply Co.	11
Chelsea Elevator Co.	8	Maacks Academy of Architecture	142	Standard Screen Co.	15
Cheney & Son, S.	143	Mack & Co.	24	Standard Stained Shingle Co.	111
Chicago Grille Works	127	Mack Iron & Wire Works	31	Stanley Rule & Level Co.	32
Chicago Machinery Exchange	21	Majestic Co.	125	Stanley Works, The	121
Chicago Millwork Supply Co.	117	Mastic Wall Board Rfg. Mfg. Co.	146	Starrett & Co., L. S.	26
Chicago Spring Butt Co.	36	Metallic Batten Co.	36	Storm Mfg. Co.	8
Chicago Technical College	133	Metallic Sign Letter Co.	142	Swan Co., Jas.	22
Chief Draftsman	127	Michigan Engine Valve Co.	107	Swarts, H. D.	12
Church & Co., E. I.	142	Michigan Gas Appliance Co.	137	Sykes Metal Lath & Roofing Co.	130
Cincinnati Mfg. Co.	29	Midland Terra Cotta Co.	88	Syracuse Twist Drill Co.	30
Cincinnati Tool Co.	4	Milburn Co., Alexander	142		
Cleveland Window Glass & Door Co.	96	Miles Mfg. Co.	14	Taylor Mfg. Co., Jas. L.	6
Coleman, Watson E.	142	Miller-Laut Co.	143	Triple A Machine Co.	7
Colgan Machinery Co.	16	Miller Lock Co.	28	Trussed Concrete Steel Co.	130
Columbia Iron & Wire Works Co.	32	Miller Mfg. Co., A. W.	20	Typewriters Distributing Co.	143
Cook & Co., H. O.	5	Millers Falls Co.	24		
Corbin, P. & F.	93	Milwaukee Corrugating Co.	128	United Electric Co.	28
Cortright Metal Roofing Co.	112	Miotke, Jos.	6	Van Doren Mfg. Co.	33
Crescent Machine Co.	19	Moeschl-Edwards Corrugating Co.	113	Van Guilder Hollow Wall Co.	142
		Moorman & Otten Co.	134		
Dahl Mfg. Co.	16	Morrill, Chas.	36	Wagner Mfg. Co.	119
Deal-Rice Lumber Co.	105	Mullins Co., The W. H.	137	Warner Elevator Mfg. Co.	8
Decatur Coffin Co.	16	Murphy Varnish Co.	89	Warren Knight Co.	25
Detroit Show Case Co.	22	Myers & Bros., F. E.	32	Waterloo Cement Machinery Corp.	9
Didrikson, H. P.	5			Waterloo Register Co.	124
Diston & Sons Co., Henry	30	National Kellastone Co.	122	Weber Mfg. Co.	7
Dixon Crucible Co., Jos.	7	National Lead Co.	127	Webster Cement Co., W. F.	123
Dow Wire & Iron Works	31	National Mfg. Co.	148	Wells Lumber Co., J. W.	131
Dunn & Co., W. E.	15	National Sheet Metal Roofing Co.	99	White Co., David	24
		Nicholls Mfg. Co.	4	White Co., L. & I. J.	29
East Bangor Consolidated Slate Co.	20	Nickerson Mfg. Co.	134	Wilev Hardware Mfg. Co.	119
Edwards Mfg. Co.	138	North American Construction Co.	109	Williamson Heater Co.	91
Elite Mfg. Co.	29	North Bros. Mfg. Co.	15	Willis Mfg. Co.	131
Ellis Engine Co.	123	Northern Hemlock & Hardwood Mfrs. Assn.	127	Witte Iron Works Co.	123
Eureka Machine Co.	107	Northfield Iron Co.	14	Wolff Mfg. Co., L.	136
		Northwestern Compo-Board Co.	109	Woodwell Co., Jos.	143
Fairbanks, Morse & Co.	141				
Flintkote Mfg. Co.	98			York Automatic Dumb Waiter Co.	8
Foos Gas Engine Co.	141				

NOTICE TO ADVERTISERS


Forms for the September number of the American Carpenter and Builder will close promptly on August 20. New Copy, changes and orders for omissions of advertisements must reach our business office, 1827 Prairie Ave., Chicago, not later than the above date. If new copy is not received by the 20th of the month preceding date of publication the publishers reserve the right to repeat last advertisement on all unexpired contracts.

AMERICAN CARPENTER & BUILDER CO.

Built by
John J.
Randall Co.
Real Estate
and Builders,
Freeport,
L. I.,
New York



Bishopric
Stucco
or Plaster
Board
Used on this
Building



Bishopric Stucco or Plaster Board Nailed to
Studding and Stucco Applied to Stucco Board

Mr. Builder: Investigate the merits of Bishopric Stucco or Plaster Board. You cannot help but be convinced of the simplicity, economy and practicability of Bishopric Stucco or Plaster Board. Note carefully the application of Stucco on Bishopric Stucco or Plaster Board in circular illustration. Then study the diagram below and you will begin to really appreciate the great superiority of Bishopric Stucco or Plaster Board.

Bishopric Stucco or Plaster Board makes plaster and cement walls *permanent*—they can't crack, crumble or disintegrate when this time-defying stucco board is used. For five long years we have tested Bishopric Stucco or Plaster Board. *Every test* that a score of building experts know has been



"Dampness Can't Penetrate"


the slightest hesitation or fear of endangering your reputation. We guarantee Bishopric Stucco or Plaster Board to be as represented.

Don't delay—write today for free samples and free handsome illustrated book, just out, "Durable Homes by the Bishopric System." Contains *latest* information on stucco work. Every builder should have a copy. Get yours *now*.

used upon it and it has *always* "stood up"—*always* made good. Its recent introduction and service already rendered have won it hundreds of friends. It will win you, once you investigate and know its many merit points over other backgrounds.

You can recommend and use Bishopric Stucco or Plaster Board without

THE MASTIC WALL BOARD AND ROOFING COMPANY, 530 Este Ave., Cincinnati, Ohio
CENTRAL DOOR AND LUMBER CO., Portland, Ore., Licensed Manufacturers and Distributors for Pacific Slope



STUCCO FINISH →

NOTE THE UNDER-CUT—
THIS IS THE KEY THAT MAKES STUCCO STICK

Day and

Night

Every Hour

our staff of chemists inspect ALPHA Portland Cement throughout each stage of its manufacture to see that the raw materials are proportioned exactly right; to be sure that the burning is thorough; that the grinding is finer than required by standard specifications; that the finished product is as good Portland Cement as can be made. Then the cement is stored for proper seasoning. We have facilities for storing 2,000,000 barrels of ALPHA. Not a bag of cement is shipped that is not properly seasoned and that we do not guarantee to more than meet every standard test.

ALPHA PORTLAND CEMENT

The High-Water Mark of Quality

is an exceptional cement, made by a company of twenty-three years' experience whose policy has always been to manufacture the best, strongest, safest Portland Cement that can be produced.

Specify ALPHA and be SURE

Six great plants on six great trunk lines—one plant directly on the Hudson, with private docks, ideally situated for Coast, Canal and export shipment—enable us to render ALPHA Service that is on a par with the high quality of ALPHA Portland Cement.

Let us send you, free of charge, valuable literature dealing with the use of ALPHA Portland Cement, with stucco work, concrete houses, and concrete improvements generally. Ask for ALPHA Book No. 10 and ask also for special literature on the kind of concrete work that most interests you.


ALPHA PORTLAND CEMENT CO.

General Offices: **Easton, Pa.**

Sales Offices: New York, Chicago, Philadelphia, Pittsburgh, Boston, Buffalo, Baltimore and Savannah

WHEN WRITING ADVERTISERS PLEASE MENTION THE AMERICAN CARPENTER AND BUILDER

Storm-Proof Hanger



Distinctive Features

Easy running.

Anti-Friction steel-roller bearings.

Frictionless contact with rail.


Great strength and durability.

Illustrated directions packed with each pair.

The cut shows the No. 66 Rigid style.

The No. 77 has a Flexible Hinge Joint.

STORM-PROOF RAIL



TITE-FIT



Requires no brackets.

Forms a continuous bracket in itself.

Requires no housing. Fits close against the building. (See sectional view.)

Perfect tread for hanger wheels. Bird- and Storm-proof.

A detailed description will be found in our general Catalog, a copy of which will be gladly mailed on request.

NATIONAL MFG. COMPANY

STERLING, ILLINOIS